

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 16, 2016
Date of Addendum: February 5, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
018	53-1362-027	RCB CULVERT REPLACEMENT - TWIN BOX	JONES	BRFN-136-2(27)--39-53	16FEB018.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0015 2401-6750001 REMOVALS, AS PER PLAN; 1.000 LS

If the above changes are not made, they will be made as shown here.

Make the following changes to the PLAN ATTACHMENT SHEETS:

Replace SHEET 2 with the attached SHEET 2.

ESTIMATED CULVERT QUANTITIES

ITEM NO.	ITEM CODE	ITEM	UNIT	TOTAL	AS BUILT QUAN.
1	2102-0425071	SPECIAL BACKFILL	CY	820.0	
2	2401-6150005	REMOVALS, AS PER PLAN	LS	1.00	
3	2402-9720026	EXCAVATION, EXISTING BRIDGE	LS	1.00	
4	2402-9720026	EXCAVATION, EXISTING BRIDGE	LS	1.00	
5	2403-0100020	STRUCTURAL CONCRETE (RGB CULVERT)	CY	1,332.0	
6	2404-7715000	REINFORCING STEEL	LB	52,874	
7	2533-4980005	MOBILIZATION	LS	1.00	
8	2599-9999014	EROSION CONTROL SYSTEM	SF	3,773	

ESTIMATE REFERENCE INFORMATION

ITEM NO.	ITEM CODE	DESCRIPTION
1	2102-0425071	SPECIAL BACKFILL RECLAIMED ASPHALT PAVEMENT (RAP) AND RECLAIMED HMA SHALL NOT BE USED FOR THE SPECIAL BACKFILL.
2	2401-6150001	REMOVALS, AS PER PLAN REMOVE EXISTING CONCRETE RAILROAD ABUTMENTS TO ONE FOOT BELOW FINISHED GRADE ELEVATION.
3	2401-6145625	REMOVAL OF EXISTING BRIDGE
4	2402-2720000	EXCAVATION, CLASS 20 INCLUDES 820 CY OF EXCAVATION FOR CORE-OUT.
5	2403-0100020	STRUCTURAL CONCRETE (RGB CULVERT)
6	2404-7715000	REINFORCING STEEL
7	2533-4980005	MOBILIZATION
8	2599-9999014	EROSION CONTROL SYSTEM

DESIGN FOR 15° SKEW (L.A.)
**TWIN 12' X 9' X 82' REINFORCED
 CONCRETE BOX CULVERT**

QUANTITIES

STA. 87+23.29
 JONES COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 1 OF 8 FILE NO. 31061
 DECEMBER, 2015

NOTE: ROADWAY QUANTITIES SHOWN ELSEWHERE IN THESE PLANS.

JONES COUNTY PROJECT NUMBER BRN-136-2027J-39-53 SHEET NUMBER 2

CHANGED BY ADDENDA