A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 17, 2016
Date of Addendum: May 12, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
306	75-C075-144	GRADING	PLYMOUTH	FM-C075(144)--55-75	17MAY306.A02

Make the following changes to the PLAN:

ADD the attached CLEARING & GRUBBING TAB to the plan:

Line No.: _____

Item Code: 2101-0850002 Page No: _____

Description: Clearing & Grubbing Category No.: _____

Project No.: FM-75 (119) (144) Contract ID: _____

Location: 64+74 - 70+00 Date: 12-7-15 By: Malcm. Arnie M.

Size		Units	Count	Total
3" - 6"	Clearing & Down Timber	0.5		
	Grubbing	1.1		
	Clearing & Grubbing	1.6	11	3.200
6" - 9"	Clearing & Down Timber	1.1		
	Grubbing	2.8		
	Clearing & Grubbing	3.9	1	3.900
9" - 12"	Clearing & Down Timber	1.9		
	Grubbing	4.8		
	Clearing & Grubbing	6.7	1	6.700
12" - 15"	Clearing & Down Timber	2.8		
	Grubbing	6.6		
	Clearing & Grubbing	9.4	HH HH HH HH 11	206.800
15" - 18"	Clearing & Down Timber	4.7		
	Grubbing	8.8		
	Clearing & Grubbing	13.5		
18" - 24"	Clearing & Down Timber	8.4		
	Grubbing	13.6		
	Clearing & Grubbing	22.0		
24" - 30"	Clearing & Down Timber	11.4	1	11.400
	Grubbing	17.6		
	Clearing & Grubbing	29.0		
30" - 36"	Clearing & Down Timber	22.0		
	Grubbing	28.0	1	28.000
	Clearing & Grubbing	50.0		
36" - 42"	Clearing & Down Timber	30.0		
	Grubbing	50.0		
	Clearing & Grubbing	80.0		
42" - 48"	Clearing & Down Timber	40.0		
	Grubbing	80.0		
	Clearing & Grubbing	120.0		
48" - 60"	Clearing & Down Timber	60.0		
	Grubbing	100.0		
	Clearing & Grubbing	160.0		
60" - 72"	Clearing & Down Timber	80.0		
	Grubbing	120.0		
	Clearing & Grubbing	200.0		
>72"	Clearing & Down Timber	120.0		
	Grubbing	160.0		
	Clearing & Grubbing	280.0		
Hedge Removal	Per 100 Linear Ft.	30.0	80' + 63'	42.900
Brush Removal	Per 100 Square Ft.	0.8		
Growing Corn	Per 100 Square Ft.	0.2		
Fence Removal	Per Station	6.0		

8 ornamental Bushes 24"

Contractor: _____ Sheet Grand Total: ~~302.900~~

Checked By: _____ Article of Measurement: 2101.03A

Audited By: _____ Article of Payment: 2101.04A

Folder Path: z:\forms\contract items
File: clearing & grubbing-e103.xls

Rev 1/97

Form E103

Line No.: _____

Item Code: 2101-0850002

Page No: _____

Description: Clearing & Grubbing

Category No.: _____

Project No.: FM-75(~~118~~) (144)

Contract ID: _____

Location: 43+00 - 46+00

Date: 12-7-15 By: Mark M. Armie M.

Size		Units	Count	Total
3" - 6"	Clearing & Down Timber	0.5		
	Grubbing	1.1		
	Clearing & Grubbing	1.6	11	3.200
6" - 9"	Clearing & Down Timber	1.1		
	Grubbing	2.8		
	Clearing & Grubbing	3.9		
9" - 12"	Clearing & Down Timber	1.9	1	1.900
	Grubbing	4.8		
	Clearing & Grubbing	6.7		
12" - 15"	Clearing & Down Timber	2.8		
	Grubbing	6.6		
	Clearing & Grubbing	9.4		
15" - 18"	Clearing & Down Timber	4.7		
	Grubbing	8.8		
	Clearing & Grubbing	13.5		
18" - 24"	Clearing & Down Timber	8.4		
	Grubbing	13.6	11	27.200
	Clearing & Grubbing	22.0	11	44.000
24" - 30"	Clearing & Down Timber	11.4		
	Grubbing	17.6	1	17.600
	Clearing & Grubbing	29.0	111	87.000
30" - 36"	Clearing & Down Timber	22.0		
	Grubbing	28.0	1	28.000
	Clearing & Grubbing	50.0	11	100.000
36" - 42"	Clearing & Down Timber	30.0		
	Grubbing	50.0		
	Clearing & Grubbing	80.0	1	80.000
42" - 48"	Clearing & Down Timber	40.0		
	Grubbing	80.0		
	Clearing & Grubbing	120.0		
48" - 60"	Clearing & Down Timber	60.0		
	Grubbing	100.0		
	Clearing & Grubbing	160.0		
60" - 72"	Clearing & Down Timber	80.0		
	Grubbing	120.0		
	Clearing & Grubbing	200.0		
>72"	Clearing & Down Timber	120.0		
	Grubbing	160.0		
	Clearing & Grubbing	280.0		
Hedge Removal	Per 100 Linear Ft.	30.0		
Brush Removal	Per 100 Square Ft.	0.8		
Growing Corn	Per 100 Square Ft.	0.2		
Fence Removal	Per Station	6.0		

Contractor: _____ Sheet Grand Total: 388.900

Checked By: dm

Article of Measurement: 2101.03A

Audited By: _____

Article of Payment: 2101.04A

Folder Path: z:\forms\contract items
File: clearing & grubbing-e103.xls

Line No.: _____

Item Code: 2101-0850002 **Page No:** _____

Description: Clearing & Grubbing **Category No.:** _____

Project No.: FM-75 (~~777~~) (144 **Contract ID:** _____

Location: 158+00 - 180+00 **Date:** 12-7-15 By: Mark M. Annie M.

Size		Units	Count	Total
3" - 6"	Clearing & Down Timber	0.5		
	Grubbing	1.1		
	Clearing & Grubbing	1.6	III	4.800
6" - 9"	Clearing & Down Timber	1.1		
	Grubbing	2.8		
	Clearing & Grubbing	3.9	II	7.800
9" - 12"	Clearing & Down Timber	1.9		
	Grubbing	4.8	II	9.600
	Clearing & Grubbing	6.7	IIII	26.800
12" - 15"	Clearing & Down Timber	2.8	I	2.800
	Grubbing	6.6		
	Clearing & Grubbing	9.4	I	9.400
15" - 18"	Clearing & Down Timber	4.7		
	Grubbing	8.8		
	Clearing & Grubbing	13.5	II	27.000
18" - 24"	Clearing & Down Timber	8.4		
	Grubbing	13.6		
	Clearing & Grubbing	22.0		
24" - 30"	Clearing & Down Timber	11.4		
	Grubbing	17.6	I	17.600
	Clearing & Grubbing	29.0		
30" - 36"	Clearing & Down Timber	22.0		
	Grubbing	28.0	I	28.000
	Clearing & Grubbing	50.0	I	50.000
36" - 42"	Clearing & Down Timber	30.0		
	Grubbing	50.0		
	Clearing & Grubbing	80.0		
42" - 48"	Clearing & Down Timber	40.0		
	Grubbing	80.0		
	Clearing & Grubbing	120.0		
48" - 60"	Clearing & Down Timber	60.0	I	60.000
	Grubbing	100.0	I	100.000
	Clearing & Grubbing	160.0		
60" - 72"	Clearing & Down Timber	80.0		
	Grubbing	120.0		
	Clearing & Grubbing	200.0		
>72"	Clearing & Down Timber	120.0		
	Grubbing	160.0		
	Clearing & Grubbing	280.0		
Hedge Removal	Per 100 Linear Ft.	30.0		
Brush Removal	Per 100 Square Ft.	0.8	III (300 sq Feet)	2.40
Growing Corn	Per 100 Square Ft.	0.2		
Fence Removal	Per Station	6.0		

10 - ornimental, 21" Tall
5 - ornimental, 48" Tall
Evergreen

Contractor: _____ Sheet Grand Total: ~~346.200~~

Checked By: _____ **Article of Measurement:** 2101.03A

Audited By: _____ **Article of Payment:** 2101.04A

Folder Path: z:\forms\contract items
File: clearing & grubbing-e103.xls