

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: October 18, 2016
Date of Addendum: October 6, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
152	77-1417-042	HMA PAVEMENT - GRADE AND NEW	POLK	NHSX-141-7(42)--3H-77 NHSX-141-7(47)--3H-77 NHSX-141-7(48)--3H-77 NHSX-141-7(49)--3H-77	18OCT152A02

Add the following to the PROPOSAL SPECIAL PROVISIONS TEXT and LIST:

720.121 ATTACHMENT OF "POINT 25 UTILITY DATA"

*** POINT 25 Utility Data ***

This Estimating Proposal has an attachment of the "POINT 25 Utility Data". This attachment is a part of the proposal form.

Add the attached Utility Bid Attachment Sheet to the Proposal

Make the following change to NHSX-141-7(42)--3H-77 plan:

Add the following note to C.3, ESTIMATE REFERENCE INFORMATION, Item 65;

This item includes all construction survey necessary for all the other projects on this contract.



UTILITY BID ATTACHMENT

County:

Polk

Project Classification:

Point 25

Project No.:

NHSN-141-7(43)--2R-77 (ROW)

NHSX-141-7(42)--3H-77 (CONST)

District Utility Coordinator:

Jerry Lavine

Iowa Department of Transportation

District Utility Coordinator

Highway Route Number or Name:

IA 141

2300 SE 17th Street

Grimes, IA 50111-6612

Segment or Section:

IA 44 to N of I-35/80

Utilities:

This project comes under the provisions of IAC 761-Chapter 115.25 Iowa Code.

Some of the utility work described below is dependent on prior work being performed by the Contractor at a specific site. In such situations the Contractor shall provide the Engineer and the affected utility a good faith notice of when the utility is to start work at the site. The notice shall be given 14 calendar days in advance of when the Contractor expects to complete the prior work and the site will be available to the utility. The Contractor shall follow up with a confirmation notice to the Engineer and the utility not less than 3 working days before the site will be ready for the utility to begin its' work.

Additional detailed information regarding the location of relocated utility facilities is available on the permits issued to the utility companies. These permits can be viewed at the District office during normal working hours. Contact the District Utility Coordinator at 515-986-5476.

Facilities- Affected:

Aureon Network Services (Local Fiber Optic):

Relocation work will start or was started 6/15/2016.

Relocation work was completed or will be completed 7/15/2016.

Fiber Optic line was relocated. Work was completed on 7/15/2016

Contact Jeff Klocko 515-830-0445

Black Hills Energy (Gas):

Relocation work will start or was started 5/18/2016.

Relocation work was completed or will be completed 6/15/2016.

Black Hills relocated their gas that was in conflict. They moved their line from the west side of Iowa 141 to the east side of Iowa 141. Work was completed on June 15th.

Contact Joe McAeavy 515-343-2030

City of Grimes (Sanitary Sewer):

Relocation work will start or was started 11/28/2016.

Relocation work was completed or will be completed 4/28/2017.

City of Grimes will be relocating their current sanitary sewer and abandoning the existing line at 79+41 and 105+27. The new sanitary line will be installed at 101+00 to 126+50.

Contact John Gade at 515/233-0000

City of Grimes (Water):

Relocation work will start or was started 11/28/2016.

Relocation work was completed or will be completed 4/28/2017.

City of Grimes will be relocating their existing water line with a new line. The existing water line will abandon between 79+32 to 105+79. The new line will be installed on SE Gateway Drive.

Contact John Gate at 515/233-0000

Iowa Communications Network (Local Fiber Optic):

Relocation work will start or was started 9/20/2016.

Relocation work was completed or will be completed 11/23/2016.

ICN/DOT needs to relocate their fiber optic lines. They have this work scheduled for this fall.

Contact Tony Taylor 515/239-1902

Facilities- Not Affected:

Consolidated Communications (Telephone):

Consolidated Communications has no facilities within the project limits. Contact Weston Grow 515-867-4769

MCI / Verizon Business (Long Distance Fiber Optic):

MCI Verizon has no conflicts on this project.

Contact Dean Boyers 972-729-6322

Mediacom (Cable TV):

Mediacom has two transverse crossings at station 105+00 and 80+00. They will findout the depth of the two lines and if they need to be lowered they will start relocation work on October 15th and finish work on November 1st.

Contact Paul May 515/246-2252

Windstream Communications of Iowa (Local Fiber Optic) :

Windstream does not have any facilities within the project limits. Contact Jim Wiand 641-787-2270

Facilities- Unknown:

Century Link (formerly Qwest) (Telephone) :

The DOT has been waiting on CenturyLink since last spring to provide a work plan that addresses their relocation work on the above project. As of 9/13/2016 we are currently working with CenturyLink to resolve any relocation issues. We are hopeful to have the work plan approved soon and they can start their relocation work this fall.

Contact Steve Parker 515/265-0968

MidAmerican Energy Company (Electric Distribution) :

MidAm removed 2 poles in conflict at station 61+00 east side and placed a bore at SE 37th

Contact Michael Younts 515/252-6565

-- END --