

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: October 18, 2016  
Date of Addendum: October 12, 2016

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
101	06-0214-027	PCC OVERLAY – UNBONDED	BENTON	STPN-021-4(27)--2J-06	18OCT101A03

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0040 2121-7425020 GRANULAR SHOULDERS, TYPE B:

From: 7,400.000 TON

To: 5,659.000 TON

If the above changes are not made, they will be made as shown here.

Make the following changes to the PLAN, Sheet Number C.2:

Change the ESTIMATE REFERENCE INFORMATION for item 4 2121-7425020 Granular Shoulders, Type B to read:

See typical 7135 for location details.

Quantity reduced by: 1347 cu. yds. for available mainline shoulder class 13 excavation material and 282 cu. yds. for available side road fillet extension work with the remainder increased by 20% for irregularities.

NOTE: The above class 13 material is assumed to weigh 140 pounds per cubic foot.

7795 tons (from tab. 7135) – 2546 tons – 533 tons (from Typ. PCC-1 & Detail sheet B.4 using 140#/cf)= 4716 x 1.2= 5659 tons