

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: March 21, 2017  
Date of Addendum: March 10, 2017

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
016	78-C078-190	BRIDGE AND APPROACHES - STEEL GIRDER	POTTAWATTAMIE	BROS-C078(190)--5F-78	21MAR016A02

Make the following change to the PLAN Sheet 4:

Replace Traffic Control Plan Tab with attached Traffic Control Plan Tab:

TRAFFIC CONTROL PLAN	
<p>TWO LANES OF TRAFFIC WILL BE MAINTAINED ON THE CURRENT ROADWAY ALIGNMENT THROUGH OCTOBER 31ST, 2017.</p> <p>TRAFFIC CONTROL DURING THIS PERIOD WILL BE ACCORDING TO IDOT STANDARD ROAD PLAN TC-273.</p> <p>THE ROADWAY WILL BE CLOSED TO TRAFFIC DURING CONSTRUCTION.</p> <p>TRAFFIC CONTROL DURING THIS PERIOD WILL BE ACCORDING TO IDOT STANDARD ROAD PLAN TC-252.</p> <p>TRAFFIC TO ADJACENT PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS.</p> <p>DURING THE ROAD CLOSURE, A DETOUR ROUTE WILL BE MARKED AND MAINTAINED BY THE CONTRACTOR. SEE SHEET 7.</p> <p>ALL SAFETY CLOSURES FOR THIS PROJECT SHALL BE FURNISHED, ERECTED, MAINTAINED AND REMOVED BY THE CONTRACTOR. THESE CLOSURES SHALL BE IN ACCORDANCE WITH IDOT STANDARD ROAD PLAN TC-252. GUARDRAIL INSTALLATION MUST BE COMPLETE BEFORE THE ROAD IS OPENED TO TRAFFIC.</p>	

108-23A  
08-01-08