

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 21, 2017
Date of Addendum: March 16, 2017

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
023	42-3720-610	Bridge New - Other	Hardin	STP-E-3720(610)--8V-42	21MAR023A02

This Addendum supersedes the March 9, 2017 Addendum 21MAR023A01.

Make the following changes to the PLAN:

In the "Boardwalk Notes" section on Sheet Number 2 of the plans, replace "ALL BOARDWALK DIMENSION LUMBER AND TIMBERS SHALL BE CCA PRESSURE TREATED NO. 2 OR BETTER SOUTHERN PINE (SP)" with "ALL BOARDWALK DIMENSION LUMBER AND TIMBERS SHALL BE NO. 2 OR BETTER SOUTHERN PINE (SP) PRESSURE TREATED WITH ALKALINE COPPER QUATERNARY (ACQ) TO A 0.4 PCF RETENTION OR TO REFUSAL OR MICRONIZED COPPER AZOLE (MCA) TO A 0.24 PCF RETENTION OR TO REFUSAL".

In the "Pre-Engineered Steel Truss Recreational Trail Bridge Notes" section on Sheet Number 3 of the plans, replace "a) MATERIAL: CCA PRESSURE TREATED DOUGLAS FIR OR SOUTHERN PINE (NO. 2 OR BETTER) WOOD PLANKS AND BE AIR DRIED TO 15% - 20% MOISTURE CONTENT." with "a) MATERIAL: ALKALINE COPPER QUATERNARY (ACQ) PRESSURE TREATED (TO A 0.4 PCF RETENTION OR TO REFUSAL) OR MICRONIZED COPPER AZOLE (MCA) PRESSURE TREATED (TO A 0.24 PCF RETENTION OR TO REFUSAL) DOUGLAS FIR OR SOUTHERN PINE (NO. 2 OR BETTER) WOOD PLANKS AND BE AIR DRIED TO 15% - 20% MOISTURE CONTENT."