

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 21, 2017
Date of Addendum: March 16, 2017

| B.O. | Proposal ID | Proposal Work Type | County | Project Number | Addendum |
|-------------|--------------------|---------------------------|---------------|------------------------|-----------------|
| 601 | 70-0929-144 | Bridge Painting | Muscatine | BRFN-092-9(144)--39-70 | 21MAR601A01 |

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0065 2528-8400256; 1.000 EACH

If the above changes are not made, they will be made as shown here.

Please add the FRA number for the project as follows:
FRA # 607203K

Please replace SHEET 2 of the attaceh601 with the attached SHEET 2

| ESTIMATE REFERENCE INFORMATION | |
|--|---|
| Data listed below is for informational purposes only and shall not constitute a basis for any extra work orders. | |
| ITEM NO. | DESCRIPTION |
| | <p>All steel to be painted shall be blasted to SP-10. The paint system shall be the Epoxy system. This includes a Zinc-rich Epoxy, an Aluminum Epoxy Mastic intermediate coat, and an Aliphatic Polyurethane topcoat.</p> <p>BRIDGE # 7075.7S092</p> <p>This bridge is to be painted. All structural steel is to be painted in the truss section of the bridge. In the girder spans, painting includes the bottom of the top flange, the exterior of the exterior girder, the exterior top of the bottom flange, the exterior of the bottom flange, and the bottom of the bottom flange of the Exterior Girders. Also, paint all steel within 15' of the abutments and joints. Top color shall be Federal ID # 16495.</p> <p>The total area of structural steel in the zones designated to be painted is estimated to be 182,000 sq. ft. This estimate is given only for the contractor's information. There will be no additional payment if the actual areas in the zones vary from the estimated amounts shown. The contractor may obtain a copy of the original construction plans for the bridge from the Office of Contracts, Iowa Department of Transportation, 800 Lincoln Way, Ames, IA 50010 (Phone: 515-239-1414).</p> <p>Contractor shall use extreme caution in the area of the lights. Lights shall be protected at all times. Contractor shall inform the State of Iowa 2 weeks ahead of scheduling work so that electricity can be scheduled to be disconnected.</p> <p>Contractor shall clean the drains and joints. All built up material shall be removed prior to washing. This work will be considered incidental to Bridge Cleaning for Painting.</p> <p>NOTE: Abrasives shall be steel shot and/or grit, aluminum oxide, or garnet abrasives. Do not use sand or coal slag.</p> |