

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: June 20, 2017  
Date of Addendum: May 22, 2017

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
011	78-0293-069	BRIDGE REPLACEMENT - STEEL GIRDER	POTTAWATTAMIE	IM-NHS-029-3(69)53--03-78	20JUN011A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0861 2601-2634100 MULCHING, 2.1 ACRES

Add Proposal Line No. 0862 2601-2636043 SEEDING AND FERTILIZING, 2.1 ACRES

Add Proposal Line No. 0863 2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING, 2.1 ACRES

If the above changes are not made, they will be made as shown here.

Add Estimate Reference notes for 3 items added above:

2601-2634100 MULCHING, 2.1 ACRES

Mulching per Article 2601.03, E, 2.

Anchor mulch into the soil using anchoring equipment with a minimum of two passes.

Included for areas requiring reshaping and seedbed preparation. Mulch shall be Certified Noxious Weed Seed Free Mulch as certified by the Iowa Crop Improvement Association or adjacent states Crop Improvement Associations.

Mulch Rate: 1 ½ tons of dry cereal straw or native grass straw per acre.

2601-2636043 SEEDING AND FERTILIZING, 2.1 ACRES

Areas shall be seeded and fertilized per Article 2601.03, C, 3.

Verify locations with the Engineer prior to seeding.

2601-2642100 STABILIZING CROP - SEEDING AND FERTILIZING, 2.1 ACRES

Included for seeding disturbed areas as directed by the Engineer.

All disturbed areas shall be seeded and fertilized per Article 2601.03, C, 1.

Make the following changes to plan sheet C.3:

Remove Standard Notes 232-3A, Erosion Control (Rural Seeding)

Remove Standard Notes 232-3C, Erosion Control (Native Grass Seeding)

Remove Standard Notes 232-11, Erosion Control (Stabilizing Crop Seeding)