

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: June 20, 2017
Date of Addendum: May 31, 2017

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
103	76-C076-068	PCC OVERLAY - UNBONDED	POCAHONTAS	STP-S-C076(68)--5E-76	20JUN103A02

Make the following corrections to sheet B-2 of the plan:

The leader pointing to the reinforcing bar on the Full-Depth Transition Section typical should be: "#5 x 48" epoxy bar at 30" centers" instead of "3 x #5 x 48" epoxy bar at 30" centers"

The leader pointing to the edge of the existing pavement on the Typical Unbonded Overlay Section should be: "Provide an approximately vertical edge, free of dust and debris. The method should not expose the top surface of the underlying PCC pavement. Incidental to Class 13 Excavation."