MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 01-0022-604

Proposed Contract Period: Late Start Date of 05/21/18 with 100 WORK DAYS

Project(s):

Project No: BHM-0022(604)--8K-01

County: ADAIR

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT Route: 5TH STREET Length: 0.00 miles

Location: IN THE CITY OF ADAIR, ON 5TH STREET, OVER IAIS RR

Quantity/Unit Item No. Item Description ______ SECTION NO. 0001 REPAIRS TO A 203'-3 X 24'-6 CONCRETE ARCH VIADUCT 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 247 CY 87,509 LB SECTION NO. 0002 ROADWAY ITEMS 2122-5190007 PAVED SHLD, PCC, 7" 43 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 03-C003-061

Proposed Contract Period: Late Start Date of 07/09/18 with 75 WORK DAYS

Project(s):

Project No: FM-C003(61)--55-03

County: ALLAMAKEE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: MAYS PRAIRIE ROAD Length: 0.00 miles
Location: ON MAYS PRAIRIE ROAD, OVER FRENCH CREEK, BRIDGE # 11Q1

_			
	Item No.	Item Description	Quantity/Unit
-	SECTION	NO. 0001 OADWAY ITEMS	
	=-	EXCAVATION, CL 10, RDWY+BORROW	250 CY
		STRUCT CONC (BRIDGE)	392 CY
		REINFORC STEEL, EPOXY COATED	84,663 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 15-C015-062

Proposed Contract Period: Late Start Date of 08/13/18 with 55 WORK DAYS

Project(s):

Project No: BROS-C015(62)--5F-15

County: CASS

Type of Work: BRIDGE REPLACEMENT - CCS

Route: TUCSON ROAD Length: 0.00 miles Location: ON TUCSON RD, FROM 690TH STREET WEST 1/4 MILES

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 1000'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 800 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 227 CY

 2404-7775000
 REINFORC STEEL
 3,116 LB

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 56,159 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 25-5970-615-A

Proposed Contract Period: Late Start Date of 04/02/18 with 50 WORK DAYS

Project(s):

Project No: BRM-5970(615)--8N-25

County: DALLAS

Type of Work: STRUCTURES (MISCELLANEOUS)

Route: WILLIS AVE Length: 0.00 miles

Location: IN THE CITY OF PERRY, WILLIS AVENUE BRIDGE OVER FROG CREEK

(BRIDGE # 503845)

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10"

620 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 26-C026-090

Proposed Contract Period: Late Start Date of 07/23/18 with 85 WORK DAYS

Project(s):

Project No: BROS-C026(90)--5F-26

County: DAVIS

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: ROBIN BLVD Length: 0.10 miles Location: ON ROBIN BLVD, 0.4 MILES WEST OF REDWOOD AVE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 150'-0 X 24'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

 2102-2625000
 EMBANKMENT-IN-PLACE
 776 CY

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 2,230 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 205 CY

 2404-7775000
 REINFORC STEEL
 47,564 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 69-3052-601-A

Proposed Contract Period: Late Start Date of 06/04/18 with 110 WORK DAYS

Project(s):

Project No: BROS-3052(601)--5F-69

County: MONTGOMERY

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: U AVE Length: 0.10 miles

Location: SO. EDGE GRANT: OVER WEST NODAWAY

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 213'-10 X 30'-6 PRETENSIONED PRESTRESSED

CONCRETE BEAM BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 2,639 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 451 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 96,590 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 16-C016-104

Proposed Contract Period: Late Start Date of 06/04/18 with 40 WORK DAYS

Project(s):

Project No: FM-C016(104)--55-16

County: CEDAR

Type of Work: PCC OVERLAY - UNBONDED

Route: F44 Length: 3.43 miles

Location: F44: FROM WEST BRANCH TO FRANKLIN AVENUE - SPRINGDALE

Item No.	Item Description	Quantity/Unit
	NO. 0001 ROADWAY ITEMS	
2303-1031500	EXCAVATION, CL 13, RDWY+BORROW STD/S-F PCC PAV'T, CL C CL 3, 8" HMA ST BASE, 1/2"	1,138 CY 455 CY 4,928 SY 126 TON
2310-5151040 2310-5151551	PCC OVERLAY, FURN ONLY PCC OVERLAY PLACE ONLY (WHITE TOPPING)	8,259 CY 43,122 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 62-7860-601

Proposed Contract Period: Late Start Date of 05/07/18 with 95 WORK DAYS

Project(s):

Project No: STP-U-7860(601)--70-62

County: MAHASKA

Type of Work: PCC PAVEMENT - REPLACE

Route: BURLINGTON ROAD Length: 0.90 miles

Location: ON BURLINGTON RD, FROM SOUTH 17TH STREET TO UNIVERSITY PARK'

S EAST CITY LIMIT LINE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 4,441 CY 2301-1033070 STD/S-F PCC PAV'T, CL C CL 3, 7" 12,930 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 87-4305-601

Proposed Contract Period: Late Start Date of 04/16/18 with 30 WORK DAYS

Project(s):

Project No: TAP-R-4305(601)--8T-87

County: TAYLOR

Type of Work: PCC SIDEWALK/TRAIL

Route: IOWA STREET Length: 0.88 miles

Location: IN THE CITY OF LENOX, TRAIL ALONG IOWA ST, LOCUST STREET, 12

16 SY

OTH STREET - LOOP AROUND LENOX COMMUNITY SCHOOL

Item No. Item Description Quantity/Unit ------SECTION NO. 0001 TRAIL ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 425 CY 4,044 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 03-0511-017

Proposed Contract Period: Late Start Date of 06/25/18 with 75 WORK DAYS

Project(s):

Project No: HSIPX-051-1(17)--3L-03

County: ALLAMAKEE

Type of Work: HMA PAVED SHOULDER - NEW

Route: IOWA 51 Length: 0.00 miles

Location: 3 MI N OF POSTVILLE TO IA 9

Project No: HSIPX-063-9(25)--3L-45

County: HOWARD

Type of Work: HMA PAVED SHOULDER - NEW
Route: U.S. 63 Length
Location: IA 9 TO THE MN STATE LINE

Length: 0.00 miles

Item Description ______

SECTION NO. 0001

ROADWAY ITEMS

HSIPX-051-1(17)--3L-03

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 35 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 2 EACH

SECTION NO. 0002

ROADWAY ITEMS

HSIPX 063-9(25)--3L-45

2102-2625000 EMBANKMENT-IN-PLACE 9 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 54-C054-110

Proposed Contract Period: Late Start Date of 08/20/18 with 45 WORK DAYS

Project(s):

Project No: STP-S-C054(110)--5E-54

County: KEOKUK

Type of Work: HMA RESURFACING

Route: W15 Length: 6.34 miles

Location: ON W15 FROM HIGHWAY 92 SOUTH TO 500 FEET SOUTH OF 277TH STRE

ET AND G38 FROM W15 EAST TO THE WASHINGTON COUNTY LINE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

COUNTY ROAD W15

2303-1032500 HMA ST INTERMEDIATE, 1/2" 10,059 TON 2303-1033500 HMA ST SURF, 1/2", NO FRIC 10,077 TON 2303-1131500 HMA ST BASE, 1/2" 34,919 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 62-C062-088-A

Proposed Contract Period: Late Start Date of 08/06/18 with 30 WORK DAYS

Project(s):

Project No: STP-S-C062(88)--5E-62

County: MAHASKA

Type of Work: HMA RESURFACING

Route: G5T Length: 2.16 miles

Location: ON G5T/T33, FROM SO. SKUNK RIVER NE 1.76 MI TO PEORIA CHESTN

UT ST; AND G5T FROM T33 E 0.30 MI

 Item No.
 Item Description
 Quantity/Unit

 SECTION NO. 0001

 ROADWAY ITEMS

 2303-0001000
 HMA WEDGE/LEVEL/STRENGTH
 1,969 TON

 2303-1031500
 HMA ST BASE, 1/2"
 2,964 TON

 2303-1032500
 HMA ST INTERMEDIATE, 1/2"
 3,164 TON

 2303-1033502
 HMA ST SURF, 1/2", FRIC L-2
 2,964 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 27-0695-706

Proposed Contract Period: Late Start Date of 04/30/18 with 45 WORK DAYS

Project(s):

Project No: MP-069-5(706)0--76-27

County: DECATUR

Type of Work: PCC PATCHING

Route: U.S. 69 Length: 39.97 miles

Location: FROM THE MISSOURI LINE, NORTH TO U.S 34. IN OSCEOLA

Project No: MP-065-5(705)13--76-93

County: WAYNE

Type of Work: PCC PATCHING
Route: U.S. 65 Length: 9.53 m
Location: FROM IOWA 2, NORTH TO LUCAS CO. LINE. Length: 9.53 miles

Item Description ______

SECTION NO. 0001

ROADWAY ITEMS -DIVISION 2 - URBAN

DECATUR COUNTY MP-069-5(706)0--76-27

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2,882 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 346 EACH

SECTION NO. 0002

ROADWAY ITEMS -DIVISION 2 - URBAN

WAYNE COUNTY MP-065-5(705)13--76-93

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 1,447 SY 172 EACH 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 29-0345-704

Proposed Contract Period: Late Start Date of 09/11/17 with 20 WORK DAYS

Project(s):

Project No: MP-034-5(704)259--76-29

County: DES MOINES

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 34 Length: 4.87 miles

Location: FROM MT PLEASANT ST., EAST TO MAIN ST BRIDGE IN BURLINGTON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 56-0275-707

Proposed Contract Period: Late Start Date of 04/30/18 with 55 WORK DAYS

Project(s):

Project No: MP-021-5(708)0--76-54

County: KEOKUK

Type of Work: PCC PATCHING

Route: IOWA 21 Length: 13.00 miles

Location: FROM IOWA 149, NORTH TO IOWA 92.

Project No: MP-027-5(707)0--76-56

County: LEE

Type of Work: PCC PATCHING
Route: IOWA 27 Length: 82.50 miles
Location: FROM THE MISSOURI STATE LINE NORTH TO IOWA 22 (RIVERSIDE)

Project No: MP-001-5(703)0--76-89
County: VAN BUREN
Type of Work: PCC PATCHING

Route: IOWA 1 Length: 23.00 miles

Location: FROM IOWA 2, NORTH TO U.S. 34

2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT

______ Item No. Item Description Quantity/Unit ______ SECTION NO. 0001 ROADWAY ITEMS KEOKUK COUNTY MP-21-5(708)0--76-54 1,062 SY 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT) 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 143 SY 61 EACH SECTION NO. 0002 ROADWAY ITEMS LEE COUNTY MP-027-5 (707) 0--76-56 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 1,350 SY 2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT) 390 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 76 EACH SECTION NO. 0003 ROADWAY ITEMS VAN BUREN COUNTY MP-001-5(703)0--76-89 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 1,429 SY

174 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 81-0202-151

Proposed Contract Period: Late Start Date of 10/09/17 with 5 WORK DAYS

Project(s):

Project No: NHSN-020-2(151)--2R-81

County: SAC

Type of Work: PCC PATCHING

Route: U.S. 20 Length: 0.00 miles

Location: 1.7 MI E OF N14/UNION AVE (WB)

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 56 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 1 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 06-0306-244

Proposed Contract Period: Late Start Date of 09/25/17 with 20 WORK DAYS

Project(s):

Project No: NHSN-030-6(244)--2R-06

County: BENTON Type of Work: REVETMENT

Route: U.S. 30 Length: 0.00 miles

Location: MUD CREEK 0.9 MI W OF CO RD W14

Project No: NHSN-001-5(119)--2R-52

County: JOHNSON
Type of Work: REVETMENT
Route: IOWA 1 Length: 0.
Location: MILL CREEK 0.1 MI N OF CO RD F14

Length: 0.00 miles

Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 59-0142-039

Proposed Contract Period: Late Start Date of 09/25/17 with 15 WORK DAYS

Project(s):

Project No: STPN-014-2(39)--2J-59

County: LUCAS

Type of Work: SLIDE REPAIR

Route: IOWA 14 Length: 0.00 miles

Location: APPROX 0.3 MI S OF CO RD S33

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 97-0311-041

Proposed Contract Period: Late Start Date of 10/02/17 with 35 WORK DAYS

Project(s):

Project No: STPN-031-1(41)--2J-97

County: WOODBURY
Type of Work: REVETMENT

Route: IOWA 31 Length: 0.00 miles Location: LITTLE SIOUX RIVER APPROX 2.0 MI S OF ANTHON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-938

Proposed Contract Period: By individual sites. Site 01: STANDARD TIME FRAME

Late Start Date of 11/27/17 with 15 WORK DAYS

Site 02: ACCELERATED TIME FRAME

Late Start Date of 09/25/17 with 10 WORK DAYS

Project(s):

Project No: NHSN-000-S(938)--2R-00

County: STATEWIDE Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 26-C026-104

Proposed Contract Period: Approx Start Date of 09/25/17 with 15 WORK DAYS

Project(s):

Project No: HSIP-S-C026(104)--6C-26

County: DAVIS

Type of Work: PAVEMENT MARKINGS

Route: MULTIPLE ROUTES Length: 14.80 miles

Location: ON 195TH ST, 230TH ST, 276TH ST, BUNCH ROAD, ICE AVE/HUSKY T

RL & OLD HWY 2

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 451 Proposal ID: 50-0141-503

Proposed Contract Period: Late Start Date of 09/18/17 with 20 WORK DAYS

Project(s):

Project No: MB-014-1(503)65--77-50

County: JASPER

Type of Work: DEBRIS REMOVAL

Route: IOWA 14 Length: 0.00 miles Location: SOUTH SKUNK RIVER 4.6 MI SOUTH OF I-80

Project No: MB-065-1(504)98--77-50

County: JASPER
Type of Work: DEBRIS REMOVAL
Route: U.S. 65 Length: 0.00 mile.
Location: INDIAN CREEK 0.2 MI S OF IA 117/330 (NB) Length: 0.00 miles

Project No: MB-065-1(507)92--77-77 County: POLK

Type of Work: DEBRIS REMOVAL
Route: U.S. 65 Length: 0.00 miles Location: SOUTH SKUNK RIVER 1.1 MI N OF NE 94TH AVE (SB)

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 452 Proposal ID: 77-0691-502

Proposed Contract Period: Late Start Date of 09/18/17 with 20 WORK DAYS

Project(s):

Project No: MB-028-1(502)16--77-77

County: POLK

Type of Work: DEBRIS REMOVAL

Route: IOWA 28 Length: 0.00 miles

Location: IN THE CITIES OF DES MOINES & W. DES MOINES AT THE RACCOON

RIVER BRIDGE 2.6 MI N OF IA 5 (SB)

Project No: MB-069-1(502)84--77-77

County: POLK
Type of Work: DEBRIS REMOVAL
Route: U.S. 69 Length: 0.00 miles
Location: DES MOINES RIVER 1.4 MI S OF I-235 IN THE CITY OF DES MOINES

______ Item No. Item Description

Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 453 Proposal ID: 94-9261-503

Proposed Contract Period: Late Start Date of 09/25/17 with 15 WORK DAYS

Project(s):

Project No: MB-926-1(503)1--77-94

County: WEBSTER

Type of Work: DEBRIS REMOVAL

Route: IOWA 926 Length: 0.00 miles

Location: DES MOINES RIVER IN FT DODGE (SB)

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: August 15, 2017 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 82-0808-303

Proposed Contract Period: Late Start Date of 10/02/17 with 90 WORK DAYS

Project(s):

Project No: IMN-080-8(303)280--0E-82

County: SCOTT

Type of Work: LANDSCAPING

Route: I-80 Length: 0.00 miles

Location: CO RD Y30 TO 2 MI E OF CO RD Y40
