

Interstate and Primary PCC Pavement Overlays Review

**Final Report
for
MLR-23-01**

December 2023
Construction & Materials Bureau



Interstate and Primary PCC Pavement Overlays Review

Final Report
for
MLR-23-01

By

Todd D. Hanson, PE
Concrete Materials Engineer
todd.hanson@iowadot.us

Construction & Materials Bureau
Iowa Department of Transportation
Ames, Iowa 50010

December 2023

TECHNICAL REPORT DOCUMENTATION PAGE

General instructions: To add text, click inside the form field below (will appear as a blue highlighted or outlined box) and begin typing. The instructions will be replaced by the new text. If no text needs to be added, remove the form field and its instructions by clicking inside the field, then pressing the Delete key twice.

Please remove this field before completing form.

1. Report No. MLR-23-01	2. Government Accession No.	3. Recipient's Catalog No.	
4. Title and Subtitle Interstate and Primary PCC Pavement Overlays Review		5. Report Date: December 2023	
		6. Performing Organization Code	
7. Author(s) Todd Hanson, Concrete Materials Engineer, https://orcid.org/0000-0002-4832-1124		8. Performing Organization Report No. MLR-23-01	
9. Performing Organization Name and Address Iowa Department of Transportation Construction & Materials Bureau 800 Lincoln Way Ames, Iowa 50010		10. Work Unit No.	
		11. Contract or Grant No.	
12. Sponsoring Agency Name and Address Iowa Department of Transportation 800 Lincoln Way Ames, IA 50010		13. Type of Report and Period Covered	
		14. Sponsoring Agency Code	
15. Supplementary Notes			
16. Abstract Iowa has a long history of PCC pavement overlays. Several research projects were placed over the years, which led to a variety of different designs and features. The objective of this study was to perform a review of concrete overlays performance on the interstate and primary system and determine any best practices or lessons learned.			
17. Key Words PCC overlay, whitetopping, unbonded overlay, bonded overlay		18. Distribution Statement No restrictions.	
19. Security Classif. (of this report) Unclassified	20. Security Classif. (of this page) Unclassified	21. No. of Pages 220	22. Price

Form DOT F 1700.7 (8-72) Reproduction of completed page authorized

Contents

Introduction.....	6
Objectives.....	6
Concrete Overlay History.....	6
Concrete Overlay Designs.....	7
Review of Iowa County IA 21 Research Project.....	7
Review of Delaware IA 13 Overlay Research Project.....	10
Review of Sac IA 175 Unbonded Overlay Experimental Project.....	12
Review of Whitetopping Overlays.....	14
Review of Unbonded Overlays.....	19
Review of Bonded Overlays.....	25
Existing Pavement Prior to Overlay Design.....	27
Design Features of Overlays.....	27
Future Overlay Design Details.....	32
Overlay Construction.....	36
Patching Overlays.....	37
Observations and Conclusions.....	40
Recommendations.....	40
References.....	42
Acknowledgements.....	43
Appendix A – Iowa Primary Overlays Project Information.....	44
Appendix B - Primary Overlays Project Construction History and Review.....	49
Appendix C – Old Pavement Resurfacing Designs.....	198
Appendix D – Iowa County IA 21 Whitetopping Overlay Test Sections.....	212

DISCLAIMER

The contents of this report reflect the views of the author(s) and do not necessarily reflect the official views or policies of the Iowa Department of Transportation. This report does not constitute a standard, specification, or regulation.

Introduction

Iowa has a long history of PCC pavement overlays. As early as 1932, there were various PCC resurfacing projects, as it was called at the time, over brick and PCC pavement. Most of these designs included welded wire fabric on top of the existing pavement. Unfortunately, there are not any records indicating the performance of any of the projects.

Several research projects were placed over the years. The first whitetopping project was placed on the Storm Lake airport in 1971. This overlay is still in service with several areas of patched panels. In 1973, a research project¹ in Greene County kicked off the modern era of bonded and unbonded overlays. In 1994, thin bonded overlay research project with 65 test sections was placed on IA 21 in Iowa county. In 2002, an overlay and widening research project with over 100 test sections was placed on IA 13 in Delaware county.

Objectives

A recent 2017 study² by the National Concrete Pavement Technology Center at Iowa State University mainly concentrated on PCC overlays on the secondary system. Using pavement management data, the research concluded that 89% of all overlays in Iowa are good to excellent. Another 2014 study³ was conducted by the National Concrete Pavement Technology Center on performance of overlays in the United States. The objective of this study was to perform a review of concrete overlays performance on the interstate and primary system and determine any best practices or lessons learned. A map and project information can be found in Appendix A. Construction history and project reviews can be found in Appendix B.

Concrete Overlay History

Iowa has a long history of PCC pavement overlays. As early as 1932, there were various PCC resurfacing projects, as it was called at the time, over brick and PCC pavement. Most of these designs included welded wire fabric on top of the existing pavement. Unfortunately, there are not any records indicating the performance of any of the projects. In 1949, a 6-inch PCC resurfacing project on US 30 in Benton County was one of the early projects to utilize widening with the overlay. Designs on these early PCC resurfacing projects may be found in Appendix C.



Figure 1 – Benton County US 30 Bonded Overlay 1949

Concrete Overlay Designs

The Iowa DOT classifies concrete overlays in the following categories:

- Whitetopping – PCC over HMA Pavement
- Unbonded – PCC over Composite Pavement
- Bonded – PCC over PCC Pavement.

There have been multiple design features incorporated and changed over the years. A variety of joint spacing and thicknesses have also been utilized.

Review of Iowa County IA 21 Research Project

In 1994, Dr. James Cable developed a research project⁴ on IA 21 in Iowa County. This whitetopping research project included 65 different test sections with thicknesses of 2, 4, 6, and 8 inch and joint spacing of 2, 4, 6, 12, and 15 feet. Also, three different types of base preparations were used on the project, including patching and scarifying, patching only, and cold in place recycling. A few sections were placed with monofilament or fibrillated polypropylene microfibers. The test section layout may be found in Appendix D.

A two-year review in 1996 showed some distress in the 2-inch sections. Eventually, some of the 2-inch sections were patched and later overlaid with HMA in 2002, 2006, and 2009. However, a 2023 review showed that most of the 4-inch test sections and all of the 6-inch test sections were in good condition, regardless of joint spacing. Approximately, four miles of the 4-, 6-, and 8-inch PCC overlay sections are performing well, after 29 years of service.



Figure 2 – 6-inch Overlay 12 x 12 ft. Joint Spacing



Figure 3 – 8-inch overlay 12 x 15 ft. Joint Spacing




Figure 4 – 6-inch overlay 6 x 6 ft. Joint Spacing



Figure 5 – 4-inch overlay 4 x 4 ft. Joint Spacing



Figure 6 – 4-inch overlay 2 x 2 ft. Joint Spacing



Figure 7 – 4-inch Overlay 4 x 4 ft. Joint Spacing exhibiting some joint deterioration.

A possible reason why the test sections still are performing very well may be because the overlay was placed the same width as the existing pavement, without widening or tied shoulders. Another factor may be for the test sections, 4 inches or thicker test, all joints were sealed.

[Review of Delaware IA 13 Overlay Research Project](#)

In 2002, Dr. Cable developed another research project⁵ on IA 13 in Delaware County. This project was a widening and unbonded overlay of a composite pavement. The old widening units were removed and a 6 foot by 8-inch-thick widening was added to each side. There were 191 test sections of 3.5-inch and 4.5-inch overlay, varying panel size, macro fibers, microfibers, tied shoulders, and untied shoulders.

The longitudinal joint former was used to form the joint between the widening units and overlay. There were issues with cracking within a short time period, due to lack of a formed joint. This coupled with the widening unit heaving caused issues on this overlay. In areas, the widening units are inversely sloped toward the outside wheel path making it difficult to remove snow.



Figure 8 – Delaware IA 13 Unbonded Overlay Construction



Figure 9 – Delaware IA 13 Widening Unit Heaving

Review of Sac IA 175 Unbonded Overlay Experimental Project

Another experimental overlay was placed on IA 175 in Sac County in 2007. This project was a 4.5 inch unbonded overlay with 2 feet by 8-inch-thick widening on each side. The existing pavement had 2-foot HMA widening on each side in the 1980s. Engineering fabric was used over the HMA widening units and no visible cracking was observed in the pavement prior to the PCC overlay. No reinforcing steel was used to tie the widening units to the overlay.

Cracking occurred in the outside wheel paths in less than two years. It was assumed that the old HMA widening unit was heaving causing the cracking. However, it was later discovered that the outside widening unit was heaving that cause the cracking. This problem led to the use of the 60-inch reinforcing steel bar across the old widening and tied to the new widening.

The district sealed all the cracking and there has not been a lot of patching required. Even with all the cracking, the overlay still rides fairly well at the time of this report.



Figure 10 – Sac IA 175 UBOL Left Shoulder Crossslope 1.66%



Figure 11 – Sac IA 175 UBOL Left Shoulder Crossslope 1.13%



Figure 12 – Sac IA 175 UBOL Left Shoulder Crossslope 1.13%

Review of Whitetopping Overlays

Review of the Iowa County IA 21 whitetopping overlay showed how well some of the test sections are performing after 29 years.

Another whitetopping project that has been in service for more than 40 years is the Adair County I-80 westbound overlay, in 1979. The design was to mill 8 inches of HMA and replace with 10 inches of PCC. Overall, the overlay is in good condition with a few patched areas. The pavement was diamond ground in 2020.



Figure 13 – Adair I-80 WB Whitetopping Overlay Paved 1979 (Picture 2023)

Review of other whitetopping overlays include Montgomery US 71 and Cass US 71 projects. Built in 2006 and 2007, respectively, both 8-inch overlays are in very good condition. The Montgomery County whitetopping has HMA shoulders and the Cass County whitetopping has tied PCC shoulders.




Figure 14 – Montgomery County US 71 Built 2006 (Picture 2023)



Figure 15 – Cass US 71 Built 2007 (Picture 2023)

One project to note that includes both whitetopping and unbonded overlay sections is on US 71 in the Clay/Dickinson counties. It is interesting to note that the whitetopping areas of the overlay are performing well, while areas of the unbonded overlay are experiencing longitudinal cracking and panel movement. The sections of whitetopping overlay used a 36-inch tie bar, while the sections of unbonded overlay have a 6-foot #5 reinforcing tie steel.



Figure 16 – Clay/Dickinson US 71 Whitetopping Overlay Built 2012 (Picture 2023)



Figure 17 – Clay/Dickinson US 71 Unbonded Overlay Built 2012 (Picture 2023)



Figure 18 – Clay US 71 Whitetopping Built 2015



Figure 19 – Clay US 71 Whitetopping Built 2016

Review of Unbonded Overlays

Many of the unbonded overlays have been placed over old 1920s and 1930s pavements that were built 18 to 20 foot wide and were widened and resurfaced in the 1950s. After the early cracking found on the Sac IA 175 overlay, it was decided to staple a 60-inch reinforcing bar across the old widening unit into the new widening/shoulder. With the exception of the US 71 Clay unbonded overlays placed in 2015 and 2016, nearly all of the unbonded overlays exhibit some type of longitudinal cracking and/or panel movement in the interior slabs.

Many of the unbonded overlays placed between 2002 and 2014 were thin at 5 inches or less. Also, between 2004 and 2014, all joints were left after sawing without any joint filler material. This likely caused issues with joint infilling, which led to problems with panels moving.




Figure 20 – Osceola IA 9 panel movement



Figure 21 – Grundy IA 14 Longitudinal Cracking and Shattered Panels

A thicker overlay did not seem to prevent the cracking with the longer reinforcing tie steel. On the Dallas US 169 unbonded overlay, this 7 inch unbonded overlay with 12 x 12-foot panels and tied shoulders with a 60-inch reinforcing bar exhibits quite a bit of longitudinal cracking. Most of the cracks have been sealed and there is very little patching. The cracking does not seem to affect the ride of the pavement, currently. The as constructed shoulder cross slope was 2 percent. Checking shoulder cross slope near the areas with longitudinal cracking indicated shoulder cross slope anywhere from 0.9% to 1.48%. Thus, the shoulders appear to heave, causing cracking off the end of the 60-inch reinforcing steel.



Figure 22 – Dallas US 169 UBOL Longitudinal Cracking



Figure 23 – Dallas US 169 UBOL Shoulder Cross Slope 1.40%

However, on the Clay US 71 overlays placed in 2015 and 2016, which include both whitetopping and unbonded overlays, both overlay types are in very good condition. As noted earlier, the unbonded overlay placed on Clay/Dickinson US 71 had a few areas of longitudinal cracking. The main difference between the 2012 overlay and the newer overlays was the joint spacing. The 2012 unbonded overlay has 6 x 6-foot panels, with a 6-foot #5 reinforcing steel over the old widening into the tied 4 x 6-foot shoulder. While the 2015 and 2016 overlays have 8 x 9-foot panels with a 6-foot #5 reinforcing steel across the old widening into the 8 x 7-foot shoulder. This design places the sawed joint directly over the old 18-foot original pavement edge.





Figure 24 – Clay/Dickinson US 71 2012 UBOL typical



Notes:

Figure 25 – Clay US 71 2015-16 UBOL typical



Figure 26 – Clay US 71 2015 UBOL



Figure 27 – Clay US 71 2016 UBOL

The 9 inch unbonded overlays in Fremont and Mills counties placed in 2009 are both performing very good. There are no patches or longitudinal cracking noted during a review in 2023. Interesting to note, the driving lane was widened to 14 foot, or 2 foot over the existing shoulder. No cracking was noted, however, HMA shoulders were used, so there was no tie steel used between the shoulder and the overlay.



Figure 28 – Fremont County I-29 NB Unbonded Overlay (2023)



Figure 29 – Mills County I-29 NB Unbonded Overlay (2023)

Review of Bonded Overlays

Many of the early bonded overlays were placed on existing pavements in poor condition. Thus, any issues in the underlying pavement reflected through the overlay in short time. Also, many of the early bonded overlay projects were fast track projects⁶, utilizing Type III cements and insulating blankets for rapid strength gain. However, the very high temperatures and rapid hydration of the Portland cement resulted in non-durable paste, leading to durability issues.

A bonding grout was required for bonded PCC overlays until the April 2003 specification revision. Issues with bonding grout drying out can cause debonding of the overlay. It was found that when the existing PCC surface is in surface saturated dry condition, bonding with the PCC overlay is more than adequate.

Another issue affecting performance of bonded PCC overlays is the alignment of sawed joints in overlay with those in the existing pavement. All joints must be aligned directly over the existing joints to prevent random cracking. All joints need to be sawn full depth of the overlay and transverse joints need to be sawed as wide as the existing joints.

Currently, there is only one bonded concrete overlay projects remaining on the interstate and primary system. Placed in 1994, the Franklin County IA 3 bonded overlay project is the last remaining bonded overlay on the primary system. This bonded overlay was also a fast-track project, however, it was placed in cooler conditions in the fall and likely the concrete temperatures were not as elevated. Thus, the pavement exhibited better performance than the fast-track overlays placed in the summer.



Figure 30 – Poweshiek I-80 Bonded Overlay 1984 with Grout on Existing Pavement




Figure 31- Franklin Co. IA 3 Bonded Overlay

The existing concrete pavement should be in fairly good condition prior to placement of a bonded PCC overlay. Otherwise, any defects in the existing pavement will be mirrored through the overlay, in a very short time period.

Existing Pavement Prior to Overlay Design

For whitetopping and unbonded overlays, the condition of the HMA creates a critical component impacting the performance of the PCC overlay. The existing HMA layer may be oxidized with large number of thermal cracks. If the thermal cracks are unable to be removed by milling or filling, these thermal cracks can lock in the overlay, causing cracking in the PCC overlay.

On several projects, after milling was completed and haul trucks drove on the surface, the existing HMA layer deteriorated in areas. On the Woodbury I-29 unbonded overlay project, the HMA layer de-bonded from the PCC surface below during milling operations. HMA resurfacing was added as extra work to alleviate some of these issues. A non-woven geotextile interlayer has also been used to fix short areas of deterioration.



Figure 32 – HMA deterioration on US 71 Cass Whitetopping Project

The condition of existing PCC pavement, prior to a bonded PCC overlay, was discussed in the Review of Bonded Overlays section.

Design Features of Overlays

During this review, several design features were noted that have impact on the performance of the overlay. One of the best features noted was using full depth pavement at the beginning (BOP) or end (EOP) of the project and transition between overlay types. Using full depth pavement at the BOP or EOP is especially important if the transition pavement is HMA. Using full depth pavement prevents the panels from migrating due to traffic.



Figure 33 – Clay/Dickinson US 71 NB panels migrating in driving lane at BOP against HMA pavement.

Using full depth pavement transition between overlay types also improves performance of the overlay. This is especially needed if there is a difference in joint spacing. For instance, an unbonded overlay with 6 x 6-foot panels butted to a whitetopping overlay with other joint spacing, such as 12 x 12 foot or 9 x 8 foot. The full depth panel prevents misaligned joints from extending into adjacent panels.




Figure 34 – Full depth transition between overlay types typical



Figure 35 – Full depth transition panel US 71 Clay County

A typical design feature of unbonded overlays where the existing pavement had been widened and widened again with the overlay that has caused performance issues is the use of 60-inch reinforcing steel stapled to the existing pavement over the widening unit, extending into the new widening. This seems to cause issues on nearly all of these unbonded overlays where it has been used.

On many of the projects that exhibit longitudinal cracking in the wheel path, it has been observed that the shoulder has heaved and is not at the cross slope as placed. Many times, the shoulder is approximately 1 percent lower cross slope than that as placed. Apparently, this tends to raise the outside panel resulting in a crack developing off the end of the tie steel in the wheel path.

Prior to 2011, a #4 reinforcing steel bar 60 inches long was placed over the existing widening and into the new widening unit. From 2011 to 2014 a #5 bar was used and a #4 from 2015 and later. It was noted that the #5 bar may be too rigid and standards were changed back to the #4 bar. Although, it does not appear that changing to a smaller diameter bar has helped eliminate longitudinal cracking. Most all are stapled to the existing pavement and panels throughout the middle are moving with direction of traffic.



Figure 36 – Typical tie steel on unbonded overlay with existing widening.



Figure 37 – Closeup of steel, stapled to existing pavement.



Figure 38 – Shoulder slope 3.3%, Paved 4%



Figure 39 – Typical cracking off end of steel in wheel path.

Observations indicate that the outside panels and shoulder appear to be locked in place with the steel stapled to the existing pavement. On several projects, the center panels are moving with traffic. On two lane pavements, there are areas where the panels are moving at each other and

becomes an area where the panels buckle. Note in Figure 38 that the panels have moved approximately 1 inch from the left and approximately 1 ½ inches from the right, resulting in the between joint to buckle.



Figure 40 – Interior panels moving towards each other and blowup.

Future Overlay Design Details

Several alternate designs have been placed in the last few years that likely will address the issues found with the 60-inch reinforcing steel. One method used on the Marshall County IA 14 project was a 36-inch reinforcing steel was stapled across the existing widening unit. The overlay was placed full width and the shoulders were not tied.




Figure 41 – Marshall County IA 14 Overlay Typical



Figure 42 – Marshall County IA 14 Overlay

The use of macro fibers has been tried successfully on a few county projects in Worth and Buchanan counties. Based on the success of those projects, test sections utilizing macro fibers and various joint spacing were placed on the Woodbury IA 31 whitetopping overlay in 2020.

Begin Sta.	End Sta.	Length feet	PCC SY	PCC CY	Fiber lbs	Transverse Sawcut Spacing FT	Longitudinal Sawcut Spacing FT
43+76	50+00	624	2079.8	359.7	1438.7	6	6
142+00	152+00	1000	3333.0	576.4	2305.6	15	12
152+00	162+00	1000	3333.0	576.4	2305.6	12	12
162+00	172+00	1000	3333.0	576.4	2305.6	9	12
172+00	182+00	1000	3333.0	576.4	2305.6	9	6
182+00	192+00	1000	3333.0	576.4	2305.6	6	6
423+00	441+00	1800	5999.4	1037.5	4150.1	6	6

Figure 43 – Woodbury IA 31 Overlay 2020 Macro Fiber Test Sections

In 2022, the adjacent Cherokee IA 31 whitetopping project was placed with 4 lbs. macro fibers per cubic yard. The shoulders were tied with a #4 x 36" reinforcing steel bar at 30-inch center to center. The joint spacing utilized 12 x 12-foot panels.




Figure 44 – Cherokee IA 31 Whitetopping with Macro Fibers



Figure 45 – Cherokee IA 31 Whitetopping with Macro Fibers

In 2022, an unbonded overlay on US 63 in Tama and Blackhawk counties was placed with 5 lbs. of macro fiber per cubic yard. No reinforcing steel was used in the project. The existing pavement was rubblized in 1998, prior to an HMA overlay. The joint spacing utilized 6 x 6-foot panels.




Figure 46 – Cherokee IA 31 Overlay Typical




Figure 47 – LJ-1 and LJ-2 Joint Typical



Figure 48 – Tama/Blackhawk US 63 Overlay with 5 lbs. macro fiber per cubic yard.

In 2023, the Plymouth IA 3 whitetopping project utilized 4 lbs. of macro fiber per cubic yard. Similar to the Cherokee IA 31 whitetopping, the modified L-1 joint was used to tie the shoulders. Joint spacing was increased to 12 x 12-foot panels.

Utilizing fibers should be the future design for overlays. The fibers allow wider joint spacing, keep any cracking tight, reduce panel movement, and may eliminate the need for reinforcing to tie shoulders or bridge old widening units. These projects should be monitored regularly for performance and incorporated into current overlay designs.

Overlay Construction

During construction of overlays, the superelevated curves are typically corrected to the proper cross slope. When this is done with the overlay, the concrete can become much thicker than the design thickness on the outside of the curve. On the Woodbury I29 northbound overlay in 2008, the thickness on the outside of the curve reached up to 15 inches in some locations. The design was a 9 inch unbonded overlay, requiring the longitudinal joints to be sawed at T/3, or 3 inches. Sawing at 3 inches was not adequate on the thickened outside edge of the pavement, which should have been 5 inches based on the concrete placed.

This led to longitudinal cracking right away. Cracking also occurred in the inside lane from due to the widened slab over the shoulder and differential settlement. Approximately 3763 feet of cracking in the left lane and 9242 feet of cracking in the right lane was cross stitched.



Figure 49 – Woodbury I-29 NB Longitudinal Cracking – passing lanes.

Two similar projects were let the next construction season on I-29 in Fremont and Mill counties. Fortunately, the same contractor placed those overlays and developed a spreadsheet with pavement depths in order to assure the longitudinal joints were sawed at T/3.

Patching Overlays

Patching of PCC overlays falls into two categories, patching the overlay and full depth patching. When there are just a shattered panel or two, the overlay itself may be patched. However, many times the reason for the shattered panel is because the overlay is typically less than design thickness at that location. It may be possible to remove some of the HMA, if thick enough, to achieve a thicker patch replacement. If the HMA is thin or has deteriorated, a full depth patch may be required.



Figure 50 – Shattered panel. Typically overlay is thin in these areas.

If panels are moving, a full depth patch to the bottom of the existing pavement is recommended to prevent further movement. Many times, the old existing pavement may have longitudinal steel making it difficult to saw through the old pavement at the depth below. On the Clay/Dickinson US 71 project, the patch was pinned to the existing pavement below. These overlays should continue to be monitored to see if the panel movement has reduced significantly.

Full depth patches were placed approximately every 500 to 1000 feet on the Osceola IA 9 project in 2023 to prevent movement. West of US 59 the pavement seemed to exhibit more movement than east of US 59. A saw and seal project was also let on the Osceola IA 9 project. This project should be monitored for performance after the patching and sealing project.



Figure 51 – Full depth PCC patch in overlay



Figure 52 – Patch, existing original pavement left in place and pins.

Regardless of the type of patching, it is imperative to not add room on the ends to the patch. This allows more movement of the panels, leading to further patching issues. Patches should be placed tight to the next panel.



Figure 53 – Panel placed with 1 inch gap. Do NOT leave space.

Observations and Conclusions

Based on review of overlays on the interstate and primary system, the following observations were noted:

- Nearly all whitetopping overlays are in good condition, with minimal cracking and very little panel movement.
- There is substantially less cracking when the overlay is placed the same width as the existing pavement.
- Longitudinal joints sawed less than T/3 based on concrete placed causes cracking.
- The 60-inch reinforcing steel over existing widening and tie shoulders has caused longitudinal cracking on nearly all overlays where it was used.
- There are less issues with cracking when the smaller 36-inch reinforcing steel is used.
- Condition of the HMA interlayer may impact project progress if issues are found during milling.
- Unfilled joints cause issues with incompressible material and may be the cause of buckling with panel movement.
- Leaving room for movement with patches promotes further panel movement.

Recommendations

Based on observations during review of concrete overlays on the interstate and primary system, the following recommendations are discussed below:

- Place overlay same width as existing pavement.
- Use 6-inch minimum thickness.
- Use maximum size reinforcing steel of #4 x 36-inch length.
- Use macro fibers at 4 lbs./cy. Fibers help reduce cracking and panel movement.

- When fibers used, joint spacing may increase to 12 x 12 ft on 6-inch for whitetopping overlays and 9 x 8 ft with 7 x 8 ft. shoulders on 6-inch unbonded overlays with existing widening (18-foot original pavement).
- Fill all joints to prevent infilling.
- Saw longitudinal joints T/3 – based on thickness placed.
- Use full depth transition sections to existing pavement and overlay type change.
- Use full depth patches at locations with panel buckling to prevent further movement.

Since there have been some more recent changes with rehabilitation and designs with fibers, it is recommended to monitor the following projects to see how these changes impact long term performance.

- Osceola IA 9 overlay with full depth patches and joint filling.
- Tama/Blackhawk US 63 overlay with fibers and no reinforcing steel.
- Marshall IA 14 overlay, reinforcing stapled over old widening unit and untied shoulders.
- Plymouth IA 3 overlay with fibers and shoulders tied.

The National Concrete Pavement Technology Center has developed several guides for developing an overlay design⁷ and specification requirements⁸. Use of these guides as well as recommendations found during this study should be implemented to improve overlay performance.

References

- ¹Betterton, R.H. and Knutson, M.J., 1973, *Five Year Performance Study of Fibrous Concrete Pavement Overlay Research in Greene County, HR-165*, Iowa Department of Transportation, Ames, Iowa
- ²Gross, J., King, D., et al, 2017, *Concrete Overlay Performance on Iowa's Roadways, IHRB TR-698*, National Concrete Pavement Technology Center, Iowa State University, Ames, IA.
- ³Fick, G. and D. Harrington. 2014. *Performance History of Concrete Overlays in the United States*. National Concrete Pavement Technology Center, Iowa State University, Ames, IA.
- ⁴Cable, J. K., J. M. Hart, and T. J. Ciha. 2001. *Thin Bonded Overlay Evaluation Construction Report*. Civil and Construction Engineering, Iowa State University, Ames, IA.
- ⁵Cable, J.K., et al, *Design and Construction Procedures for Concrete Overlay and Widening of Existing Pavements, TR-511*, 2005, Center for Portland Cement Concrete Pavement Technology, Iowa State University, Ames, Iowa
- ⁶Calvert, G., Lane, O.J., Andersen, C., 1990, *Thin Bonded Overlay with Fast Track Concrete, HR-531*, Iowa Department of Transportation, Ames, Iowa
- ⁷Harrington, D. and G. Fick. 2014. *Guide to Concrete Overlays, Third Edition*. National Concrete Pavement Technology Center, Iowa State University, Ames, IA.
- ⁸Fick, G. and D. Harrington. 2015. *Guide Specifications for Concrete Overlays*. National Concrete Pavement Technology Center, Iowa State University, Ames, IA.


Acknowledgements

The author would like to thank the following for their input and review:

John Hart, Chris Brakke, Kevin Merryman, and Elijah Gansen from the Iowa Department of Transportation. Greg Mulder and Lee Shepard from the Iowa Concrete Paving Association. Peter Taylor, Leif Wathne, and Dan King from the National Concrete Pavement Technology Center. Craig Hughes from Cedar Valley Corporation and Jason Meihost from Croell, Inc.

Appendix A – Iowa Primary Overlays Project Information

Google Map of Interstate and Primary PCC Overlays



Interstate & Primary Overlay Project History Table

Iowa DOT Interstate & Primary PCC Overlays															
Existing Pavement	Overlay Type	District	County	PROJECT NO.	Route	DESCRIPTION	LENGTH (Miles)	S.V.	ORIG CONST.	OVERLAY CONST.	ORIG. THICK/ WIDTH	OVERLAY THICKNESS (in)	JOINT SPACING (ft)	PROJECT NOTES	CONTRACTOR
HMA	WT	4	Adair	IR-80-2(82086-14-01	I-80	I-80 WB. MP 83.85 to MP 97.25	5.000		1979	1979	10	10	20	10'x24'	GCC
PCC	BOL	4	Pottawattamie	I-EACR-80-1(126)	I-80	I-80 EBL Avooca to Shelby	4.492	63,246	1966	1979	3	3	20	3' replaced no later than 1990 (new PCC)	KCC
HMA	WT	4	Adair	IM-80-2(89188-14-01	I-80	I-80 EBL (T. Lane off) MP 85.75 to MP 98.86	8.100		1981	1981	10	10	20	10'x12.5' overlaid with 4" HMA in 2009	GCC
PCC	BOL	1	Poweshiek	IR-80-5(106)	I-80	I-80 fr 1 mi. E of IA 146 E approx. 9 mi. to I-25	9.084	127,900	1984	1984	10" PCC	4	20	4 overlaid with 4" HMA in 2007	MAN
PCC	BOL	3	Buena Vista	IR-71-1(132)	U.S. 71	U.S. 71 - Jct. IA 3 to Jct. IA 10	6.800	95,773	1949	1986	4	4	20	4" Bonded Fast Track RESEARCH Project	CFC
PCC	BOL	4	Pottawattamie	IR-80-4(167)	I-80	I-80 (WB) Shelby intchg. MLE E to Avooca intchg. US 59	4.134	53,600	1946	1988	6	6	20	6' replaced no later than 2005 (new PCC)	FJ
PCC	BOL	6	Scott	IR-280-9(97)	I-280	I-280 SBL fr 1/2 IA 22, N to US 6	7.250	137,390	1972	1989	5	5	20	5.0 C.I. replaced sometime after 2011 (new PCC)	CVC
PCC	BOL	6	Scott	IR-280-8(98)	I-280	I-280 (NBL) fr I-80 SE to Mississippi river bridge	1.000	19,212	1973	1990	5	5	20	5.0 C.I. replaced 2011?	VCC
PCC	BOL	6	Scott	IR-280-8(98)	I-280	I-280 (NBL) fr I-80 SE to Mississippi river bridge	7.230	142,863	1973	1990	5	5	20	5.0 C.I. replaced 2011?	VCC
PCC	BOL	1	Hamilton	IR-35-5(54)133-12-40	I-35	I-35 N of intchg. with Co. rd D41 N to intchg. IA	4.022	65,259	1967	1991	5	5	20	5.0 C.I. replaced 2003? (New PCC)	FCC
PCC	BOL	1	Hamilton	IR-35-5(56)133-12-40	I-35	I-35 fr 2 mi. N of IA 175 intchg. N approx. 1 mi. N of Co. rd D41 intchg.	6.052	111,469	1967	1992	8" PCC	5	20	5.0 C.I. SB lane replaced sometime after 2011 (New PCC)	FJ
PCC	BOL	2	Franklin	NHS-3-5(50)19-35	IA 3	From 3 mi. W. of Jct 541, E. 1.8 mi. & 2.0 mi. W. of I-35 intchg.	2.900	40,260	1970	1994	9" PCC	3	20		CVC
HMA	WT	6	Iowa	SFP-21-3(10)-2C-48	IA 21	IA 21 fr Jct. of US 6 N to Jct. of IA 212	7.000		1961	1994	3" HMA 1964 0.5" HMA 7" CTB 1994	2, 4, 6	Various	Ver. 204" DOT RESEARCH Project Thin sections resurfaced	MAN
Comp	UBOL	6	Delaware	SFP-13-2(3)2C-28	IA 13	IA 13 fr NCL of Manchester N to IA 3	9.845		1937	2002	3" HMA 1982 2" HMA 1964 10-7-10-18" 1937	3.5 to 4.5	4 to 6'	3.5-4.5"x28" RESEARCH Project	FCC
HMA	WT	4	Montgomery	NSHN-071-2(16)-2R-69	U.S. 71	U.S. 71 from US 24 North to Cass Co. line	12.574	177,035	1972	2005	2" HMA 1981 9" HMA 24" 1972	8	14	8" 24" 3" milled	MAN
Comp	UBOL	3	Sac	SFP-175-4(13)-2C-81	IA 175	IA 175 from 6th Co. line E to W. Jct US 71	8.977	122,246	1939	2006	4" HMA 24" 1986 10-7.5-10-20" 1939	4.5	7	4.5" 28" 1806 HMA widening w/eng. fabric over joint	CVC
HMA	WT	4	Cass	NHSH-071-3(42)-3R-15	U.S. 71	U.S. 71 from Montgomery Co. line N. to Co. rd G 45	10.560		1972	2007	2" HMA 1981 9" HMA 24" 1972	8	14	8" x 32' (12' with 4" tied lanes) 3" milled	FLY
Comp	UBOL	3	Woodbury	IM-029-6(18)132-13-97	I-29	I-29 from Monroes Co. line N to Sergeant Buif interchange (NBL)	14.144	236,138	1959	2008	3" HMA 1989 10" 24" PCC 1959	9.5	15	3" Milled 9" 26" FD inside Shldr. paved integral. 7" Out Shldr. 14' driving lane over 12' existing & Shldr.	CVC
HMA	WT	2	Bremer	NHSH-218-8(109)-2R-09	U.S. 218	U.S. 218 Along Wisniewsky Bypass (MP 186.57 to 189.46)	7.750	279,840	1958	2009	11.5" 24" HMA	8.5	14	8.5" x 32' (12' with 4" tied lanes)	MAN
Comp	UBOL	4	Fremont	ESIMK-029-1(75)16-15-36	I-29	N. of Co. rd. I-24 PCC overlay NBL/HMA	4.340	66,170	1972	2009	8" 24" CRK/4" CTB	9	15	1" HMA interlayer 9" 26" (6" tied FD PCC Shoulders 10" R HMA) shoulder COARSEN	GOD
Comp	UBOL	4	Millis	ESIMK-029-2(65)38-15-65	I-29	I-29 from 3 mi. E. of N. Jct US 24 N. to Pottawattamie Co. line (NBL)	5.700	102,473	1971	2009	8" HMA 8" CRK/4"	9	15	8" HMA interlayer 9" 26" (6" tied FD PCC Shoulders + 10ft HMA) 8" 24" (6" tied FD PCC Shoulders + 10ft HMA) 5.5" 28" (4.5" tied long joints)	CVC
Comp	UBOL	3	Oceola	SFP-009-3(21)-2C-72	IA 9	IA 9 from E. of relocated IA 60 E. to W. of Jct Co. rd L-58	8.700	136,497	1931	2009	1.5" HMA 1983 3" HMA 1981 3" PCC widen 1956 10-7-10-18" 1931	5.5	5	4" bars @ 30" CTR 9.5" x 2' Widening	FLYNN

Interstate & Primary Overlay Project History Table (continued)


Iowa DOT Interstate & Primary PCC Overlays															
Comp HMA	UBOL & WT	3	Clay	NHSK-071-8(89)-3H-21	US 71	US 71: From Co. Rd. 855 N. to 15th St. in Spencer	7:740	138,911	1991	2015	6	6	8	6" x 32" (6' x 6' ML and 4' x 6' Shldr) panels Shoulders UBOL #4 bars 36" @ 60" UBOL 2" Milling	CVC
Comp HMA	UBOL & WT	3	Clay	NHSK-71-8(88)-3H-21	US 71	US 71: Buena Vista Co. Line N. to Co. Rd. B53	6.95	123895	1991	2016	6	6	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) WT #4 bars 36" @ 30" CTR WT 2" Milling	CVC
Comp HMA	UBOL & WT	3	Clay	NHSK-71-8(88)-3H-21	US 71	US 71: Buena Vista Co. Line N. to Co. Rd. B53	6.95	123895	1991	2016	6	6	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) panels Shoulders UBOL #4 bars 36" @ 60" UBOL 2" Milling	CVC
Comp HMA	UBOL	6	Benton	STPN-021-4(27)-2J-06	IA 21	IA 21: From E 66 N. to Just S. US 30	3.46	62080	1979	2016	5.5	5.5	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) 2" HMA Bondbreaker	MAN
Comp HMA	UBOL	4	Dallas Boone	NHSK-169-4(63)-3H-25	US 169	US 169 From IA 141 N to US 30	13.02	299862	1940	2018	7	7	12	7" x 32" (12 x 12" ML and 4 x 12" Shldr) #4 bars 36" @ 60" CTR Geotextile Interlayer	MAN
Comp HMA	UBOL	1	Marshall Grundy	HSPX-014-5(81)-3H-64	IA 14	IA 14 From Co. Rd. E18 N. to W. JCT IA 175	11.28	155401	1992	2019	6	6	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) 1" milling Shoulder/Widening not tied	CVC
HMA	WT	3	Woodbury	STP-031-1(43)-2C-97	IA 31	IA 31 From E. JCT US 20 N. to Co. Rd. 066	8.2	137007	1995	2020	6	6	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) #4 x 36" @ 30" c-c 3" Milling Fiber Test Sections	CVC
HMA	WT	3	Cherokee	STP-031-3(11)-2C-18	IA 31	Washtato US 99	10.17	162607		2022	6	6	12	Fibers 4 lb/cy 3" Milling Euclid Turf Strand SF Fibers #4 x 36" @ 30" c-c	CVC
HMA	WT	3	Plymouth	NHSK-003-1(106)-2R-75	IA 3	Lamar to Remsen	8.72	181506		2022	6	6	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) #4 x 36" @ 30" c-c 2" Milling 12 x 12 test section	Croell
Comp HMA	UBOL	1	Tama	NHSK-063-5(72)-3H-86	US 63	From Traer to 0.5 mi S of IA 98	13.14	25286		2022	5	5	6	6" x 32" (6' x 6' ML and 4' x 6' Shldr) 3" Milling Fibers 5 lb/cy - Forta Ferro	Croell
HMA	WT	3	Plymouth	NHSK-003-1(104)-2R-75	IA 3	Remsen to Cherokee Co Line	5.36	75050		2023	6	6	12	6" x 36" (12 x 12" ML & 6 x 12" Shldr) 2" Milling #4 x 36" @ 30" c-c Fibers 4 lb/cy Forta Ferro	Croell

Interstate & Primary Overlay Project History Table (continued)

Iowa DOT Interstate & Primary PCC Overlays															
Comp	UBOL	2	Worth	STP-065-018)-2C-38	U.S. 65	U.S. 65 from IA 9 in Nanny N. to Co. Rd 105	1928-9	1928-9	2009	1928-9	1928-9	5	5	5	FLYNN
Comp	UBOL	2	Chickasaw	NHSX-018-7(18)-3H-19	U.S. 18	U.S. 18 from ECL of Fredericksburg E. to West Union	1938	1938	2011	1938	1938	4	4	4	MAN
Comp	WT NB	3	Clay	NHSX-071-8(15)-3H-21	U.S. 71	U.S. 71 from US 18 North to SCL of Milford-NBL	1954	1954	2012	1954	1954	6	6	6	MAN
HMA	UBOL SB	3	Clay	NHSX-071-8(15)-3H-21	U.S. 71	U.S. 71 from US 18 North to SCL of Milford-SBL	1992	1992	2012	1992	1992	6	6	6	MAN
Comp	UBOL	1	Grundy	STP-014-6(13)-2C-38	IA 14	IA 14 from 5 mile South of US 20 North to IA 57	1954	1954	2013	1954	1954	4.5	4.5	4.5	CFI
Comp	UBOL	2	Fayette	NHSX-003-7(19)-3H-33	IA 3	IA 3 from West County Line to North City Limits of Osceola	1930	1930	2013	1930	1930	5	5	5	Croell
Comp	UBOL	5	Lucas	NHSX-065-2(10)-3H-59	U.S. 65	U.S. 65, From Wayne Co. Line N. to US 34	1954	1954	2013	1954	1954	5	5	5	MAN
Comp	UBOL	2	Kossuth	NHSX-169-8(19)-3H-55	U.S. 169	U.S. 169, E. Jct. IA 9 N to Minnesota State Line	1940	1940	2014	1940	1940	5	5	5	Croell
Comp	UBOL	1	Poweshiek	NHSX-063-4(19)-2H-79	U.S. 63	US 63 from NCL Montezuma North to just south of I-80	1987	1987	2014	1987	1987	5	5	5	Croell
Comp	UBOL	3	Cherokee	NHSX-059-7(16)-3H-18	U.S. 59	US 59 from DA Co. Line N. to IA 3	1991	1991	2014	1991	1991	6	6	6	CVC
Comp HMA	UBOL & VIT	3	Cherokee	NHSX-003-2(19)-3H-18	IA 3	Iowa 3, Plymouth Co to ECL of Clifton	1937	1937	2015	1937	1937	6	6	6	KNIFE
Comp	UBOL	1	Polk	STPH-069-4(100)-2J-77	U.S. 69	US 69 From Just N of 118th Ave N. to just S. of IA 210	1921	1921	2015	1921	1921	5	5	5	FLN
Comp HMA	UBOL & VIT	3	Clay	NHSX-071-8(15)-3H-21	U.S. 71	US 71 From Co. Rd. 833 N to 15th St in Spencer	1951	1951	2015	1951	1951	6	6	6	CVC

Appendix B - Primary Overlays Project Construction History and Review

Year	2006	Overlay Type	Whitetopping
County	Montgomery	Design	8" – 24 ft. CD 14 ft. HMA Shoulders
Route	US 71	Milling	3" milling
Project	NSHN-071-2(36)—2R-69	Interlayer	Existing HMA
Location	U.S. 71 from US34 North to Cass Co. line	Tie Bars	n/a



Notes:

- ① Finished slope shall match existing pavement except that the maximum allowable slope is 3.0 %, minimum allowable slope is 2.0 %. Section may be modified as directed by the Engineer through areas of special shaping.
- ② Shoulder material as specified elsewhere in these plans. See Typical 7153M for more details.
- ③ Top 4" of existing shoulder material will be removed from BOP to Sta 27+50. Top 1" of existing shoulder material will be removed from Sta. 27+50 to EOP. Shoulder will be reconstructed as per Typical 7153M. Per side per station.
- ④ 10' climbing lane on right. Includes 400' tapers at each end.

Construction

Some issues with HMA failing during construction. Several areas patched with new HMA.






Review 2023

Overall, in good condition. A few areas with cracking just off centerline (~4 to 5 locations). Some issues with centerline rumble strips went through transverse joints and were patched.



Year	2007	Overlay Type	UBOL
County	Sac	Design	4.5" x 28 ft. (7 x 7 ft. panels)
Route	IA 175	Milling	1/2" at CL – 2% cross slope
Project	STP-175-4(13)--2C-81	Interlayer	Existing HMA
Location	Ida Co. line E to W. Jct US 71	Tie Bars	None




LOCATION		Per Station				PCC OVERLAY, GMC (PLACE)	PCC OVERLAY, GMC (FURNISH)	MILLING	CLASS 13	
ROAD IDENTIFICATION	STATION TO STATION	D	J	T1	T2	Sq. Yds.	Sq. Yds.	Sq. Yds.	Cu. Yds.	
IA 175 (Div. 1)	2373+57	2533+80.1	28	2	4.5	8.0	311.1	46.91	266.67	4.32
IA 175 (Div. 2)	2533+80.1	2568+00	28	2	4.5	8.0	311.1	46.91	266.67	4.32
IA 175 (Div. 2)	2568+00	2575+51.7	28	1	4.5	8.0	311.1	45.06	288.89	2.16
IA 175 (Div. 2)	86+20.0	100+60.7	28	1	4.5	8.0	311.1	45.06	288.89	2.16
IA 175 (Div. 1)	100+80.7	332+93.6	28	2	4.5	8.0	311.1	46.91	266.67	4.32
IA 39 (Div. 2)	3+52.9	7+26.1	28	2	4.5	8.0	311.1	46.91	266.67	4.32

Notes:

- ① Refer to tabulation listing of superelevated curves and Standard Road Plans for additional requirements through superelevated curves.
- ② Shoulder material as specified elsewhere in these plans; refer to typical 7135 on B.01 for "Type 'B' Granular Surfaced Shoulders."
- ③ Quantity includes PCC widening units to be placed with PCC overlay and based on 5 inch thickness for irregularities.
- ④ Mill the existing HMA pavement 1/2" deep at centerline, and to a 2% cross slope except in areas of superelevation and as shown on typical MW-1.
- ⑤ Includes both sides.
- ⑥ Existing pavement width is 24' except in Div. 2 (corporate limits of Odebolt) where it is 26'.

2610
MODIFIED

IA 175 / IA 39



JOINTS	
————	Sawn (saw-cut width = $\frac{1}{8}$ " , saw-cut depth = $1\frac{1}{2}$ ")
- - - - -	Permissable Construction, Unsawn



2008 Cracking

Quite a bit of longitudinal cracking showed up the next year after construction. It was noted that the outside shoulders appeared to be heaving based on the cross slope.





Driving lane panel cross slope 2.09%



Shoulder panel cross slope 1.31%

2017 Patching Project

Many of the areas needing patching were not at design thickness of 4.5 inches. Note in the picture that the overlay is 3 inches where patching.




2021 Review

After most of the cracking occurred, the district filled the longitudinal cracks with hot pour sealant. Even with all the cracking that occurred early, the pavement continues to ride fairly well. There are likely areas that need to be patched.





Year	2007	Overlay Type	Whitetopping
County	Cass	Design	8" x 32 ft. (12 x 14 ft. CD)
Route	US 71	Milling	3" Milled
Project	NHSN-071-3(42)--2R-15	Interlayer	Existing HMA
Location	Montgomery Co. line N. to Co. Rd G-43	Tie Bars	L-2 #5



DESIGN RATES	
ITEM	RATE
Milling	145 lbs./cu. ft.
Special Backfill	140 lbs./cu. ft.

TABLE OF DESIGN QUANTITIES Per Station									
LOCATION		(F)	(G)	(D)	MILLING	CLASS 13	SPECIAL	6" PCC	6" PCC
ROAD IDENTIFICATION	STATION TO STATION	INCHES	INCHES	FEET	SF	EXCAVATION	BACKFILL	OVERLAY	OVERLAY
US 71	683+77.00 (D) 894+84.68	8	3	32	266.7	22.2	28	355.56	79.01
US 71	(D) 100+00.00 434+90.00	8	3	32	266.7	22.2	28	355.56	79.01
US 71	564+21.00 582+91.00	8	6	32	266.7	22.2	14	355.56	79.01

Modified

Notes:

- (1) Existing pavement width is 24 ft.
- (2) Finished slope shall match existing pavement except that the maximum allowable slope is 3.0% minimum allowable slope is 2.0%. Section may be modified as directed by the Engineer through arrow of special sloping.
- (3) Shoulder material as specified elsewhere in these plans refer to Typical 7110M.
- (4) 6" depth 4' wide, 6" to be replaced with Special Backfill for subdrain work prior to PCC overlay. (Both sides)
- (5) Includes 4" PCC paved shoulder. Refer to Typical 2205M for climbing lane details.
- (6) Refer to Typical PCC-4 for details. See Tab 104-1 for locations.
- (7) Equation Sta. 894+84.68 Back - Sta. 100+00.00 Road
- (8) Refer to Detail Sheet 003 for details.

Construction

There were areas where the HMA was in poor condition and new HMA was placed. A shortage of haul trucks caused the paving machine to move slowly waiting for concrete. There are several areas where the grout box material was dropped into the pavement. These areas have major popouts from the light particles in the gravel source.










2023 Review

Overall, in good condition. There are approximately 3 to 4 areas with cracking at quarter point. There are also areas where milled rumble strips went through transverse joints and blew out edge.





Year	2008	Overlay Type	UBOL
County	Woodbury	Design	9" x 26' FD Inside Shoulder integral. 7" Outside Shoulder.
Route	I-29 NB	Milling	2" Milling
Project	IM-029-6(183)132--13-97	Interlayer	Existing HMA
Location	Monona Co. Line N to Sgt. Bluff	Tie Bars	#5



NOTES

- ① Shoulder rumble strip required. Refer to Sheets U.08 and U.10 for details.
- ② "L-2" Joint required. See Standard Road Plan RH-51.
- ③ The median shoulder may be placed with the 26-ft. wide I-29 NB main-line pavement.
- ④ For the PCC alternate, use "L-1", "KT-1", or "BT-1" joint. See Standard Road Plan RH-51.
- ⑤ UAC and protect existing subdrains.
- ⑥ Profile grade for this project is located on the centerline of the NB lanes.
- ⑦ Use "L-2", "K-2", or "BT-2" joints. See Standard Road Plan RH-51.

During milling of the HMA, there were a few areas where the HMA peeled off the existing concrete.






Section 2 Cross stitching 9242 feet right, 3763 feet left.



Year	2009	Overlay Type	UBOL
County	Osceola	Design	5.5"x28' (4.5x4.5x5' long joints)
Route	IA 9	Milling	None
Project	STP-009-2(21)—2C-72	Interlayer	Existing HMA Surface
Location	IA 60 E. to L-58	Tie Bars	#4 bars 6' @30" CTR




ROAD IDENTIFICATION	LOCATION	STATION TO STATION	Per Station				PCC OVERLAY, GMC (PLACE) Cu. Yds.	PCC OVERLAY, GMC (FURNISH) Cu. Yds. ③	CLASS 13 EXCAVATION Cu. Yds. ④
			①	②	⑤	⑥			
IA 9	102+09	360+31.4	28	2	5.5	9.5	311.11	56.79	4.94
IA 9	762+99.47	839+58.21	28	2	5.5	9.5	311.11	56.79	4.94
IA 9	848+89.11	935+58.5	28	2	5.5	9.5	311.11	56.79	4.94
IA 9	943+71.5	1043+25	28	2	5.5	9.5	311.11	56.79	4.94

TYPICAL UNBONI

Notes:

- ① Longitudinal joints shall be located at centerline, 4.5-ft. L. and R. of centerline and 9.0-ft. L. and R. of centerline. A modified "L-1" MK-II joint shall be located at 9.0-ft. L. and R. of centerline with a 9-ft. long reinforcing bar. Transverse joints shall be located at 5.0-ft. spacings.

Each 6-ft. rebar shall be attached to the existing HMA surface in at least 3 locations. Connectors shall be no less than 12-in. apart and no more than 15-in. apart. See Sheet U01 for a plan view of the required joint layout.
- ② Shoulder material as specified elsewhere in these plans; refer to typical 7135 on Sheet B.1 for "Type 'B' Granular Surfaced Shoulders."
- ③ Quantity is estimated using a 6-in. thickness over the existing 24-ft. wide pavement and a 10-in. thickness for the integral 2-ft. widening units.
- ④ Includes both sides.
- ⑤ Existing total pavement width is 24'.
- ⑥ Earth Shoulder Construction: Place and compact Class 13 Excavation in this area to build up the shoulder and eliminate the secondary ditch along the edge of the existing shoulder. Slope shall be adjusted as directed by the Engineer.
- ⑦ Any existing HMA edgecut or fillet material within 2-ft. of the edge of the existing pavement shall be considered Class 13 Excavation except at paved county road intersections.
- ⑧ Existing HMA fillet material that is located 2-ft. or more from the edge of existing pavement will be tabulated as Additional Class 13 Excavation at Entrances and Driveway Road Intersections. See Tab A300.13 on Sheet C.8.



Construction

Some issues with late sawing causing cracking off end of saw joints.



2021 Review

Panels moving, especially west of US 59. Maintenance placed patches with foam on either said to accommodate slab movement. We noted that now the slabs will move even more. District will let a patching project to ad full depth patches in areas to prevent slab migration.





Longitudinal cracking




PCC overlay in better condition east of US 59.




2023

Project let in 2023 included 4293.3 SY of 10-foot x 28-foot x 17-inch full depth patching and 8.9 miles of joint sealing for the entire project. Full depth patches were selected try to stop panel movement.


Year	2009	Overlay Type	WT
County	Bremer	Design	8.5" x 32' (12' with 4' Shoulder.
Route	US 218	Milling	Scarify Existing
Project	NHSN-218-8(109)--2R-09	Interlayer	Existing HMA
Location	Waverly Bypass	Tie Bars	Modified L-2 5' bar



Location		P	E	M	L	R	S	PCC Pavement Sq. Yds.	*Pavement Scarification Sq. Yds.	Pavement Scarification Tons	
Road Identification	Station To Station	Inches	Inches	Inches	Feet	Feet	Feet				
Northbound Lanes											
U.S. 218	319+44.00	328+25.00	8.5	11.5	1.5	16	16	6	3132	2838	223
U.S. 218	336+75.00	496+66.38	8.5	11.5	1.5	16	16	6	56,858	46,197	3538
U.S. 218	506+25.00	514+52.97	8.5	11.5	1.5	16	16	6	2944	2392	188
U.S. 218	523+36.66	550+63.78	8.5	11.5	1.5	16	16	6	9696	7878	227
U.S. 218	559+64.78	658+85.00	8.5	11.5	1.5	16	16	6	35,236	28,629	2255
U.S. 218	666+85.00	713+85.00	8.5	11.5	1.5	16	16	6	16,711	13,578	1069
Southbound Lanes											
U.S. 218	311+26.00	496+66.38	8.5	11.5	1.5	16	16	6	65,921	55,854	4399
U.S. 218	506+25.00	514+83.43	8.5	11.5	1.5	16	16	6	3052	2480	195
U.S. 218	523+67.12	550+63.78	8.5	11.5	1.5	16	16	6	9588	7790	613
U.S. 218	559+64.78	658+85.00	8.5	11.5	1.5	16	16	6	35,236	28,629	2255
U.S. 218	666+85.00	713+85.00	8.5	11.5	1.5	16	16	6	16,711	13,578	1069
TOTALS								255,085	209,843	16,131	



DETAIL "A"



Construction







2023 Review

Overall, in good condition. An area on the north end of the southbound lanes exhibits some issues at the joints. There are a few random areas of longitudinal cracking in the driving lane.








2023 Review

Pavement in very good condition. No issues with cracking.





Year	2009	Overlay Type	UBOL
County	Mills	Design	9" x 26' (8' & 6' HMA Shoulders) CD
Route	I-29	Milling	4-5" Existing HMA removed
Project	ESIMX-029-2(65)38--1S-65	Interlayer	1" New HMA
Location	3 miles N. of N. Jct US34 N. to Pottawattamie Co. line	Tie Bars	L-2



LOCATION NORTHBOUND LANES		MW	M	S	T	U	E
ROAD IDENTIFICATION	STATION TO STATION	Feet	Feet	Inches	Inches	Inches	Feet
Mills Co.	EQN: STA. 865+69.20 = STA. 860+71.80						
I-29 NBL	701+31.00 862+65.16	50	UAC	5.0	9.0	10.0	10.0
	863+58.63 944+44.40	50	UAC	5.0	9.0	10.0	10.0
Pott. Co.	EQN: STA. 944+44.40 = STA. 00+00.00						
I-29 NBL	00+00.00 60+24.60	50	UAC	4.0	9.0	10.0	10.0


2023 Review

Pavement in very good condition. No issues with cracking.





Year	2009	Overlay Type	UBOL
County	Worth	Design	5.5"x28' (4.5x4.5x5' long joints)
Route	US 65	Milling	0.5" Milling – Paved Half Width
Project	STP-065-9(18)--2C-98	Interlayer	Existing HMA
Location	IA 9 N. to Co. Rd 105	Tie Bars	#4 bars 6' @ 30" CTR





LOCATION		(M)	(T1)	(D)	(T2)	(J)	PCC OVERLAY QMC (Furnish) Cu. Yds.	PCC OVERLAY QMC (Place) Sp. Yds.	REMARKS
ROAD IDENTIFICATION	STATION TO STATION	Inches	Inches	Feet	Inches	Feet			
US 65	2329+00.05 2331+25.05	0.5	5.0	24	8.0	4	129.2	800.0	225' to BOP
US 65	2331+25.05 2434+22.00	0.5	5.0	24	8.0	4	4405.1	28137.9	BOP to 1st Bridge Approach
US 65	2436+14.00 2447+03.05	0.5	5.0	24	8.0	4	626.0	3872.2	End 2nd Bridge Approach to 1st Reconstruction
US 65	2462+79.00 2575+61.00	0.5	5.0	24	8.0	4	6460.7	40113.8	End 1st Reconstruction to Town Section
US 65	2575+61.00 2629+28.00	2.0	5.0	24	8.0	4	2482.0	19,082.7	Town Section
US 65	2629+28.00 2667+38.00	0.5	5.0	24	8.0	4	2120.5	13,546.7	Town Section to 3rd Bridge Approach
US 65	2669+28.00 2767+06.00	0.5	5.0	24	8.0	4	5427.7	34,766.2	4th Bridge Approach to 5th Bridge Approach
US 65	2786+82.99 2908+06.00	0.5	5.0	24	8.0	4	6625.8	43,104.0	End 2nd Reconstruction to 225' from EOP
US 65	2908+06.00 2910+31.00	0.5	5.0	24	8.0	4	129.2	800.0	225' to EOP
370th St.	Total Area = 2054.5						50.7	228.3	Quantity subtracted to get TOTAL
390th St.	Total Area = 2051.6						50.7	228.0	Quantity subtracted to get TOTAL
430th St.	Total Area = 2054.5						50.7	228.3	Quantity subtracted to get TOTAL
TOTAL:							29,569.0	183,448.9	

Notes:

Modified

- ① Finished slope shall match existing pavement except that the maximum allowable slope is 3.0% minimum allowable slope is 2.0%. Section may be modified as directed by the Engineer through areas of special shaping.
Refer to tabulation listing of superelevated curves and Standard Road Plans for additional requirements through superelevated curves.
- ② Refer to other drawings for details of shoulder design and construction.
- ③ Refer to Standard Road Plan RF-19C. Subdrain on one side only.
- ④ PCC Pavement with PCC Widening Units and HMA Resurfacing
- ⑤ Quantities include partially paved shoulders based on T2 of 8.5 Inches for irregularities.
- ⑥ See Typical TL-1, TL-2 and 'J' Sheets for locations where ② is omitted for turn lanes.



- Notes:
- ① Extend existing expansion joints in kind in new pavement.
 - ② Place CF joint in overlay.

Construction

Overlay was placed half width at a time.



2013 Review

Areas of cracking and broken panels.




2021 Review

Areas of blowups due to panel movement.




2023 - Patching project let in 2023 with 2536.4 SY of 10-inch full depth patching and 293 patches by count.


Year	2011	Overlay Type	UBOL
County	Chickasaw-Fayette	Design	4" x 32' (4" x 24' & 4' x 8" widening) - Paved half width
Route	US 18	Milling	0.5" Milled 2%
Project	NHSX-018-7(58)--3H-19	Interlayer	Existing HMA
Location	ECL of Fredericksburg E. to West Union	Tie Bars	#5 bars 6' @ 30" CTR





Location		Overlay Quantities (2) Per Station										Remarks	
Road Identification	Station To Station	S	B	C	L	H	Class 13		T	BW	G		Granular Shoulder
		Inches	Inches	Feet	Feet	Feet	Du. Yds.	Du. Yds.	Inches	Feet	Feet	Tons	
US 18	346+55.4 - 416+37	4	0.5	32	16	16	12.35		49.38	4	4	6	33.97
US 18	420+08 - 78+66.0*	4	0.5	32	16	16	12.35		49.38	4	4	6	33.97
US 18	82+74 - 99+92.9	4	0.5	32	16	16	12.35		49.38	4	4	6	33.97
US 18	99+42.9 - 100+42.9	Vari	0.5	32	16	16	12.35		54.32	4	4	6	35.87
US 18	100+42.9 - 108+68.8	5	0.5	32	16	16	12.35		59.28	4	4	6	37.77
US 18	108+68.8 - 109+18.8	Vari	0.5	32	16	16	12.35		54.32	4	4	6	35.87
US 18	109+18.8 - 340+33	4	0.5	32	16	16	12.35		49.38	4	4	6	33.97
US 18	346+82 - 701+87.27	4	0.0	32	16	16	12.35		49.38	4	4	6	33.97

Sta. 346 to W-14





W-14 to EOP



Construction

Placed half width other lane open to traffic. Used a modified drop off.





2017 Cracking



2021 Review






2023



A patching project was let in 2023 with 10,221.09 SY of full depth patching by area and 1680 SY of full depth patches by count. The vast majority of patches were only the 4.5-inch overlay, with a few areas of 10 inch and 17-inch full depth.

Year	2012	Overlay Type	WT & UBOL
County	Clay	Design	6" x 24' (6' outside, 4' inside 8" PCC Shoulders)
Route	US 71 SB	Milling	1 1/2 to 2 1/2" Milling
Project	NHSX-071-8(55)--3H-21	Interlayer	Existing HMA
Location	US 18 N to SCL of Milford	Tie Bars	#5 x 6' @30" CTR - UBOL #5 x 3' @30" CTR - WT





Milepost	Direction	Existing Pavement Type
207.92-212.88	NB	Composite
212.88-217.37	NB	HMA
207.92-212.88	SB	HMA
212.88-214.55	SB	Composite
214.55-215.33	SB	HMA
215.33-216.08	SB	Composite
216.08-217.37	SB	HMA

Over existing composite pavement



Over existing HMA pavement





Construction



2021 Review

UBOL sections - Longitudinal cracking off end of reinforcing in the outside wheel path. Shoulder heaving. Whitetopping overlay sections in very good condition.






Shoulder cross slope 3.3%, Design 4%.







Whitetopping section

Year	2013	Overlay Type	UBOL
County	Grundy	Design	4.5" x 30' with safety edge; 5.5' x 5.5'- x 4' long joints
Route	IA 14	Milling	1" HMA
Project	STP-014-6(31)--2C-38	Interlayer	Existing & New HMA
Location	From 0.5 miles S of US 20 N to IA 57	Tie Bars	#5 bars 3' @ 30" CTR



Location		Overlay Quantities (Per Location)											Remarks					
Road	Station To Station	(B)	(S)	(C)	(L)	(R)	(T)	(BW)	(C)	(2) Class 13	(8) Tack Coat	Stress Relief	PCC Overlay	PCC Overlay	(T)	(BW)	(C)	
		Inches	Inches	Feet	Feet	Feet	Inches	Feet	Feet	Cu. Yds.	Gal.	Sq. Yds.	Cu. Yds.	Sq. Yds.	Inches	Feet	Feet	
IA 14	382+75																	See Typical HMA1 on sheet B.2
IA 14	384+00									24	51	1,022	178.0	1,228.7	4.5	4	5	
IA 14	386+30	1	4.5	48	Vari.	Vari.				60	101	2,027	377.8	2,533.3	4.5	4	5	
IA 14	392+00	1	4.5	30	14	14				609	709	14,178	3,038.8	19,333.3	4.5	4	5	
IA 14	439+00	1	4.5	30	14	14				325	611	12,222	2,619.7	16,868.7	4.5	4	5	
IA 14	500+00	1	4.5	30	14	14				802	988	19,762	4,137.6	26,548.9	4.5	4	5	(6)
IA 14	578+50	1	4.5	30	14	14				11	12	244	52.4	333.3	4.5	4	5	
IA 14	588+50	1	4.5	30	14	14				501	630	12,591	2,614.6	16,827.1	4.5	4	5	(6)
IA 14	639+00	1	4.5	30	14	14				11	12	244	52.4	333.3	4.5	4	5	
IA 14	639+00	1	4.5	30	14	14				289	336	6,722	1,440.8	9,168.7	4.5	4	5	
IA 14	666+50	1	4.5	30	14	14				310	361	7,211	1,545.6	9,833.3	4.5	4	5	
IA 14	696+00	1	4.5	30	14	14				925	611	12,222	2,619.7	16,868.7	4.5	4	5	
										3,667	4,422	88,446	18,677.4	119,469.3				
IA 14	746+00																	See Typical HMA1 on sheet B.2





Construction

Tie steel was glued down with epoxy.






2021 Review

A few broken panels in wheel paths. Some of these areas have been patched.





Year	2013	Overlay Type	UBOL
County	Fayette	Design	5" x 32' (4.5 x 5' panels 24' wide & 4' x 9.5" widening)
Route	IA 3	Milling	1 1/2" Milling
Project	NHSX-003-7 (29)--3H-33	Interlayer	Existing HMA
Location	County Line to NCL of Oelwein	Tie Bars	#5 bars 6' @ 30" CTR



3R_Overlay_ MODIFIED	
STATION TO STATION	
677+22.20	785+50.50
791+45.50	1002+44.54
1007+77.46	1124+00.00

Longitudinal joint: See B.6 for Jointing Details
 Transverse joint: See B.6 for Jointing Details





Construction

During milling operations, the mill removed HMA on the outside edge of the pavement in areas. Fabric interlayer was used to cover the exposed PCC pavement.





2017 – Cracking at 4 ft from edge. Location of old edge of widened pavement.






2021 Review

Cracking along paint line. Some patching.



Year	2013	Overlay Type	UBOL
County	Lucas	Design	5" x 32' (5" x 22' & 5" x 9" widening)
Route	US 65	Milling	1954 8.5" PC8
Project	NHSX-065-2(20)--3H-59	Interlayer	1" HMA Bond Breaker
Location	Wayne Co. Line N. to US 34	Tie Bars	#5 bars 36" @ 30" CTR





Construction





2023 Review

Several areas with patches. Patches were full lane width, with no midpanel longitudinal joint. Several areas with outside wheel path cracking. Shoulder cross slope was 1.0 to 1.5%. Fairly long areas in good condition as well.













Year	2014	Overlay Type	UBOL
County	Kossuth	Design	5" x 32' (5" x 24' & 4' x 8" widening)
Route	US 169	Milling	Profile to 2% cross slope, 1"
Project	NHSX-169-8(59)--3H-55	Interlayer	Existing HMA
Location	IA 9 N to Minnesota State Line	Tie Bars	#5 bars 5' @ 30" CTR



Location		S	M	C	L	R	Overlay Quantities			Per Station		BW	E	Remarks
Road Identification	Station To Station	Inches	Inches	Feet	Feet	Feet	Class 13, ② Excavation Cu. Yds.	Unbonded PCC Overlay Sq. Yds.	Unbonded PCC Furnished Cu. Yds.	Scarification Overlay Sq. Yds.	Feet	Feet		
US 169	4400.0 - 344+65.0	5	VAR.	32	16	16	9.3	355.6	56.8	266.7	4	2		
US 169	349+90.0 - 410+94.6	5	VAR.	32	16	16	9.3	355.6	56.8	266.7	4	2		
US 169	410+94.6 - 411+74.6	5	VAR.	32	16	16	9.3	355.6	56.8	266.7	4	2	SUPERELEVATION TRANSITION	
US 169	411+74.6 - 415+05.0	5	VAR.	32	16	16	9.3	355.6	56.8	266.7	4	2	SUPERELEVATED	





Construction











2023 Review




Areas of broken panels with Durapatch.





Year	2014	Overlay Type	UBOL
County	Poweshiek	Design	5" x 32' (5" x 20' & 6" x 9.5" widening) 5 x 5 x 6' long joints
Route	US 63	Milling	0.5 to 1.5"
Project	NHSN-063-4(39)--2R-79	Interlayer	Existing HMA
Location	Montezuma N to Just south of I-80	Tie Bars	#5 bars 36" @ 30" CTR





'BAR' JOINT
DETAIL "B"

Construction 2014

HMA was thin in some areas. 1482 tons of HMA added for stress relief layer. Issues with center line rumble strip blowing out joints.















2023 Review

Lots of areas with longitudinal cracking. Some areas with broken panels.





Year	2014	Overlay Type	UBOL
County	Cherokee	Design	6" 12x12 & 6x6 Panels – 10 ft. shoulders. 44 ft. Total
Route	IA 3	Milling	2" Milling
Project	NHSX-059-7(46)--3H-18	Interlayer	Existing HMA
Location	IDA Co. Line N. to IA 3	Tie Bars	#4 bars 6' @ 30" CTR






TABLE OF DESIGN QUANTITIES										Per Station		REMARKS
ROAD IDENTIFICATION	LOCATION		SIDE	W1	W2	T1	T2	PCC OVERLAY, GPC (FLAC)	PCC OVERLAY, GPC FINISH	MILLING		
	STATION TO	STATION									Feet	
US 59	810+00	810+63.40	Rt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	Ida County Line	
US 59	0+00	266+00.63	Rt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58		
US 59	266+00.63	269+72.45	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	D63	
US 59	270+00.60	270+88.24	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	D63	
US 59	270+88.24	566+37.80	Rt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	RR Guardrail	
US 59	566+37.80	566+98.83	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	RR Guardrail	
US 59	571+15.17	571+27.34	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	RR Guardrail	
US 59	571+27.34	581+89.61	Rt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	RR Guardrail	
US 59	581+89.61	586+51.50	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	Washburn St. (S)	
US 59	586+51.50	595+35.61	Rt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58		
US 59	595+35.61	597+11.61	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	Washburn St. (N)	
US 59	597+11.61	635+82.20	Rt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	Spring Rd HMA Ent.	
US 59	635+82.20	639+47.20	Rt.	12.0	--	6.0	--	133.33	22.22	26.58	Linden St.	
US 59	259+24	267+53	Rt-C	0-24.0	--	6.0	--	107.12	17.85	34.95	US 59 & IA 31 Inter.	
US 59	267+53	269+72.45	Rt-C	24.0	--	6.0	--	266.58	44.43	86.97	US 59 & IA 31 Inter.	
US 59	270+00.60	270+88	Lt-C	24.0	--	6.0	--	267.73	44.62	87.35	US 59 & IA 31 Inter.	
US 59	270+88	281+37	Lt-C	24.0-0	--	6.0	--	133.27	22.21	43.48	US 59 & IA 31 Inter.	
US 59	810+00	810+63.40	Lt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	Ida County Line	
US 59	0+00	52+00	Lt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58		
US 59	52+00	56+47	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	D66	
US 59	56+47	268+85.88	Lt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58		
US 59	268+85.88	269+72.45	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	IA 31	
US 59	270+00.60	277+61.73	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	IA 31	
US 59	277+61.73	426+36.49	Lt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58		
US 59	426+36.49	430+92.66	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	C44	
US 59	430+92.66	566+86.66	Lt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	RR Guardrail	
US 59	566+86.66	566+98.83	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	RR Guardrail	
US 59	571+15.17	571+27.34	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	RR Guardrail	
US 59	571+27.34	632+87.20	Lt.	12.0	10.0	6.0	6.0	244.44	40.74	26.58	RR Guardrail	
US 59	632+87.20	639+47.20	Lt.	12.0	--	6.0	--	133.33	22.22	26.58	Linden Street	



Notes:

- ⑩ Sta. 810+00 to Sta. 426+36.49
Longitudinal joints shall be located at centerline, 6.0-ft Lt. and Rt. of centerline, 12.0-ft Lt. and Rt. of centerline, and 17.0-ft Lt. and Rt. of centerline. A modified 'L-1' (ML-1) joint shall be located at 12.0-ft Lt. and Rt. of centerline with a 6-ft. long reinforcing bar. Transverse joints shall be located at 6.0-ft. spacings. See 'EX-JNT A' on Sheet B.4.
- ⑪ Sta. 426+36.49 to Sta. 639+47.20
Longitudinal joints shall be located at centerline, 12-ft Lt. and Rt. of centerline. A modified 'L-1' (ML-1) joint shall be located at 12.0-ft Lt. and Rt. of centerline with a 6-ft. long reinforcing bar. Transverse joints shall be located at 10.0-ft. spacings. See 'EX-JNT B' on Sheet B.4.
- ⑫ Shoulder material as specified elsewhere in these plans; refer to typical 7145 on Sheet B.3.
- ⑬ Quantity is estimated using a 6-in. thickness over the existing 24-ft. wide pavement and a 10-in. thickness for the integral 2-ft. widening units.
- ⑭ Refer to 'EX-JNT' on B.4 for rebar placement.
- ⑮ Slope shall be 3% on 'Turn Lanes' and 4% on shoulders.

Sta. 810+00 to 426+36




Sta. 426+36 to 639+47



Construction

Placed half width.








Review 2021

Areas of cracking at quarter point. Some broken panels.



Year	2015	Overlay Type	UBOL
County	Polk	Design	5" x 36' (5" x 20' & 8' x 9.5" widening) 5 x 5 x 6' long joints
Route	US 69	Milling	0.5" to 2" milling
Project	STPN-069-4(100)--2J-77	Interlayer	Existing HMA
Location	118th Ave N. to Just S. of IA 210	Tie Bars	#5 bars 36" @ 30" CTR





Construction

Placed half width. Some random cracking off sawed joints.








Review 2021

Longitudinal cracking in wheel path.







Shoulder cross slope 3.5%, Design 4%

Year	2015	Overlay Type	UBOL & WT
County	Clay	Design	6" x 32' (9 x8' panels ML & 7x8' panels shoulders) UBOL 6" x 32' (6 x 6' ML and 4 x 6' Shoulder) WT
Route	US 71	Milling	2" Milling
Project	NHSX-071-8(59)--3H-21	Interlayer	Existing HMA
Location	B53 N to 15th St in Spencer	Tie Bars	L-1 #4 @30" 6' – UBOL L-1 #4 @30" 3' WT

Typical Cross Section – UBOL




TYPIC UNBOI OVER C




Notes:

Modified 'L-1' (ML-1) joint #4 Bars at 30" on center spacing with a 6-ft long reinforced bar centered over widening unit (10.5' Lt. and Rt. of centerline). Maintain minimum 6-in clearance from transverse joints. Minimum 3 staples per Tiebar. Slapping process subject to Engineer approval prior to Paving operation. Approval is based on no tiebar movement during Paving operation. Mechanical insertion of the tie bar is allowed.

TYPIC AN





Typical Cross Section WT



ROAD IDENTIFICATION	LOCATION		Per Station				PCC OVERLAY, 5% FURFISH (CY)	PCC OVERLAY, 5% FURFISH (CY)
	STATION TO STATION		(D)	(L)	(T)	(T)		
US 71	371+48	375+00	33	12	12	6.0	355.56	59.26
US 71	498+00	522+00	30	12	12	6.0	355.56	59.26
US 71	595+00	584+00	32	12	12	6.0	355.56	59.26
US 71	631+00	648+75	34	12	12	6.0	355.56	59.26
US 71	664+00	678+00	32	12	12	6.0	355.56	59.26

TYPIC



- Notes:
- 1) Extend existing expansion joints in kind in new pavement.
 - 2) Modified "L-1" (ML-1) Joint HMA Bars at 30" on center spacing with a 3-ft long reinforcing bar centered over joint. Maintain minimum 6-in clearance from transverse joints. Minimum 3 staples per Tiebar. Stapping process subject to Engineer approval prior to Paving operation. Approval is based on no tiebar movement during Paving operation.
- Longitudinal joints shall be located at centerline, 6.0-ft Lt. and Rt. of centerline and 12.0-ft Lt. and Rt. of centerline. A modified "L-1" (ML-1) joint shall be located at 12.0-ft Lt. and Rt. of centerline with a 3-ft. long reinforcing bar. Transverse joints shall be located at 6.0-ft. spacings.
- Mechanical insertion of tie bar is allowed.

TY
AI
PC

Milepost	Existing Pavement Type
188.13-190.29	Composite
190.29-192.21	HMA
192.21-193.80	Composite
193.80-195.06	HMA

Construction





2023 Review

Overall, both the UBOL and WT are in very good condition.




UBOL Overlay section



Whitetopping Overlay section



Year	2016	Overlay Type	UBOL & WT
County	Clay	Design	6" x 32' (9 x8' panels ML & 7x8' panels shoulders) UBOL 6" x 32' (6 x 6' ML and 4 x 6' Shoulder) WT
Route	US 71	Milling	2" Milling
Project	NHSX-071-8(58)--3H-21	Interlayer	Existing HMA
Location	Buena Vista Co. Line N. to Co. Rd. B53	Tie Bars	L-1 #4 @30" 6' – UBOL L-1 #4 @30" 3' WT

Typical Cross Section - UBOL



ROAD IDENTIFICATION	LOCATION	STATION TO STATION	Per Station				PCC OVERLAY, GNC #LACE) sq. yds	PCC OVERLAY, GNC FURSH) sq. yds
			(D) Panel	(L) Panel	(E) Panel	(T) Panel		
US 71	18+45	119+00	32	12	12	6.0	355.56	59.28
US 71	211+00	228+56	32	12	12	6.0	355.56	59.28
US 71	238+05	278+00	32	12	12	6.0	355.56	59.28
US 71	279+00	305+00	32	12	12	6.0	355.56	59.28


TYP
UNE
OVER



- Notes:
-) Extend existing expansion joints in kind in new pavement.
 -) Modified "L-1" (ML-1) joint #4 Bars at 30" on center spacing with a 6-ft long reinforced bar centered over widening unit (10.5' Lt. and Rt. of centerline). Maintain minimum 6-in clearance from transverse joints. Minimum 3 staples per Tiebar. Stapling process subject to Engineer approval prior to Paving operation. Approval is based on no tiebar movement during Paving operation. Mechanical insertion of tie bar is allowed.
 -) See ML-2 on Sheet B.2.



TYPICAL CR
AND JOINT
PCC UNBOND
OVER EXISTIN

Typical Cross Section – WT



ROAD IDENTIFICATION	LOCATION	STATION TO STATION	Per Station			PCC OVERLAY, 6" THICK	PCC OVERLAY, 6" THICK
			①	②	③		
US 71	114+00	221+00	32	12	12	6.0	355.56
US 71	204+00	272+00	32	12	12	6.0	355.56
US 71	394+00	568+00	32	12	12	6.0	355.56

TYPIC



- Notes:
- Extend existing expansion joints in kind in new pavement.
 - Modified 1-1/2" (M-1) joint #4 Bars at 30" on center spacing with a 3-ft long reinforced bar centered over joint. Maintain minimum 6-in clearance from transverse joints. Minimum 3 staples per Tiebar. Stapling process subject to Engineer approval prior to paving operation. Approval is based on no tiebar movement during Paving operation.
Longitudinal joints shall be located at centerline, 6.0-ft Lt. and Rt. of centerline and 12.0-ft Lt. and Rt. of centerline.
A modified 1-1/2" (M-1) joint shall be located at 12.0-ft Lt. and Rt. of centerline with a 3-ft long reinforcing bar. Transverse joints shall be located at 6.0-ft spacings.
Mechanical insertion of the bar is allowed.

TYPICAL CF AND JOINT PCC UNBON OVER EX1

Construction



Review 2023

Overall, both the UBOL and WT are in very good condition.




Whitetopping overlay section





Unbonded overlay section

Year	2016	Overlay Type	UBOL
County	Benton	Design	5.5" x 32' (6 x 6' ML and 4 x 6' Shoulder)
Route	IA 21	Milling	n/a
Project	STPN-021-4(27)--2J-06	Interlayer	New HMA
Location	From E66 N. to just S. US 30	Tie Bars	#4x36" @30" C-C



Location		Overlay Quantities (Per Location)									Remarks
Road	Station To Station	(S)	(C)	(L)	(R)	(1)	PCC Overlay	PCC Overlay	(T)	(BW)	
		Inches	Feet	Feet	Feet	Class 13	Dia. Yds.	Sq. Yds.	Inches	Feet	Feet
JA 21	72+65 to 247+25	5.5	32.0	16.0	16.0	1347	10,563	62,080	8	4.0	6.0
		approx. MP 57.82 to MP 61.18									
		17,460' ± 2x8.167sf/27= 10,563 CY PCC									
		17,460' ± 2x1,042sf/27= 1348 CY CI 13									





Construction






Review 2023


Overall, the overlay is in very good condition.



Year	2018	Overlay Type	UBOL
County	Dallas/Boone	Design	7" x 32' (12 x 12' ML and 4 x 12' Shoulder)
Route	US 169	Milling	n/a
Project	NHSX-169-4(63)--3H-25	Interlayer	Fabric Interlayer
Location	IA 141 N to US 30	Tie Bars	



Location		(S)	(C)	(L)	(R)	(T)	(BW1)	(BW2)	(G)
Road	Station to Station	Inches	Feet	Feet	Feet	Inches	Feet	Feet	Feet
US 169	26+12.6 - 62+94	75.0	32.0	16.0	16.0	9.5	4.0	4.0	Vari.
US 169	91+01 - 710+00	74.0	32.0	16.0	16.0	9.5	4.0	4.0	Vari.



Location		(S)	(C)	(L)	(R)	(T)	(BW1)	(BW2)	(G)
Road	Station to Station	Inches	Feet	Feet	Feet	Inches	Feet	Feet	Feet
US 169	73+61 - 91+01	75.0	32.0	16.0	16.0	9.5	4.0	4.0	Vari.

Review 2021

Lots of longitudinal cracking.








Shoulder cross slope 1.2%, Design 2%.

2023



Lots of longitudinal cracking. Most have been sealed.



Year	2019	Overlay Type	UBOL
County	Marshall/Tama	Design	6" x 32' (6 x 6' ML and 4 x 6' Shoulder)
Route	IA 14	Milling	1" Milling
Project	HSPIX-014-5(81)--3H-64	Interlayer	Existing HMA
Location	Co. Rd. E18 N. to W. JCT IA 175	Tie Bars	Shoulder not tied



Location	Station To Station	Inches	C	L	R	S	T	Division 1 Overlay Quantities Per Location			Division 2 Overlay Quantities Per Location			Remarks	
								PCC Overlay Cu. Yds.	PCC Overlay Sq. Yds.	Class 13 Cu. Yds.	PCC Overlay Cu. Yds.	PCC Overlay Sq. Yds.	Special Backfill Cu. Yds.		
IA 14	371+50.00	447+75.63	6	32	16	16	4	4	3165	15012	1745	1056	6337	1745	
	37+33.40	462+1.50	6	32	16	16	4	4	1965	11728	1077	662	4079	1077	St. Turn Lane Lane
	467+7.50	489+5.50	6	32	16	16	4	4	1458	852	23	18	157	23	St. Turn Lane Lane
	484+5.50	52400.00	6	32	16	24			235	1292	115	52	235	119	Excludes St. Turn Lane
	52400.00	56450.00	6	32	16	16	4	4	1875	11292	1033	645	3951	1033	
	152+57.40	503+00.00	6	32	16	16	4	4	18502	113315	10279	6184	37405	10279	



Construction





Review 2021

In very good condition. Shoulders do appear to be heaving, but no cracking due to no tie steel.



Sta 33+00 Mainline 1.9%



Sta 33+00




Station 412+00

2023

Still performing very well.





Year	2020	Overlay Type	WT
County	Woodbury	Design	6" x 32' (6 x 6' ML and 2 x 6' Shoulder)
Route	IA 31	Milling	3" Milling
Project	STP-031-1(43)--2C-97	Interlayer	Existing HMA
Location	E. JCT US 20 N. to Co. Rd. C66	Tie Bars	Fiber Test Sections



LOCATION		Per Station				PCC OVERLAY (P.L.A.C.E.S)	PCC OVERLAY (P.L.A.C.E.S)
ROAD IDENTIFICATION	STATION TO STATION	L	R	T1	T2	Sq. Yds.	Sq. Yds.
IA 31	43+76 - 277+54	12	12	6	8	333.3	57.64
(A. 3)	278+53 - 319+45.5	12	12	6	8	333.3	57.64
(A. 3)	318+58.5 - 458+50	12	12	6	8	333.3	57.64

TYPIC
UNBONDED
FULL D





Notes:

L-1 joint shall use detail D-1 as shown on PY-101. No tie bars to be used except as stated in note (2).

An "L-1" joint shall be located at 12.0-ft. Lt. and Rt. of centerline with a 3-ft. long reinforcing bar.

Reinforced bars shall be #4 Bars at 30" on center spacing with a 3-ft long reinforcing bar centered over joint. Maintain minimum 6-in clearance from transverse joints. Minimum 3 staples per Tiebar. Stapling process subject to Engineer approval prior to Paving operation. Approval is based on no tiebar movement during Paving operation.

Mechanical insertion of tie bar is allowed.

**TYI
AN
PC**

Macro Fiber Test Sections

Begin Sta.	End Sta.	Length feet	PCC SY	PCC CY	Fiber lbs	Transverse Sawcut Spacing FT	Longitudinal Sawcut Spacing FT	Remarks
43+76	50+00	624	2079.8	359.7	1438.7	6	6	Use Detail EX-JNT A on sheet B.2
142+00	152+00	1000	3333.0	576.4	2305.6	15	12	Use Detail EX-JNT B on sheet U.1
152+00	162+00	1000	3333.0	576.4	2305.6	12	12	Use Detail EX-JNT B on sheet U.1
162+00	172+00	1000	3333.0	576.4	2305.6	9	12	Use Detail EX-JNT B on sheet U.1
172+00	182+00	1000	3333.0	576.4	2305.6	9	6	Use Detail EX-JNT B on sheet U.1
182+00	192+00	1000	3333.0	576.4	2305.6	6	6	Use Detail EX-JNT B on sheet U.1
423+00	441+00	1800	5999.4	1037.5	4150.1	6	6	Use Detail EX-JNT A on sheet B.2

Construction








Review 2021


Overall, the overlay is in very good condition.





Year	2022	Overlay Type	UBOL
County	Cherokee	Design	6" x 28' (12' x12' ML and 2 x 12' Shoulder), Fibers – 4 lb/cy
Route	IA 31	Milling	3" Milling
Project	STP-031-3(11)--2C-18	Interlayer	Existing HMA
Location	Washta to US 59	Tie Bars	L-1, 3 ft @ 30" centers






2022 Review

Overall, the overlay is in very good condition. A few areas with random cracking off sawed joints. Issues with center line rumble strip depth and crossing joint.






Year	2022	Overlay Type	WT
County	Plymouth	Design	6" x 36' (6 x 6' ML and 6 x 6' Shoulder) 12x12 Test Section
Route	IA 3	Milling	2" Milling
Project	NHSX-003-1(106)--2R-75	Interlayer	Existing HMA
Location	Lemars to Remsen	Tie Bars	L-1, 3 ft @ 30" centers





LOCATION			PER STATION				CLASS 13 Cu. Yds. (1)	BLADE SHARPING Sta. (2)	MILLING Sq. Yds.
ROAD IDENTIFICATION	STATION TO STATION		(L) Feet	(R) Feet	(M1) Inches	(M2) Inches			
IA 3	819+62.39	851+99.31	12	12	2	2	14.81	2.50	286.67
IA 3	851+61.52	1014+12.77	12	12	2	2	14.81	2.50	286.67
IA 3	1014+11.66	1244+00	12	12	2	2	14.81	2.50	286.67
IA 3	1244+00	1273+00	12	12	2	2	14.81	2.50	286.67

TYPI



LOCATION			PER STATION				PCC OVERLAY (P.L.CE) Sq. Yds.	PCC OVERLAY (FURNISH) Sq. Yds.
ROAD IDENTIFICATION	STATION TO STATION		(L) Feet	(R) Feet	(T1) Inches	(T2) Inches		
IA 3	819+62.39	851+99.31	12	12	6	9	400	77.78
IA 3	851+61.52	1014+12.77	12	12	6	9	400	77.78
IA 3	1014+11.66	1244+00	12	12	6	9	400	77.78
IA 3	1244+00	1273+00	12	12	6	9	400	77.78





Construction

Overlay was placed full width to be able to place shoulders as soon as 325 psi maturity was reached. Goal was to pave ~1 mile per day and fully open each section within 2 days after paving. The test section of 12 x 12 foot panels is located between Otter Ave. and Oyens Ave. (~Sta 1028+00 to 1038+00).






2022 Review



Overall, the overlay is in very good condition.




Year	2022	Overlay Type	UBOL
County	Tama/Blackhawk	Design	5" x 32' (6 x 6' ML and 4 x 6' Shoulder)
Route	US 63	Milling	1" Milling
Project	NHSX-063-5(72)--3H-86	Interlayer	Existing HMA
Location	Traer to 0.5 mi S of IA 58	Tie Bars	Fibers 5 lb/cy – No Tie Steel



Location		(M)	(C)	Remarks
Road Identification	Station To Station	Inches	Feet	
US 63	131+25.40	493+88.60	1	32.0 EQUATION $493+88.60(RK) = 0+000(AH)$
US 63	0+00	332+36	1	32.0 EQUATION $493+88.60(RK) = 0+000(AH)$





Construction





2023 Review

Overall, the overlay is in very good condition.



Year	2023	Overlay Type	WT
County	Plymouth	Design	6" x 36" (12 x 12' ML and 6' x 12' Shoulder)
Route	IA 3	Milling	3" Milling
Project	NHSN-003-1(104)--3H-75	Interlayer	Existing HMA
Location	Remsen to Co. Line	Tie Bars	Fibers 4 lb/cy #4 x 36" at 30" C-C






TABLE OF DESIGN QUANTITIES			Per Station					
LOCATION			L	R	T1	T2	PCC OVERLAY, GMC (PLACE)	PCC OVERLAY, GMC (FURNISH)
ROAD IDENTIFICATION	STATION TO STATION		Feet	Feet	Inches	Inches	Sq. Yds.	Cu. Yds.
IA 3 DIV. 1	1315+30	1332+78	12	12	6	9	266.67	44.44
IA 3 DIV. 2	1332+78	1596+74	12	12	6	9	266.67	44.44



- Notes:
- ① L-1 joint shall use detail D-3 as shown on PP-101. No tie bars to be used except as stated in note ②.
 - ② An 'L-1' joint shall be located at 12.0-ft. Lt. and Rt. of centerline with a 3-ft. long reinforcing bar.
- Reinforced bars shall be #4 Bars at 30" on center spacing with a 3-ft long reinforcing bar centered over joint. Maintain minimum 6-in clearance from transverse joints. Minimum 3 staples per Tiebar. Stapling process subject to Engineer approval prior to Paving operation. Approval is based on no tiebar movement during Paving operation.
- Mechanical insertion of tie bar is allowed.

T
A
PI

Construction



2023 Review




Appendix C – Old Pavement Resurfacing Designs

Design No. R-1
First used in letting of 5-10-32


R-1

Dubuque FA 148 D 8.365

Similar to Design No R2 except
for the details below




Tin strips 8" x 10' - 30 gauge - oiled
lapped at $\frac{3}{4}$ ", bent over edge to subgrade
Subgrade paper



Design No. R-2
 First used in letting of 9-12-33


R-2

Cerro Gordo	NRH 1 B	1.059
Winnebago	NRM 139	0.294
Woodbury	P 45	1.8015




U bars placed thus - alternate bars reversed due to variations in old slab on Cerro Gordo N.R.H. 1 B




3/4" Expansion joints @ 61'-6" U bars designed thus



R-3





Expansion joint U bars $\frac{3}{8}\phi \times 7'-0"$



Design No. R-4
First used in letting of 1-29-35

R-4

Dubuque NRM 17 DEF 1.995





Design No. R-5
 First used in letting of 1-29-35

R-5

Dubuque NRM 17 DEF 1.995



slab thickness
 inches → 10 7



Design No R-6
 First used in letting of 6-29-36

R-6



Des Moines WPMH 572B 0.933



Design No. R-7
First used in letting of 4-21-42

R-7


Des Moines DAVI-2 2.045



Design No. R - 8
 First used in letting of

Plymouth U-38 (b)


R-8



Construction Joints
 $8 - \frac{3}{8}'' \phi \times 18''$ dowels

Welded Assemblies - $8 - \frac{3}{4}'' \phi \times 24''$ dowels
 to $2 - \frac{3}{8}'' \phi \times 9'$ bars

Exp. tubes at E.J.



Welded mesh
 $19 - \#4$ wires at 6" cc. long.
 $16 - \#4$ " " 12" cc transv.
 Mats lapped one transv. wire.

Mesh 2" from jt.
 Mesh 2" from top.
 Center of dowels $2\frac{1}{2}''$ from top - "A"
 " " " 4" " " " "B"




Design No. R-9

First Used in Letting of 7-19-49

Benton
Benton

F 233(2)
F 278(2)

R 9




Design No. R-10

First Used in Letting of 8-1-50


Linn

F-96(11) 4.312 Miles 1950



R10



Contraction Joints at 16'-4" intervals



R-11




First Used in Letting of 6-6-50

Linn


U-22(5)

R-12





Center 24'

Lt. + Rt. 24' Unit




Design R 13 Width 24 Ft Min 6" Edge 10"
First used in letting of 7-6-50
Page U 651(4) 0.989 Miles 1950

R-13




Appendix D – Iowa County IA 21 Whitetopping Overlay Test Sections


Whitotopping Research Location
Iowa County IA 21
STP-21-3(10)—2C-48



WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT



WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT




16


WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT

SECTION	STATION	PREP.	PAVEMENT THICKNESS	FIBERS	JOINT SPACING			
24	2456 + 00	PATCH AND SCARIFY	6"	NF	6'			
25	2458 + 00							
25	2460 + 00							
26	2468 + 00	PATCH ONLY	6"	NF	12'			
27	2479 + 00							
28	2480 + 00							
29	2487 + 00							
30	2489 + 00							
31	2496 + 00							
32	2503 + 00							
33	2505 + 00							
34	2515 + 00					4.5"	ACC	N/A


WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT



WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT



WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT



WHITETOPPING RESEARCH
 STP-21-3(10)--2C-48
 IOWA COUNTY
 TEST SECTION LAYOUT

SECTION	STATION	PREP.	PAVEMENT THICKNESS	FIBERS	JOINT SPACING
61	2689 + 00 2691 + 00	COLD	2"	NF	4'
62					
63	2698 + 00 2700 + 00	-IN- PLACE	4.5"	ACC	N/A
64	2704 + 00				
65	2714 + 00	RECYCLE			