

TE  
191  
.T43  
A34  
2001/02

# **LEVEL I & II AGGREGATE INSTRUCTION MANUAL**

**2001/2002**

**TECHNICAL TRAINING  
AND  
CERTIFICATION  
PROGRAM**



**HIGHWAY DIVISION**







## **TABLE OF CONTENTS**

	<b>Page</b>
<b>I.M. 213-Aggregate Technician's Certification Program .....</b>	<b>1</b>
<b>I.M. 209-Certified Aggregates Testing and Certified Aggregates .....</b>	<b>21</b>
Appendix A.....	26
Appendix B.....	31
Appendix C.....	39
 <b>Section I-Aggregates .....</b>	 <b>45</b>
Aggregates Defined.....	45
Natural Aggregates .....	46
Synthetic Aggregates .....	46
Manufactured Aggregates .....	46
Natural Sands and Gravels .....	46
Aggregate Uses .....	47
 <b>Section II-Sampling Methods and Equipment .....</b>	 <b>49</b>
Introduction .....	49
Importance of Proper Sampling.....	49
Sampling Frequency.....	49
Random Sampling.....	50
Location for Sampling.....	51
Sample Records .....	52
Review.....	54
 <b>I.M. 208-Materials Laboratory Qualification Program .....</b>	 <b>56</b>
<b>I.M. T-203-General Aggregate Source Information .....</b>	<b>70</b>
<b>I.M. 204-Inspection of Construction Project Sampling and Testing Purpose .....</b>	<b>111</b>
<b>I.M. 301-Aggregate Sampling Methods and Determination of Minimum Size of Samples for Sieve Analysis.....</b>	 <b>176</b>
 <b>Section III-Aggregates Properties and Characteristics .....</b>	 <b>180</b>
Aggregate Production Problems .....	180
Deleterious Material.....	182
Resistance to Abrasion.....	182
Los Angeles Abrasion Test .....	182
Durability and Soundness.....	183
Method of Test for Determining the Soundness of Aggregates by Freezing and Thawing.....	 185
Specific Gravity .....	186
Aggregate Moisture.....	187
Unit Weight .....	189
Shape and Surface Texture.....	189
Gradation .....	190
Dense Graded Aggregate .....	190
Gap Graded Aggregate .....	190
Plasticity Index .....	190



Summary.....	191
<b>Section IV-Sieve Analysis</b> .....	193
General Requirements.....	193
<b>I.M. 336-Methods of Reducing Aggregate Field Samples to Test Samples</b> .....	196
<b>I.M. 302-Method of Test Sieve Analysis of Aggregates</b> .....	202
<b>I.M. 306-Method of Test to Determine the Amount of Material Finer Than the 75 <math>\mu</math>m (#200) Sieve in Aggregate</b> .....	214
<b>I.M.216-Guidelines For Verifying Certified Testing Results</b> .....	218
<b>I.M. 307-Method of Test Specific Gravity of Aggregates</b> .....	225
Specific Gravity Problems.....	230
<b>I.M. 308-Method of Test Determination of Free Moisture and Absorption of Aggregates</b> .....	232
Moisture Tests Problems .....	237
<b>Section V-Aggregate Source Inspection</b> .....	239
Introduction .....	239
Quarries .....	239
Ledge Control .....	240
Lateral Variations.....	244
Lateral Variations Due to Weathering .....	245
Faulted and Dipping Beds .....	245
Deleterious Materials .....	248
Production Changes .....	248
Sand and Gravel Pits .....	251
<b>I.M. 104-Field Equipment Cleaning, Calibration, and Repair</b> .....	254
<b>I.M. 344-Method of Test for Determination of the Amount of Shale in Fine Aggregate</b> .....	257
<b>I.M. 345-Method of Test for Determination of the Amount of Shale in Coarse Aggregate</b> .....	260
<b>Appendix A-Forms</b>	
Aggregate Sieve Analysis.....	263
Certified Gradation Test Report .....	269
PCC Plant Report.....	271
ACC Plant Report .....	272
Sieve Analysis Worksheet Problems .....	275
Sieve Analysis Worksheet Blanks .....	283
Course Evaluation.....	286



October 2, 2001  
Supersedes October 3, 2000

Office of Materials

Matls. I.M. 213

---

## **TECHNICAL TRAINING AND CERTIFICATION PROGRAM**

### **(General Rewrite)**

#### **GENERAL**

The purpose of the Technical Training and Certification Program is to ensure Quality Control (QC)/Quality Assurance (QA) and Acceptance of Aggregates, Hot Mix Asphalt (HMA), Portland Cement Concrete (PCC), Grade Inspection, Precast and Prestressed Concrete, and Pavement Profiles and to ensure proper documentation of Quality Control/Quality Assurance and Acceptance procedures and test results by industry and contracting authority personnel.

This Instructional Memorandum (I.M.) explains the requirements to become certified and to remain certified to perform inspection and testing in the state of Iowa. This I.M. also describes the duties, responsibilities and the authority of persons assigned the position of Certified Technician in any of the above areas for construction or maintenance projects. Appendix C of this I.M. lists what tests and procedures the technician is qualified to perform for each level of certification they obtain.

Through a cooperative program of training, study, and examination, personnel of the construction industry, State DOT, and other contracting authorities will be able to provide quality management and certified inspection. Quality Control/Quality Assurance and Acceptance testing and inspection will be performed by certified personnel and documented in accordance with the I.M.'s.

A technician who is qualified and holds a valid certification(s) shall perform Quality Control/Quality Assurance and Acceptance at a production site, proportioning plant, or project site. Responsibilities cannot be delegated to non-certified technicians. The duties of a Certified Technician may be assigned to one or more additional Certified Technicians.

The Technical Training and Certification Program will be carried out in accordance with general policy guidelines established or approved by the Highway Division Director. The Director will be advised by a Board of Certification composed of the following members:

- Director – Office of Materials
- Director – Office of Construction
- Representative of District Materials Engineers\*\*
- Representative of District Construction Engineers\*\*
- Representative of Associated General Contractors (AGC of Iowa)
- Representative of Iowa Concrete Paving Association (ICPA)
- Representative of Asphalt Paving Association of Iowa (APAI)
- Representative of Iowa Ready Mixed Concrete Association (IRMCA)
- Representative of Iowa Limestone Producers Association (ILPA)
- Representative of County Engineers
- Coordinator of Technical Training and Certification Program\*\*

\*\* Appointed by Program Director



The Director of the Office of Materials will be the Program Director. Coordinators will be appointed by the Program Director to assist in administration of the program and to handle such planning, administration, and coordinating functions as may be needed.

Appeals on actions taken in this program shall be submitted to the Program Director. Unresolved appeals will be submitted to the Certification Board.

### **TRAINING**

The training necessary to become certified will be provided by the Iowa DOT or an agency approved by the Program Director. Producers/Contractors are encouraged to conduct their own pretraining program. A complete listing of training opportunities is available in the Technical Training and Certification Program's Information and Registration Booklet published each fall. This book is available at any of the Iowa DOT Materials Offices. They may also be obtained from the ICPA, IRMCA, ILPA, and APAI.

### **CERTIFICATION REQUIREMENTS**

1. A candidate must attend instruction and pass the examination(s) for all levels of certification prepared and presented by the Program Director or someone designated by the Program Director. If the new candidate fails the examination, they will have one opportunity to retake the examination. The retake must be completed within 6 months of the original exam. If they fail the retake of the examination, they will need to attend the training again before taking the examination the third time. If an individual is recertifying they will have only one opportunity to take the examination. If they fail the examination they must take the applicable training before retaking the examination.
2. All prerequisites shall be met before the applicant may attend the next level of training for the certification desired. A listing of certification levels and prerequisites is located in Appendix A.
3. Once the candidate has met all the criteria and has received certification, it is recommended the Certified Technician work under the supervision of an experienced technician until they become efficient in the inspection and testing methods they will be performing.  
An individual requesting to become certified as a Precast/Prestress Concrete Technician is required to obtain forty hours of experience assisting in quality control inspection at an approved plant before certification will be issued. The experience must be documented and shall be approved by the District Materials Engineer. This experience must be completed within two years from the date the individual attended the training.
4. Registered professional engineers, engineering graduates, and geology graduates from accredited institutions will be exempt from the training requirement in the areas they have had instruction. In order to obtain certification for any technical level, these persons must pass all applicable tests for the level of certification they wish to obtain. All certificates issued in accordance with these requirements will be subject to the same regulations concerning expiration, recertification, etc., as applies to certificates obtained via training and examinations.

Out-of-state technicians will be issued certifications when the following criteria are met:



1. The applicant must be certified in another state or shall have received equivalent training, if the state does not have a certification program, in each level of certification they are requesting.
2. The applicant must pass an examination for each level of certification desired, which will be administered by the Iowa Department of Transportation.
3. The applicant must follow the prerequisite requirements of the Technical Training and Certification Program.

Out-of-state applications should be submitted to the Iowa DOT Materials Office in Ames, Iowa to schedule test dates. Copies of all the applicant's certifications must accompany the application.

### **CERTIFICATION**

Upon successfully completing the requirements for certification, the Program Director will issue a certificate and a pocket certification card. This certification is not transferable. A certification shall be valid for five years.

### **CERTIFICATION IDENTIFICATION**

The certificate will contain letters that identify the District of record, the certificate holder, certification number, the level of certification, and the expiration date of each level.

The assigned certification number may change if the certificate holder changes their residence.

### **RENEWAL OF CERTIFICATION**

A certification shall be valid through December 31<sup>st</sup> of the fifth year. A 90-day grace period will be allowed. If the individual has not renewed their certification within the 90-day grace period, they are automatically decertified. The individual may obtain certification by taking the examination for the level of certification they are requesting. If the individual does not take the examination within one year after they are decertified in any level of certification, they must retake all applicable schooling and pass the examinations. If an applicant becomes decertified in any level of certification, and that certification is a prerequisite for other levels of certification the applicant will also be decertified in those related levels of certification.

All Certified Technicians will be required to pass an examination in each level of certification they hold before recertification will be issued. Failure of any level shall require the applicant to retake the applicable schooling and pass the test.

The certificate holder shall be responsible for applying for certification renewal and for maintaining a current address on file with the appropriate District Materials Office.

Technicians certified as Level I HMA and/or Level II PCC shall attend a minimum of two update classes each in the five-year period between certification and each recertification. These classes will be held by the Iowa DOT or an agency or organization approved by the TTCP. These update classes will be listed in the Technical Training and Certification Booklet, or the Certified Technician may contact the Iowa DOT for information. If an individual does not attend the two update classes required before their certification expires, they must take the entire schooling and pass the examination for the certification required.



---

The Certified Technician will not receive credit for the following:

1. More than one update per training season in each level of certification.
2. An update taken during the same training season in which the individual re-certified.

### **PERFORMANCE REQUIREMENTS**

A written notice may be issued to the Certified Technician for any inadequacies performed during their duties. Upon receipt of two such notices, the Certified Technician may be given a three-month suspension. After receiving three notices, the Certified Technician is subject to decertification. An example of this notice is shown in Appendix B.

### **DECERTIFICATION**

The certificate will become invalid for the following reasons:

1. Failure of the certificate holder to renew the certificate prior to regular expiration as described above.
2. Use of false or fraudulent information to secure or renew the certificate.
3. Use of false or fraudulent actions or documentation by the certificate holder.
4. Not performing tests and technician duties properly and in accordance to specifications.

### **FUNCTIONS AND RESPONSIBILITIES**

A certificate holder at each production site, project site, proportioning plant, or laboratory will perform duties. The Certified Technician shall perform quality control testing in accordance with specified frequencies and submit designated reports and records.

The specification requirement for materials testing by a Certified Technician does not change the supplier's responsibilities to furnish materials compliant with the specification requirements.

The District Materials Engineer and/or Project Engineer will be responsible for monitoring the sampling, testing, production inspection activities and Quality Control performed by the contractor. A monitor shall have satisfactorily completed the training and be certified for the level of technician they are monitoring.

The District Materials Engineer and/or Project Engineer will have authority and responsibility to question and where necessary, require changes in operations and Quality Control to ensure specification requirements are met.

### **QUALITY CONTROL, TESTING, AND DOCUMENTATION**

The QC Technician shall be present whenever construction work related to production activity, such as stockpiling or other preparatory work, requires record development and/or documentation is in progress. The QC Technician's presence is normally required on a continuing basis beginning one or more days before plant operation begins and ending after



---

plant shut down at the completion of the project. The work shall be performed in a timely manner and at the established frequencies.

The QC Technician's presence is not normally required during temporary plant shut downs caused by conditions, such as material shortages, equipment failures, or inclement weather.

All Quality Control activities and records shall be available and open for observation and review by representatives of the contracting authority.

Reports, records, and diaries developed during progress of construction activities will be filed as directed by the contracting authority and will become the property of the contracting authority.


Quality Control activities, testing, and records will be monitored regularly by contracting authority representatives. The Project Engineer or District Materials Engineer will assign personnel for this function.

Monitor activities will be reported and filed at prescribed intervals with the Project Engineer, District Materials Engineer, producer, contractor, and the contractor's designated producer.

At no time will the monitor inspector issue directions to the contractor, or to the QC Technician. However, the monitor inspector will have the authority and responsibility to question, and where necessary, reject any operation or completed product, which is not in compliance with contract requirements.

#### **ACCEPTANCE**

Completed work will be accepted on the basis of specification compliance documented by acceptance test records, and monitor inspection records. Specification noncompliance will require corrective action by the producer, contractor, or by the contractor's designated producer, and review of events and results associated with noncompliance by the Project Engineer.





---

**CERTIFICATION LEVELS**

<b><u>CERTIFICATION LEVEL</u></b>	<b><u>TITLE</u></b>	<b><u>PRE-REQUISITES</u></b>
<b><u>AGGREGATE</u></b>		
Level I Aggregate	Certified Sampling Technician	None
Level II Aggregate	Certified Aggregate Technician	Level I Aggregate
<b><u>PORTLAND CEMENT CONCRETE</u></b>		
Level I PCC**	PCC Testing Technician	None
Level II PCC	PCC Plant Technician	Level II Aggregate & Level I PCC
Level III PCC	PCC Mix Design Technician	Level II PCC
** American Concrete Institute (ACI) Grade I certification will be acceptable as a portion of the Level I PCC training.		
<b><u>HOT MIX ASPHALT</u></b>		
Level I HMA	HMA Technician	Level II Aggregate
Level II HMA	HMA Mix Design Technician	Level I HMA
<b><u>PROFILOGRAPH</u></b>		
Profilograph	Profilograph Technician	None
<b><u>PRESTRESS</u></b>		
Prestress	Prestress Technician	Level I PCC or ACI Grade I <i>If the technician will be performing gradations, they will need to be Aggregate Level II certified.</i>





---

**UNSATISFACTORY PERFORMANCE NOTICE**

Issued To: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Date: \_\_\_\_\_

This notice is to inform you that your performance as a Certified Inspector/Technician was unsatisfactory for the reason(s) listed below. After receipt of two such notices you may be give a three-month suspension. After three notices, you are subject to decertification

This notice will be placed in your permanent file with the District Materials Office in which you reside. It will also be placed on the statewide computer file.

The goal of the Technical Training and Certification Program (TTCP) is to work with contractors, producers, cities, and counties to continually improve the quality of Iowa's construction projects. We hope you will work with us to achieve this goal.

Unsatisfactory Performance:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

\_\_\_\_\_  
District Materials Engineer

cc: Program Director – Materials Engineer Ames  
TTCP Coordinator  
Resident Construction Engineer





## **CERTIFIED TECHNICIANS QUALIFICATIONS**

Tests and Procedures the Certified Technician is qualified to perform for each Level of Certification.

### **LEVEL I AGGREGATE**

- I.M. 204 – Inspection of Construction Projects Sampling and Testing (when material is incorporated)
- I.M. 209 Appendix C – Aggregate Specification Limits and Sampling and Testing Guide (when material is produced)
- I.M. 301 – Aggregate Sampling Methods

### **LEVEL II AGGREGATE**

- I.M. 216 – Guidelines for Verifying Certified Test Results
- I.M. 302 – Method of Test Sieve Analysis of Aggregates
- I.M. 306 – Method of Test to Determine the Amount of Materials Finer Than the #200 Sieve in Aggregate
- I.M. 307 – Method of Test Specific Gravity of Aggregates
- I.M. 308 – Method of Test Determination of Free Moisture and Absorption of Aggregates
- I.M. 336 – Methods of Reducing Aggregate Field Samples to Test Samples
- I.M. 344 – Method of Test for Determination of the Amount of Shale in Fine Aggregate
- I.M. 345 – Method of Test for Determination of the Amount of Shale in Coarse Aggregate

### **LEVEL I PCC**

- I.M. 204 – Inspection of Construction Projects Sampling and Testing
- I.M. 208 – Materials Laboratory Qualification Program
- I.M. 216 – Guidelines for Verifying Certified Test Results
- I.M. 315 – Making and Testing Concrete Cylinders
- I.M. 316 – Flexural Strength of Concrete
- I.M. 317 – Slump of Portland Cement Concrete
- I.M. 318 – Air Content of Mixed Concrete by Pressure
- I.M. 327 – Sampling Concrete for Slump, Air, and Strength
- I.M. 328 – Making, Protecting, and Curing Concrete Flexural Specimens
- I.M. 340 – Weight Per Cubic Foot, Yield, and Air Content of Concrete
- I.M. 383 – Testing the Strength of PCC Using the Maturity Method
- I.M. 385 – Temperature of Freshly Mixed Concrete
- I.M. 525 – Method of Designing Flowable Mortar
- Iowa 410-B – Method of Test for Flow of Grout Mixtures
- AASHTO T 97 – Third Point Loading

### **LEVEL II PCC**

- I.M. 527 – Paving Plant Inspection
- I.M. 528 – Structural Concrete Plant Inspection
- I.M. 529 – P.C. Concrete Proportions



### **LEVEL III PCC**

- I.M. 530 – Quality Management and Acceptance of PC Concrete Pavement
- I.M. 531 – Test Method, Combining Aggregate Gradations
- I.M. 532 – Aggregate Proportioning Guide for Portland Cement Concrete Pavement

### **LEVEL I HMA**

- I.M. 204 – Inspection of Construction Projects Sampling and Testing
- I.M. 208 – Materials Laboratory Qualification Program
- I.M. 216 – Guidelines for Verifying Certified Test Results
- I.M. 320 – Method of Sampling Compacted Pavement Layers
- I.M. 321 – Method of Test for Compacted Density of Asphaltic Concrete (Displacement Method)
- I.M. 322 – Methods of Sampling Uncompacted Asphaltic Concrete
- I.M. 323 – Method of Sampling Asphaltic Materials
- I.M. 325 – Compacting Asphalt Concrete by the Marshall Method
- I.M. 325G – Method of Test for Determining the Density of Hot Mix Asphalt by Means of the Superpave Gyratory Compactor
- I.M. 337 – Determining Thickness of Completed Courses of Base, Sub-base, and Asphaltic Concrete
- I.M. 350 – Maximum Specific Gravity of Asphaltic Paving Mixtures Field Procedure for Central Laboratory Test Method
- I.M. 357 – Method of Preparation of Bituminous Mix Samples for Test Specimens
- I.M. 501 – Asphaltic Terminology, Equations, and Example Calculations
- I.M. 508 – Asphaltic Concrete Plant Inspection
- I.M. 509 – Tank Measurement and Asphalt Cement Content Determination
- I.M. 511 – Control of Asphaltic Concrete Mixtures
- I.M. 514 – Verification of Field Density for Asphalt Concrete Paving

### **LEVEL II HMA**

- I.M. 380 – Method of Test for Vacuum Saturated Specific Gravity and Absorption of Combined or Individual Aggregate Sources
- I.M. 510 – Method of Design of Asphaltic Concrete Mixes
- AASHTO T 176 – Plastic Fines in Graded Aggregate and Soils by use of the Sand Equivalent Test
- AASHTO T 304 – Uncompacted Void Content of Fine Aggregate
- ASTM D 4791 – Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate

### **PROFILOGRAPH**

- I.M. 341 – Method of Test Determining Pavement Profiles with the 25 Foot Profilograph

### **PRESTRESS**

- I.M. 570 – Inspection and Acceptance Precast and Prestressed Concrete Bridge Units



### **AGGREGATE TECHNICIAN DUTIES**

Duties of the Aggregate Technician are detailed in Materials I.M. 209 and I.M. 300 series and consist of, but are not limited to, the following:

**A. Sampling**

1. Obtain representative samples by approved method(s).
2. Sample at required frequencies.
3. Identify samples with pertinent information such as:
  - a. Type of material
  - b. Intended use
  - c. Production beds working depth
  - d. Sampling method

**B. Gradation testing**

1. Follow appropriate gradation testing methods.
2. Maintain current applicable specifications.
3. Post test results within 24 hours of sampling.

**C. Other testing as required (specific gravity, moisture, deleterious material, etc.)**

1. Follow appropriate testing methods.
2. Maintain current applicable specifications.
3. Complete required reports.

**D. Sampling and testing equipment**

1. Clean and check testing sieves for defects.
2. Assure scale accuracy.
3. Maintain sampling and testing equipment.

**E. Communication**

1. Notify Materials Department for production start-up or changes.



2. Relay test results to appropriate production or supervisory personnel.
3. Report failing test results immediately to appropriate personnel (including Materials Department) and assure remedial actions are taken.

F. General

1. Monitor stockpiling procedures to avoid contamination and excess segregation.
2. Assure proper identification of stockpiles
3. Assure specification requirements for intended use are met before shipment.
4. Assure sampling locations are safe.
5. Assure proper bedding planes or production depths are maintained.

G. Documentation

1. Report all production test results of certified aggregates on form #821278 and distribute as required.
2. Assure "plant production log" is maintained.

### **PORTLAND CEMENT CONCRETE (PCC) TECHNICIAN DUTIES PAVING AND STRUCTURAL CONCRETE**

The Quality Control Technician shall have no other duties while performing certified inspection duties. The District Materials Engineer may approve all Quality Control activities be performed by a single Certified Technician for low production situations.

Many of the duties of the PCC Level II Technician are detailed in I.M. 527 (Paving) and I.M. 528 (Structural) and consist of, but are not limited to, the following:

#### **A. Stockpiles**

1. Assure proper stockpiling procedures.
2. Prevent intermingling of aggregates.
3. Prevent contamination.
4. Prevent segregation.

#### **B. Plant Facilities**

1. Assure safe sampling locations.
2. Check for equipment compliance.
3. Assure proper laboratory location and facilities.

#### **C. Calibration**

1. Be present during calibration (paving).
2. Check plant calibration (structural).
3. Assure proper batch weights.

#### **D. Cement (Fly Ash) and Aggregate Delivery**

1. Check for proper sources and certification.
2. Document quantities delivered.
3. Monitor condition of shipments.

#### **E. Plant Sampling**

1. Check aggregate gradations by obtaining, splitting, and testing samples.



2. Check aggregate moistures and specific gravity.

F. Proportion Control

1. Check scale weights and operation.
2. Check admixture dispensers.
3. Check mixing time and revolutions.
4. Check cement yield. (Paving plant only unless over 10,000 c. yds.).

G. Concrete Tests

1. Cure flexural test specimens.
2. Test flexural specimens (Contract agency will perform test in structural plant).
3. Conduct maturity testing.

H. Test Equipment

1. Clean and maintain scales, screens, pycnometers and beam molds, and laboratory facility.

I. Documentation

1. Prepare daily plant reports (paving), weekly plant reports (structures).
2. Document all checks and test results in the field book.
3. Maintain daily diary of work activity.

### **HOT MIX ASPHALT (HMA) TECHNCIAN INSPECTION DUTIES**

The Quality Control Technician shall have no other duties while performing certified inspection duties. The District Materials Engineer may approve all Quality Control activities be performed by a single Certified Technician for low production situations.

Many of the duties of the Hot Mix Asphalt Technician are detailed in I.M. 508 and 511. These duties consist of, but are not limited to, the following:

#### **A. Stockpiles**

1. Assure proper stockpiling
2. Prevent intermingling of aggregates.
3. Prevent contamination.
4. Prevent segregation.
5. Document certified aggregate deliveries.

#### **B. Plant Erection**

1. Assure safe sampling locations.
2. Check specification compliance.
2. Check for proper laboratory location.

#### **C. Calibration**

1. Be in possession of appropriate mix design data.
2. Be present at the calibration.
3. Assure proper procedures being followed.
4. Obtain and/or record calibration data.
5. Check for proper gate settings.

#### **D. Asphalt Delivery**

1. Check for proper source and certification
2. Document deliveries.
3. Document quantities by tank stick, weighing, or metering.
4. Monitor Temperature



E. Plant Sampling

1. Check cold-feed gradation by obtaining, splitting, and testing samples.
2. Obtain asphalt binder samples.
3. Test aggregate moisture.

F. Mix Control

1. Monitor coating of aggregates.
2. Monitor and record mix temperature.
3. Monitor and record asphalt binder temperature.
4. Check trucks for proper loading and possible segregation.
5. Monitor mixing time.
6. Monitor recycle proportions.

G. Weights

1. Observe scale calibrations.
2. Check for specification compliance.
3. Regularly check calibrations.

H. Testing

1. Core testing\*.
  - a. Determine field density and percent voids of compacted mix.
  - b. Calculate quality index for density and thickness when required.
2. Uncompacted mix.
  - a. Bulk specific gravity of laboratory-compacted specimen.
  - b. Maximum specific gravity.
  - c. Calculate voids, VMA, film thickness.




I. Documentation

1. Prepare Daily Plant Inspection Report.
2. Document all checks and test results in field book.
3. Maintain a daily diary of work activity.
4. Moving averages.
5. Control Charts.

\*On projects where the contractor is not responsible for the quality control testing, then the agency is responsible for core testing functions.







## PRESTRESS TECHNICIAN DUTIES

Duties of the Prestress Technician are detailed in Materials I.M. 570 and consist of, but are not limited to, the following:

### A. Pre-pour

1. Identify and document materials requiring outside fabrication inspection.
2. Identify potential fabrication or production problems and notify Iowa DOT inspectors.
3. Verify that all materials incorporated meet the requirements of the contract documents.
4. Review concrete placement documents for strand locations.
5. Check tension calculations.
6. Measure elongation and gauge pressure during tensioning.
7. Check hold down and insert locations.
8. Check stress distributions.
9. Check steel reinforcement and placement.
10. Check strand position.
11. Check condition of pallet.
  - a. level
  - b. holes
  - c. gaps
  - d. other deformities
12. Determine moisture of aggregates.
13. Check form condition and placement.
  - a. oil
  - b. line alignment level
  - c. tightness

### B. Concrete Placement

1. Check on use of an approved mix design and batching operations (sequence).



2. Assure appropriate placement and proper vibration techniques.
3. Measure and record concrete temperature.
4. Assure test cylinders are properly made.
5. Assure appropriate finish.
6. Assure appropriate curing operations.

C. Post-pour


1. Check temperature and record during curing process.
2. Assure concrete strength has been met prior to releasing the line.
3. Assure proper detensioning procedure.
4. Check unit for defects and obtain approval for repairs.
5. Identify and store cylinders with the respective units.
6. Check beam ends for fabrication in accordance with the plans.
7. Assure exterior sides of fascia beams are grouted.
8. Inspect after patching and desired surfacing.
9. Measure and record overall dimensions of beam.
10. Measure and record camber at release and compare to design camber.
11. Check and/or measure and record lateral sweep before shipping.
12. Assure proper cylinder cure.



### **PROFILOGRAPH TECHNCIAN DUTIES**


Duties of the Profilograph Technician are detailed in Materials I.M. 341 and consist of, but are not limited to, the following:

- A. Test pavement for smoothness criteria
- B. Evaluate and certify test results
  - 1. Certified person that reduces trace must sign certified test report
  - 2. Profilograms become part of permanent project record
- C. Documentation
  - 1. Certified Profilograph test report must include following statement:  
  
This is to certify that all testing and trace reduction herein described  
has been performed according to applicable contract specifications and  
requirements.





# NOTES







October 2, 2001  
Supersedes April 3, 2001

Matls. I.M. 209

---

## **CERTIFIED AGGREGATES APPROVED PRODUCER PROGRAM**

### **GENERAL**

This I.M. deals with requirements for furnishing certified aggregate and the approved producer program.

In order to furnish certified aggregates to projects, an aggregate producer shall be on the approved aggregate producer listing (Appendix B, attached). The specific requirements, including the details of the required quality control program are in Appendix A (attached).

Specification Limits for aggregates being produced, and certified gradation sampling and testing frequency requirements are found in Appendix C. For complete details on aggregate quality and gradation requirements, refer to the appropriate referenced specification.

Non-compliance to the approved Producer Quality Control Program shall constitute grounds for the source and/or producer to be placed on conditional status by the District Materials Engineer. Continued noncompliance will be considered sufficient grounds to remove the producer from the Approved Producer List.

An Aggregate Review Board will meet, as needed, for disciplinary actions and appeals involving approved producers.

The Aggregate Review Board shall consist of:

- The State Materials Engineer
- The Chief Materials Geologist

The prime contractor or a contractor-authorized representative (the producer) shall be responsible for source product Quality Control.

Aggregate source gradation testing will be performed and documented in accordance with this Instructional Memorandum by persons qualified in accordance with the provisions of I.M. 210.

The gradation tests will be called certified gradation tests and the aggregate represented will be called certified aggregate.

Source gradation tests will be considered advisory when the aggregate acceptance is determined by sampling and testing, on the project, in accordance with I.M. 204. The advisory tested group will hereinafter be called proportioned aggregates. For all other aggregates, source gradation tests may be considered the basis of acceptance.

Sampling and testing duties described in this Instructional Memorandum shall not be delegated to non-certified technicians.

---



---

### **SAMPLING, TESTING AND DOCUMENTATION**

Gradation sampling, testing, and documentation of certified aggregates, at the source, shall be the responsibility of the aggregate producer or supplier. Quality sampling, testing, and documentation of certified aggregates shall be the responsibility of the IDOT Area Inspector.

Certified source testing shall be performed at frequencies as outlined in Appendix C of this I.M. utilizing the procedures contained in Materials I.M. Series 300. Additional certified gradation testing may be required at the time material is shipped to a project, for a stockpiled material carried through a winter season, or if there is evidence of segregation, contamination, or degradation. When additional certified testing of stockpiled material is required, the testing shall be at a frequency of at least one per 6000 Mg (tons). Bins or other means of securing representative samples shall be furnished for the sampling of stockpiled material.

Source quality will be determined by testing samples secured by District Materials personnel. This will not relieve the producer or supplier of their responsibility for quality of the material.

The quality of the material produced shall be determined before shipment to a project.

Not less than 24 hours before start up, or as soon as possible for a production change, the appropriate District Materials Engineer shall be notified. The notification shall include the estimated daily production and total production, the intended use (project or warehouse stock), production ledge(s) if applicable, and responsible person(s). Failure to notify may result in additional quality sampling and testing, or rejection of the material.

All producer gradation test results performed on certified aggregates, whether compliant or non-compliant, shall be promptly reported to the District Materials Engineer on form # 821278. These reports shall indicate whether the aggregate is being produced for direct project delivery, stockpiling for a specific project, or for advance warehouse stock.

Selected production limits shall be included on form # 821278.

Production limits for aggregate produced for use in A.C.C. or P.C.C. mix designs are generated by the contractor and supplied to the aggregate producer on forms 955 and 955QMC respectively.

### **CERTIFIED AGGREGATE DELIVERY DOCUMENTATION**

Documentation may be accomplished by numbered truck ticket, transfer list or shipment statement (such as form # 821278), or by a bill of lading (for rail or barge shipments). The certified documentation shall be furnished to project inspection personnel or receiving contractor before material is incorporated.

- For aggregates as bid items measured by mass (weight), the certified truck tickets shall be numbered and include signatures or initials in accordance with Article 2001.07.
- In the case of shipment by rail or barge, the documentation shall be sent to the project



engineer and receiving contractor or ready mix operator no later than the same day as shipment source departure. The documentation shall include the rail car or barge number(s).

- Documentation not having an exact mass (weight) shall include an estimated quantity (i.e. transfer listings or form 821278, etc.).

The following certification statement is required to be on the document used to certify the material being delivered (i.e. truck ticket, 821278, etc.): **"This is to certify the material herein described meets applicable contract specifications."**

\*Note: This certification statement shall be signed or initialed by an authorized representative of the aggregate supplier.

To ensure proper identification of delivered aggregates, the following additional information is required on the certification document:

#### **Proportioned Aggregate:**

P.C.C. Aggregate: Type or size, quantity, source name or T-203 A number, production beds (for quarried stones) and the delivery date.

Note: For aggregate being delivered for use in a contractor mix design (CMD), the product size is required in lieu of the Iowa DOT gradation number.

A.C.C. Aggregate: Product size, quantity, source name or T-203 A number, production beds (for quarried stones), the delivery date and project number.

Note: The project number is preferred when practical, as in the case of shipping to a paving plant site, but not required when shipping to a plant or ready mixed concrete plant supplying material to multiple projects.

#### **Non-proportioned Aggregate**

Iowa DOT gradation number, project number, quantity, source name or T-203 A number and the delivery date.

Note: Documentation for revetment stones shall include production beds.

Note: No gradation number is required for chock stone or revetment.

### **MONITORING OF CERTIFIED AGGREGATES**

The District Materials Office will be responsible for monitoring of sampling and testing of aggregates for gradation by the certified technician.

Monitor inspection samples are secured from aggregate being produced for a project, reserved stockpiles or stockpiles for intermittent project usage.



---

Monitor Sampling for Quality Testing shall be performed at the following minimum frequency:

- One per 12,000 Mg (tons)  
or
- If monthly production is greater than 12,000 Mg (tons), the minimum sampling frequency is one per month.

Monitor sampling for Gradation Testing may be independent samples or proficiency (split-bucket) samples for comparison testing in accord with I.M. 216. Sampling shall be performed at the following minimum frequency:

- Proportioned aggregates: one per 18,000 Mg (tons) representing the various products made.
- Non-proportioned aggregates: one per 36,000 Mg (tons) representing the various products made.

Note: These sampling frequencies may be adjusted by the District Materials Engineer. Monitoring of certified gradation testing may be waived when a product quantity is less than 2000 Mg (tons).

Periodic evaluation of certified technicians will be performed by the District Materials Representative and kept on file. Correlation (split-bucket) sample results will be compared per I.M. 216.

At no time will the District Materials Office representative issue directions to the producer. However, the representative will have authority and responsibility to question and where necessary reject any operation, which is not in accordance with the specifications, special provisions, and instructional memorandums.

#### **REHANDLING OF CERTIFIED AGGREGATES**

When certified aggregates are re-handled the District Materials Engineer shall be notified and afforded the opportunity to monitor the re-handling procedure.

For the purpose of this I.M., re-handling is meant to include the physical unloading and reloading of aggregate at a temporary storage site before the aggregate is delivered to its final destination. Re-handled certified aggregates may be required to be re-tested, with or without re-weighing, and re-certified on a numbered shipment ticket with proper identification and certification statement.

#### **ACCEPTANCE**

In the case of proportioned aggregates, acceptance tests will be performed on samples obtained at the proportioning plant in accordance with Construction Procedures and

---



---

Instructions Manual Section 3.22 and Materials Instructional Memorandums 204 and 513.

Certified aggregate may be incorporated into a project on the basis of the certified truck ticket, certified bill of lading, shipment listing, certified transfer listing or Certified Gradation Test Report (Form #821278). When the material represented is non-proportioned aggregate, the project number must be on the certified document and a copy furnished for project inspection personnel. When the aggregate represented is proportioned aggregate, the project number is preferred when practical, as in the case when shipping to a paving plant site, and not required when impractical, as in the case when shipping into warehouse stock at a ready mix plant. A file of certified shipment or transfer documents for proportioned aggregate will be maintained by the contractor or ready mix operator and made available for inspection at each plant or project site during the project period. Project inspection personnel shall verify that all material incorporated in the project is properly certified and document this verification and quantity on each of the appropriate daily or periodic construction reports. No other project documentation for the incorporated aggregate is required.

Documentation procedures for asphalt and concrete paving plants that have **multiple** project and commercial mix responsibilities would function in the same manner as described above for ready mix plants.

Acceptance of non-proportioned aggregates will be based on proper certification and on visual examination by the contracting authority to ensure against obvious contamination or segregation.

Minor quantities of non-critical aggregates may be visually inspected by the contracting authority and recorded in the project field book. Quantities less than 200 Mg (ton) are considered minor. An example of a non-critical aggregate is a non-proportioned aggregate such as granular backfill material for bridge abutments.





---

## APPENDIX A

### GUIDELINES FOR AGGREGATE PRODUCER QUALITY CONTROL PROGRAM

#### GENERAL

This appendix contains the minimum requirements for the producer Quality Control Program in order to become an approved aggregate producer.

Each producer must submit a written application to their District Materials Engineer for review and approval. **Note:** Producers with operations in more than one District shall apply to each District Materials Engineer where certified material production exists or is anticipated. The applications are available from the DME Offices and the Iowa Limestone Producers Association (ILPA) office. (A sample application is attached.)

#### DEFINITIONS

The following definitions apply to the Quality Control Program guidelines:

**Source** - Any location aggregate is produced at or shipped from on a certified basis (e.g., quarries, pits, project sites, terminal locations, portable production operation, etc.).

**Conditional Status** - This is a written notice from the District Materials Engineer to a producer that certified aggregates will no longer be accepted from a particular source. Application of Conditional Status may vary depending upon situation or specific circumstances. The Conditional Status may apply only to a production operation and aggregate produced by that operation. In other situations, when the deficiency is more widespread, the Conditional Status may apply to an entire company or division within a company until the problem is resolved. In the case of portable production operations, Conditional Status shall apply to the specific production operation regardless of source location, and shipment of aggregate previously produced by the affected production operation may be placed on Conditional Status when warranted.

#### GUIDELINES FOR AGGREGATE PRODUCER QUALITY CONTROL PROGRAM

##### 1. Aggregate Certification

The producer has the overall responsibility of certifying that material being placed in the certified stockpile is produced under and conforms to the Aggregate Certification Program, and the producer Quality Control (QC) Program. The Iowa DOT, through its monitoring activities (sampling/testing, visual observation, etc.), will verify the continued compliance to the program.



2. Knowledge of Current Specifications

The producer Quality Control representative(s) must maintain up-to-date knowledge of the specifications that apply to aggregate products currently being produced at the source. The producer representative shall have available, at the testing lab, a copy of the current Standard Specifications, all applicable Supplemental Specifications and all applicable Instructional Memorandums (I.M.s) for aggregate inspection, as well as a current geological section, if applicable. The producer shall be aware of any Special Provisions, which change current aggregate specifications. This applies to both quality and gradation requirements. The producer shall be responsible for providing these up-to-date publications to their QC representative.

3. Plant Production Log

The producer is required to maintain a plant production log when producing under the program. This production log shall detail, on a daily basis, samples taken, pass/fail results, corrective actions, plant/ledge changes, etc. The log must be kept at a designated location and be readily available to the Iowa DOT representative for review.

4. Visual Inspection

The producer is responsible for visually inspecting the aggregate source process on a frequent basis. Visual inspection can be defined as observing the processing or production area, as well as the condition of the aggregate in the flow stream or stockpiles. This visual inspection does not take away from actual testing, but enhances the inspection to ensure quality aggregates. It is the responsibility of the producer Quality Control representative to observe the overall operation to detect segregation, degradation, and contamination that are detrimental to the quality of the product.

5. Quality Requirements

Any certified stockpile must meet the designated quality before shipment. The producer is responsible for supplying material meeting all quality requirements. Intentional shipment of untested or out of specification material shall constitute grounds for immediate rejection of material and placement of the source and/or the producer on conditional status. The producer Quality Control representative shall obtain and maintain quality information on specific ledges, production methods, and certified stockpiles for each source.



6. Production Notification

Twenty-four hours before startup or as soon as possible for production change, the appropriate Area Materials Coordinator (AMC) or District Materials Engineer (DME) shall be notified. Failure to notify may result in material rejection or resampling of the stockpile. Notification shall include the estimated intended tonnage to be produced, estimated daily production rate, intended use (e.g., project information or warehouse stock), and if applicable, production ledges, and responsible person(s).

7. Production

A. The producer shall establish gradation production limits for each material to be certified to help ensure a product that is uniformly graded and meets specifications at the time of use.

1. Gradation production limits shall apply to individual products within each source and be maintained for each stockpile.
2. Gradation production limits are subject to review, only, by the AMC or DME.
3. Repeated non-adherence to the producer established gradation production limits will require stockpile sampling and testing by the producer.

B. Testing and Reporting

1. Minimum test frequencies as per I.M. 209, Appendix C
2. Test results shall be known before delivery when the product is being shipped to a project.
3. All test results shall be available at a designated location within 24 hours of sampling when the material is being placed into a certified stockpile.
4. Report gradation test results to DME and contractor, when applicable, on Form #821278.

C. Maintaining Ongoing Quality Control Procedures



1. Proper ledge control
  2. Equipment (production and testing)
  3. Stockpiling procedures
  4. Proper stockpile identification (signing, stockpile maps, etc., as required).
8. Delivery
- A. Stockpile identification to ensure delivery from proper stockpiles.
  - B. Visual inspection for contamination, segregation, etc.
  - C. Stockpile gradation resampling may be required.
  - D. Proper identification and certification of delivered aggregate as per I.M. 209.
  - E. Maintain ongoing QC procedures.
  - F. Report tonnage to the AMC when requested.
9. Quality Control Structure

In order to ensure quality as a priority, the producer Quality Control personnel shall have a line of communication directly to their management, as well as their production operation.



### AGGREGATE PRODUCER APPROVAL APPLICATION

Company Name \_\_\_\_\_

Address \_\_\_\_\_

(IF MORE THAN ONE; i.e., Regional Offices, etc., PLEASE ATTACH LIST AND AREA COVERED.)

1. Are copies of current applicable specifications, aggregate testing I.M.s and source information data such as geologic sections available at the respective sources or testing facilities?(Yes or No) If No, explain \_\_\_\_\_
2. Is a plant production log maintained on a daily basis and available for inspection? (Yes or No) If No, explain \_\_\_\_\_
3. Who (position) is responsible for production notification to the Area Materials Coordinator? \_\_\_\_\_
4. Which company representative (position) is normally responsible for daily overall Quality Control processes at the source? \_\_\_\_\_
5. Describe the certified stockpile identification system in place at each source (Map, signing, etc.) \_\_\_\_\_
6. Please attach a detailed summary of your Quality Control Program. (Note: Please refer to Guidelines for Required Aggregate Producer Quality Control Program)
7. Please attach a flow chart of your current Quality Control structure (Include names, addresses, phone numbers of appropriate management personnel, chain of command, etc., for problem resolution).

Indicate the District(s) for which you are seeking approval.

1                      2                      3                      4                      5                      6

AUTHORIZED SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

DME RECOMMENDATIONS \_\_\_\_\_  
\_\_\_\_\_

DME SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

APPROVAL (YES or NO) REMARKS \_\_\_\_\_  
\_\_\_\_\_

MATLS. ENGINEER SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_







---

**APPENDIX B  
APPROVED AGGREGATE PRODUCERS**

This appendix lists the approved aggregate producers and the Districts to which the producer has applied.

<b><u>Producer</u></b>	<b><u>Approved Districts</u></b>
Acme Fuel & Materials Company Muscatine, IA	DISTRICT 5
Aggregate Materials Company Dubuque, IA	DISTRICT 6
Aggregates, Inc. Cedar Rapids, IA	DISTRICT 6
Anderson Sand & Gravel Company De Witt, IA	DISTRICT 6
Arcadia Limestone Company Arcadia, IA	DISTRICT 1
Bard Concrete Dyersville, IA	DISTRICT 6
Basic Materials Corporation Waterloo, IA	DISTRICT 2
Becker Gravel Company, Inc. Stratford, IA	DISTRICT 1, DISTRICT 2, DISTRICT 3, DISTRICT 4
Bedrock Gravel Company Auburn, IA	DISTRICT 3
Bellco of Nebraska, Inc. Council Bluffs, IA	DISTRICT 4
Bellevue Sand & Gravel Company Bellevue, IA	DISTRICT 6
Blazek Corporation Lawler, IA	DISTRICT 2
Bogges Construction Company Estherville, IA	DISTRICT 3



---

<b><u>Producer</u></b>	<b><u>Approved Districts</u></b>
Boyer Sand & Rock, Inc. Hawarden, IA	DISTRICT 3
Brockman Mgt., LLC, dba Brockman Sand Co. Ft. Madison, IA	DISTRICT 5
Bruening Rock Products, Inc./Skyline Const., Inc. Decorah, IA	DISTRICT 2, DISTRICT 5, DISTRICT 6
Builders Sand & Cement Company Davenport, IA	DISTRICT 6
Central Stone Company #1 Hannibal, MO	DISTRICT 5
Cessford Construction Company Burlington, IA	DISTRICT 5
Cessford Construction Company Le Grand, IA	DISTRICT 1
Cohrs Construction, Inc. Spirit Lake, IA	DISTRICT 3
Concrete, Inc. Gifford, IA	DISTRICT 1
Concrete Materials Sioux Falls, SD	DISTRICT 3
Conreco, Inc. Omaha, NE	DISTRICT 4
Coots Materials Company Vinton, IA	DISTRICT 6
Corell Recycling - A Div. of Corell Contractor, Inc. Des Moines, IA	DISTRICT 1
Crawford Quarry Company Cedar Rapids, IA	DISTRICT 6
Croell Redi Mix Sumner, IA	DISTRICT 2

---



---

**Producer**

**Approved Districts**

Dave's Sand & Gravel, Inc.  
Everyly, IA

DISTRICT 3

Douds Stone, Inc.  
Ottumwa, IA

DISTRICT 5

Estherville Sand & Gravel Company  
Estherville, IA

DISTRICT 3

Falk, L. R. Construction Company  
St. Ansgar, IA

DISTRICT 2

Flewelling Sand & Gravel  
Moville, IA

DISTRICT 3

Fred Carlson Company, Inc.  
Decorah, IA

DISTRICT 1, DISTRICT 2

Ft. Calhoun Stone Company  
Blair, NE

DISTRICT 3, DISTRICT 4

Fort Dodge Asphalt Company  
Fort Dodge, IA

DISTRICT 1

Gray Quarry, Inc.  
Hamilton, IL

DISTRICT 5

Greene Limestone Company  
Charles City, IA

DISTRICT 2

Hahn Ready Mix  
Muscatine, IA

DISTRICT 5

Hallett Materials  
Des Moines, IA

DISTRICT 1, DISTRICT 3,  
DISTRICT 4

"Hank" Stalp Gravel Company  
West Point, NE

DISTRICT 3

Heartland Asphalt, Inc.  
Mason City, IA 50401

DISTRICT 2

Heckett MultiServ  
Wilton, IA

DISTRICT 5



---

**Producer**

**Approved Districts**

Heckett MultiServ West  
Sterling, IL

DISTRICT 6

Higman Sand & Gravel  
Akron, IA

DISTRICT 3

Ideal Sand Co. aka Ideal Ready Mix Co., Inc.  
West Burlington, IA

DISTRICT 5

Iron Mountain Trap Rock Company  
Iron Mountain, MO

DISTRICT 5

J. W. Ready Mix & Construction  
Sac City, IA

DISTRICT 3

Kerford Limestone Company  
Weeping Water, NE

DISTRICT 4

Knocks' Building Supplies  
Parkersburg, IA

DISTRICT 2

Kruse Paving, Inc.  
Lakefield, MN

DISTRICT 3

Kruse Rock & Gravel  
Milford, IA

DISTRICT 3

Kuhlman Construction Company  
Colesburg, IA

DISTRICT 6, DISTRICT 2

L. G. Everist, Inc.  
Sioux Falls, SD

DISTRICT 3

L & M Sand & Gravel, Inc.  
LeMars, IA

DISTRICT 3

L & W Quarries  
Centerville, IA

DISTRICT 5

LaHARV Construction Company, Inc.  
Forest City, IA

DISTRICT 2, DISTRICT 3

Linwood Mining & Minerals Corporation  
Davenport, IA

DISTRICT 5, DISTRICT 6



Lyman-Richey Sand & Gravel Company  
Omaha, NE

DISTRICT 3, DISTRICT 4

**Producer**

**Approved Districts**

Mallard Sand & Gravel Company  
Valley, NE

DISTRICT 3, DISTRICT 4

Manatts, Inc.  
Brooklyn, IA

DISTRICT 1, DISTRICT 2,  
DISTRICT 3, DISTRICT 4,  
DISTRICT 5, DISTRICT 6

Manatts Sand & Gravel, Inc.  
Tama, IA

DISTRICT 1, DISTRICT 2,  
DISTRICT 6

Marengo Ready Mix, Inc.  
Marengo, IA

DISTRICT 6

Martin Marietta Aggregates  
Des Moines, IA

DISTRICT 1, DISTRICT 2,  
DISTRICT 3, DISTRICT 4  
DISTRICT 5, DISTRICT 6

Martin Marietta Aggregates  
Valley, NE

DISTRICT 4, DISTRICT 5

MatX, Inc.  
Colorado Springs, CO

DISTRICT 6

Moberly Stone Company  
Moberly, MO

DISTRICT 5

Moline Consumers Company  
Moline, IL

DISTRICT 6

Molo Sand & Gravel  
Dubuque, IA

DISTRICT 6

Myrl & Roy's Paving, Inc.  
Sioux Falls, SD

DISTRICT 3

New Ulm Quartzite Quarries, Inc.  
New Ulm, MN

DISTRICT 2

North Iowa Sand & Gravel, Inc.  
Mason City, IA

DISTRICT 2

Northwest Materials  
Fort Dodge, IA

DISTRICT 1



Ortonville Stone Company  
Ortonville, MN

DISTRICT 3

**Producer**

**Approved Districts**

Paul Niemann Construction Company  
Sumner, IA

DISTRICT 2, DISTRICT 6

Pederson Brothers, Inc.  
Harmony, MN

DISTRICT 2

Pella Construction Company Ltd.  
Pella, IA

DISTRICT 1, DISTRICT 5

Persinger Sand & Gravel  
Smithland, IA

DISTRICT 3

Peterson Contractors, Inc.  
Reinbeck, IA

DISTRICT 1, DISTRICT 2  
DISTRICT 3, DISTRICT 4  
DISTRICT 5, DISTRICT 6

Prairie Sand & Gravel  
Prairie Du Chhien, WI

DISTRICT 2

Preston Ready Mix Corporation  
Preston, IA

DISTRICT 6

Quality Concrete Company  
Clinton, IA

DISTRICT 6

Randall Transit Mix Company  
Northwood, IA

DISTRICT 2

Recycled Aggregate Products Company  
Sioux City, IA

DISTRICT 3

Rehms-Stewart, Inc.  
Ocheyedan, IA

DISTRICT 3

Reilly Construction Company, Inc.  
Ossian, IA

DISTRICT 1, DISTRICT 2,  
DISTRICT 3, DISTRICT 4  
DISTRICT 5, DISTRICT 6

River Bend Enterprises  
Nashua, IA

DISTRICT 2

River City Stone - Div. of Mathy

DISTRICT 6



Dubuque, IA

River Products Company, Inc., The  
Iowa City, IA

DISTRICT 1, DISTRICT 5

**Producer**

**Approved Districts**

Rohlin Construction Company, Inc.  
Estherville, IA

DISTRICT 1, DISTRICT 2,  
DISTRICT 3

Roverud Construction, Inc.  
Spring Grove, MN

DISTRICT 2

RVBT aka Rock Valley Sand & Gravel  
Rock Valley, IA

DISTRICT 3

S & A Construction, LTD  
Allendale, MO

DISTRICT 4

S & G Materials  
Iowa City, IA

DISTRICT 6

Schildberg Construction Company, Inc.  
Greenfield, IA

DISTRICT 4

Sieh Sand and Gravel  
Spencer, IA

DISTRICT 3

Shell Rock Products  
Shell Rock, IA

DISTRICT 2

Spencer Quarries  
Spencer, SD

DISTRICT 3

Stoner Sand  
Ridgeway, MO

DISTRICT 5

Tiefenthaler Ag-Lime Inc.  
Breda, IA

DISTRICT 3

Ulland Brothers, Inc.  
Albert Lea, MN

DISTRICT 2

W. Hodgman & Sons, Inc.  
Fairmont, MN

DISTRICT 2, DISTRICT 3

Wayne T. Hansen Corporation  
Algona, IA

DISTRICT 2, DISTRICT 3

Weber Stone Company, Inc.  
Anamosa, IA

DISTRICT 6

Welden Aggregates, Inc.  
Iowa Falls, IA

DISTRICT 1

**Producer**

**Approved Districts**

Wendling Quarries, Inc.  
De Witt, IA

DISTRICT 1, DISTRICT 5,  
DISTRICT 6

West Des Moines Sand  
Des Moines, IA

DISTRICT 1

Western Iowa Limestone  
Harlan, IA

DISTRICT 4

Wetherell Excavating & Trucking, Inc.  
Storm Lake, IA

DISTRICT 3

Wiltgen Construction Company  
Calmar, IA

DISTRICT 2

Winn Corporation Sand & Gravel  
Ollie, IA

DISTRICT 5

Wright Materials Company  
Belmond, IA

DISTRICT 2

Zupke Sand & Gravel  
Randalia, IA

DISTRICT 2





## AGGREGATE SPECIFICATION LIMITS AND SAMPLING AND TESTING REFERENCE GUIDE

(See Specifications for complete Details)

October 3, 2000

Supersedes April 25, 2000

Matls. I.M. 209, Appendix C

New Issue

TEST LIMITS October 2000	Spec #	F & T A	F & T C	LA Abrasion	Absorption	Chert	Shale	Clay Lumps	Plastic Index	Mud Balls	Mortar Strength	Al <sub>2</sub> O <sub>3</sub> Limit	Pore Index	Gradation Number	Certified Inspection
<b>Fine Aggregate for PCC</b>															<b>Gradations</b> 1/150C
PCC	4110.00						2				1.5			1	
Note: Maximum 40% between sieves If the gradation is 80% or less passing the #16 sieve and 50% or less passing the #30 sieve, no mortar strength is required. Annual test requiring mortar strength of more than 1.5 and a fineness modulus of more than 2.75 for continued approval.															
PCC, Class L	4111.00						2				1.3			1	1/1500
Note: Maximum 45% between sieves															
Mortar	4112.00						2				0.9			2	1/1500
Note: Shale + coal not to exceed 2%															
Class V	4117.03													8	1/1500
Note: Only from sources acceptable as coarse aggregate PCC.															
<b>Coarse Aggregate for PCC</b>															
Crushed Stone	4115.00														
Note: Chert particles are those retained on the 3/8" sieve, except for 4115.06 which uses the #4 sieve. Note: Chert refers to unsound chert on 3/8" sieve which break into 3 or more pieces when subjected to freeze/thaw tests.															
Structural		6		50		2	1	0.5				0.5		3-5	1/1500
Nonstructural		6		50		3	1	0.5				0.5		3-5	1/1500
Gravel	4115.00														
Structural		6		35		2	1	0.5						3-5	1/1500
Nonstructural		6		35		3	1	0.5						3-5	1/1500
Deck Overlay	4115.00	4		40	2.5	0.5						0.4		6	1/1500
Note: Chert+Shale+Coal+Iron not to exceed 1%.															
Class V Aggregate	4117.00													7	1/1500
Note: Course Aggregate as in 4115 and Fine Aggregate as in 4110 and 4111.															





## AGGREGATE SPECIFICATION LIMITS AND SAMPLING AND TESTING REFERENCE GUIDE

(See Specifications for complete Details)

October 3, 2000

Supersedes April 25, 2000

Matls. I.M. 209, Appendix C

New Issue

TEST LIMITS October 2000	Spec #	F & T A	F & T C	LA Abrasion	Absorption	Chert	Shale	Clay Lumps	Plastic Index	Mud Balls	Mortar Strength	Al <sub>2</sub> O <sub>3</sub> Limit	Pore Index	Gradation Number	Certified Inspection
<b>Granular Surfacing</b>															
Agg. for Granular Shoulders	4120.02														1/3000
Note: Requirements are equivalent to 4120.04, 4120.05, or 4120.06.															
Class C Gravel	4120.03		15				10			15				10	1/3000
Class A Crushed Stone	4120.04		15	45						4				11	1/3000
For shoulders only; If "A" Freeze does not exceed 10, an abrasion of 55% will be allowed.															
Class B Crushed Stone	4120.05		20	55						4				11	1/3000
Note: "C" Freeze + Abrasion not to exceed 65%															
Class D Crushed Stone	4120.06														1/3000
Note: "C" Freeze, Abrasion, and Gradation to be determined by Contract Documents.															
Paved Shoulders Fillets	4120.07		15	45						4				16	1/3000
<b>Granular Subbase</b>															
	4121.00	25		45								1.5		12	1/3000
Note: Crushed PCC, sand, gravel, or crushed stone, or combinations. See specifications for details. The following are virgin materials:															





## AGGREGATE SPECIFICATION LIMITS AND SAMPLING AND TESTING REFERENCE GUIDE

(See Specifications for complete Details)

October 3, 2000

Supersedes April 25, 2000

Matls. I.M. 209, Appendix C

New Issue

TEST LIMITS October 2000	Spec #	F & T A	F & T C	LA Abrasion	Absorption	Chert	Shale	Clay Lumps	Plastic Index	Mud Balls	Mortar Strength	Al <sub>2</sub> O <sub>3</sub> Limit	Pore Index	Gradation Number	Certified Inspection
<b>Crushed Stone-Base</b>															
Macadam Stone	4122.02		10	45										13	1/1500
<b>Modified Subbase</b>															
	4123.00		15	45								4.7(-#40)		14	1/3000
Note: Material with Al <sub>2</sub> O <sub>3</sub> less than 0.7 (+4) may have an abrasion maximum of 55. Note: If gravel only, 75% of +3/8" must be crushed with a minimum of one fractured face.															
<b>Cover Aggregate</b>															
Cover Aggregate for Bituminous Seal Coats	4125.01A		10	40			5							1,19-21	1/1500
Note: Friction Type 4D or better, Shale on Sand Cover Aggregate shall not exceed 2%.															
Aggregate for Slurry Mixture	4125.01B	10		40			5							23	1/1500
Note: Friction Type 4 or better, Sand Equivalent of not less than 45.															
<b>Fine Aggregate for ACC</b>															
Type A	4127.03					2		0% on 1.5"						22,24-27	1/1500
Type B	4126.00													24-27	1/1500
Note: Crushed fine aggregate shall be produced from sources meeting freeze/thaw and abrasion loss requirements for coarse aggregates for ACC.															
<b>Coarse Aggregate for ACC</b>															
Type A	4127.00	10		45	6.0							0.7		24-27	1/1500
Note: Mudballs + Clay Lumps not to exceed 0.5% Note: The fine portion of combined materials shall not exceed 2% shale retained on the #16 sieve.															
Type B															
Primary	4126.02	25	10	45	6.0							1.5		24-27	1/1500
Non-Primary	4126.02	45	10	45	6.0							2.5		24-27	1/1500
<b>Composite Aggregate for ACC</b>															
	4126.04							4						24-27	1/1500
Note: This gradation only applies to Marshall mixtures.															





## AGGREGATE SPECIFICATION LIMITS AND SAMPLING AND TESTING REFERENCE GUIDE

(See Specifications for complete Details)

October 3, 2000

Supersedes April 25, 2000

Matls. I.M. 209, Appendix C

New Issue

	Spec #	F & T A	F & T C	LA Abrasion	Absorption	Chert	Shale	Clay Lumps	Plastic Index	Mud Balls	Mortar Strength	Al <sub>2</sub> O <sub>3</sub> Limit	Pore Index	Gradation Number	Certified Inspection
<b>TEST LIMITS</b> October 2000															
<b><u>Revetment Stone</u></b>															
Class A	4130.02	10		50								0.7	25		N/A
Class B	4130.03	10		50								0.7	25		N/A
Class D	4130.04		10	50											N/A
Class E	4130.04	10		50								0.7	25		N/A
Erosion Stone	4130.05		15	50						5				34	N/A
Note: Minimum of 50% layers greater than 5" thick. A minimum of 10% with the greatest dimension not more than 2 times the smallest.															
<b><u>Porous Backfill</u></b>	4131.00	10		45								0.7		29	1/1500
Note: Shall not exceed 5% shale on the #16 sieve.															
<b><u>Special Backfill</u></b>															
Crushed Stone/Concrete	4132.02													30,31	1/3000
Gravel	4132.03											10		31	1/3000
Note: Carbon of no more than 1% on fraction passing to #40 sieve.															
<b><u>Granular Backfill</u></b>	4133.00									4				32	1/3000
Note: "C" Freeze and Abrasion requirements are equivalent to those of either 4120.04 or 4120.05.															
<b><u>Recycled PCC</u></b>															
Note: Recycled PCC must meet gradation and sampling frequency of the intended product.															
<b><u>Recycled Composite Pavement</u></b>															
Recycled composite pavement must meet gradation and sampling frequency of the intended product.															



# **AGGREGATE GRADATION TABLE – ENGLISH**


**OCTOBER, 2001**

Grad No.	Section No.	Intended Use	Percent Passing											Notes
			1.5"	1.0"	¾"	½"	⅜"	#4	#8	#30	#50	#100	#200	
1	4110,4111,4125	PCC FA, Cover Agg.					100	90-100	70-100	10-60			0-1.5	1
2	4112	Mortar Sand						100	95-100	40-75	10-40	0-30	0-3	
3	4115 (57,2-8)	PCC CA	100	95-100		25-60		0-10	0-5				0-1.5	2
4	4115 (2-8)	PCC CA	100	50-100	30-100	20-75	5-55	0-10	0-5				0-1.5	
5	4115 (67, 2-8)	PCC CA		100	90-100		20-55	0-10	0-5				0-1.5	
6	4115.06 (Repair & Overlay)	PCC CA			100	97-100	40-90	0-30					0-1.5	
7	4117 (Class V)	PCC FA & CA	100					80-92	60-75	20-40				
8	4117.03 (Class V)	Fine Limestone					100	90-100					0-30	
10	4120.03 (C Gravel)	Granular Surface			100			50-80	25-60					3
11	4120.04, 4120.05 A, B Cr. St.)	Granular Surface & Shoulder		100	95-100	70-90		30-55	15-40				6-16	4,5
12	4121	Granular Subbase	100						10-20		0-15		0-6	6
13	4122.02 (Cr. St.)	Mac. St. Base	3" nominal maximum size – screen over ¾" or 1.0" screen.											
14	4123	Modified Subbase	100		70-90				10-40				3-10	5
16	4120.07 (Cr. St.)	Paved Shoulder Fillet	100			0-50		0-10						7
19	4125 (0.500" Cr. Gr. Or Cr. St.)	Cover Aggregate			100	97-100	40-90	0-30	0-15				0-2	
20	4125(0.500" Scr. Gr.)	Cover Aggregate			100	95-100	40-80	0-15	0-7				0-1.5	
21	4125 (¾")	Cover Aggregate				100	90-100	10-55	0-20	0-7			0-1.5	
23	4125.01B (Cr. St.)	Slurry Treatment					100	70-90	45-70	19-34	12-25	7-18	5-15	
29	4131	Porous Backfill			100	95-100	50-100	10-50	0-8					
30	4132.02 (Cr. St.)	Special Backfill	100						15-45				0-10	5
31	4132.03 (Gravel)	Special Backfill		100	90-100	75-90			30-55				3-7	
32	4133 (Sand/Gr./ Cr. St.)	Granular Backfill	100 % passing the 3" screen						20-100				0-10	8,9
34	4130.05 (6" Cr. St.)	Erosion Stone	100% passing the 9" screen – 100% retained on the 3" screen											

**Notes:** (Gradations No. 9, 15, 17, 18, 22, 24, 25, 26, 27, 28, and 33 have been deleted.)

- When the fine aggregate is sieved through the following number sieves – 4, 8, 16, 30, 50 and 100 – not more than 40% shall pass one sieve with the next higher number, for section 4110, nor 45% for section 4111
- When used in precast and prestressed concrete bridge beams, 100% shall pass the 1.0" sieve.
- When compaction of material is a specification requirement, the minimum percent passing the No. 200 sieve is 6%.
- See specification for combination of gravel and limestone screenings.
- Unwashed air dry samples of crushed composite material shall be tested for gradation compliance except that no gradation determination will be made for the material passing the No. 200 sieve.
- For granular subbase made from crushed concrete, it may be necessary to scalp or screen to attain the specified gradation. The gradation requirements for granular subbase, not made from crushed concrete and without blending sand, shall be 8% to 30% passing the No. 8 sieve.
- Gradation 3 or 4 may be substituted, at the contractor's option.
- Crushed stone shall have 100% passing the 1.0" sieve.
- When granular backfill is used under flowable mortar, one of the following alternative materials shall be used: natural sand complying with Section 4110, except the % passing the No. 200 sieve shall not exceed 4%; gravel, crushed stone, or crushed concrete meeting gradation requirements of Section 4121.








# NOTES







## **SECTION I** **AGGREGATE**

Today's highways must have the strength and durability to sustain high volumes of traffic for many years. Since pavements and base courses of these highways are composed largely of aggregates, these materials must be of a quality level that will permit satisfactory performance. Consequently, the role of the aggregate inspector is vital to securing good highway performance. Design and construction techniques can never satisfactorily compensate for the use of substandard aggregates. A well-designed and constructed highway using good aggregates will provide good service for many years. A well-designed and constructed highway using substandard aggregates will soon become a maintenance problem. This section contains general information on aggregates and the tests used to control their quality. Those aggregates commonly produced and used in Iowa will be emphasized, as will the tests that have been determined through experience to be the best measure of their quality.

### **AGGREGATES DEFINED**

Generally, aggregates are granular construction materials composed of hard mineral particles, crushed or uncrushed, which are or can be properly sized for the use intended. Glacial clay is composed of minute granular mineral. However, the term "aggregate" as used in this booklet will be referring to granular materials that contain, at most, only a few percent of particles that will pass through a 75  $\mu$ m (#200) sieve.

### **Coarse and Fine Aggregates:**

Aggregates are frequently referred to as "fine" or "coarse." There is no universally accepted particle size that separates fine aggregate from coarse aggregate. We have chosen the 4.75 mm (#4) sieve as the sieve size with which to make this separation. All particles which will pass through a 4.75 mm (#4) sieve, and be

*Aggregates are often referred to as rock, gravel, mineral, crushed stone, slag, sand, rock dust, or fly ash.*

### **Aggregate Classification**

***Coarse Aggregate:*** Any aggregate that does not pass the 4.75 mm (no. 4 sieve).

***Fine Aggregate:*** Any aggregate that passes the 4.75 mm (no. 4 sieve).



predominately retained on the 75  $\mu\text{m}$  (#200) sieve, are referred to as “fine aggregates.” All particles which are retained on 4.75 mm (#4) or larger sieves are referred to as “coarse aggregate.”

**Natural Aggregates:**

Natural aggregates are all those produced from naturally occurring materials, such as sand, gravel, limestone, etc., which can be modified by crushing, washing, or screening as necessary for the use intended.

**Synthetic Aggregates:**

Synthetic aggregates are all those produced from materials that have been mineralogically altered by artificial means. Expanded shales and clays (lightweight aggregate), fly ash, slag, etc., are examples of synthetic aggregates.

**Manufactured Aggregates:**

Manufactured aggregates are produced by the mechanical crushing and sizing of either natural or synthetic materials. Manufactured sand, for instance, could be made by crushing and sizing either a natural material such as limestone or synthetic material such as slag. However, even though a manufactured sand can be a natural aggregate, it cannot be a natural sand. The reason for this is explained in the next paragraph.

**Natural Sands and Gravels:**

Those aggregates referred to as “natural sand” or “natural gravel” result from the natural disintegration of rock and are produced without artificial crushing. They can, however, be washed or mechanically sized.


Thus, the term “natural” is used in two different ways. There are natural aggregates as opposed to synthetic aggregates and natural sands or gravels as opposed to manufactured sands or gravels. Consequently, sand made by crushing quartzite or limestone is a natural aggregate but not a natural sand. The specifications required fine aggregates for concrete floors and pavements to be natural sands.



### **Aggregate Uses**


Aggregates are used in portland cement concrete, asphaltic concrete, bases, subbases, granular backfills, etc. A summary of the quality and gradation specifications for the construction aggregates are listed in Division 41, Construction Materials of the Standard Specifications.







# NOTES





## **SECTION II**

### **SAMPLING METHODS AND EQUIPMENT**

#### **Introduction**

This chapter deals with the different sampling methods and equipment. Before beginning to study, be sure to have a copy of the current I.M. Volume II prepared by the Materials Office of the Highway Division.

#### **Importance of Proper Sampling**

No other single phase of an Aggregate Inspector's duties is as important as obtaining a representative sample. At this point, all of the money and time which will be expended on the remaining activities of testing and evaluating may be lost or rendered useless by an improper sampling technique on the part of the Aggregate Inspector. In other words, if the sample you take is not representative of the total material, it is absolutely impossible to end up with a test result that means anything. At the completion of instruction you must know how to obtain a proper sample. Without this knowledge, it is useless to proceed further into the areas of test procedure.

*No other single phase of an Aggregate Inspector's duties is as important as obtaining a representative sample.*

#### **Sampling Frequency**

Minimum sampling and testing frequencies required at the time of aggregate production are listed in I.M. 209, appendix C. The required minimum aggregate sampling and testing frequencies of aggregates at time of use (proportioned aggregate) are listed in the appendices of I.M. 204. Sampling frequencies listed are minimums and may need to be increased for reasons such as low or intermittent production and widely varying or noncomplying test results.



### **Size of Sample**

Refer to **Materials I.M. 301 in the Field Testing Manual**. Appropriate minimum aggregate sample sizes for the determination of sieve analysis are listed on page 2 of this I.M. The sample sizes are based on the maximum particle size in the finished products.

### **Random Sampling**

The sample must be representative of the total of the material being tested. This is normally accomplished by random sampling. The random sample should not be obtained because of any particular reason or notion. All material produced should have an equal chance of being tested. The inspector should not determine when or what to sample by judging if the material looks good, bad, or average, because that represents a judgement sample and not a random sample. Random samples are taken when the plant is operating at the usual rate for that plant.

It must be pointed out that not all test samples are random samples. Normally they will be the same, but there will be times when the inspector must choose the time of sampling such as new hammers placed on the secondary crusher, an area of clay in the quarry, or fine sand seams in a gravel pit. These things will directly affect gradation of the material and must be checked immediately to keep the material within proper limits. During a normal day's operation, all samples taken and tested may be random samples if all operations are running consistently. Some days will have no random samples taken, such as the first days to establish crusher settings, etc. Some days will have a combination of random and check samples. Keep in mind that during



normal, steady production the samples should be taken on a random basis to represent the total of the material being produced.

### **Location for Sampling**

To help assure that representative samples are taken, one of the following methods will be used for obtaining aggregate samples: 1) obtaining a portion of the material carried on a conveyor belt, 2) intercept the complete material streamflow from the end of a conveyor belt or from overhead bin discharge, 3) sampling from the production stockpile (only for fine aggregate or as directly by the Transportation Center Materials Engineer). The preferred method of coarse aggregate sampling is the streamflow method.

Whichever sampling method is used, at least three separate increments must be taken for each field sample. Obtaining more than three increments, when possible, will better represent the material being tested by providing a wider cross-section of the product.

The field sample must also meet the minimum weight requirement as listed in I.M. 301 for the product being tested.

To obtain an off-the-belt sample, stop the belt, insert a template at three or more separate locations along the belt, remove all material within the template, and combine it into the field sample. In belt sampling, the ends of the template should be spaced just far enough apart to get an increment that weighs approximately one-third the minimum weight of the field sample. If the template does not yield the minimum size of field sample in three locations, additional locations will be necessary. No less than three separate locations should be used in obtaining one field sample. All material within each

### ***Methods for Obtaining Aggregate Samples:***

- \*Off the Belt Sampling*
- \*Streamflow Sampling*
- \*Stockpile Sampling*  
*(fine aggregate only)*

#### **1. Conveyor Belt Sampling**



#### **2. Streamflow Sampling**





increment is removed from all three or more increments and mixed back together to make one field sample. When obtaining field sample by interception of aggregate streamflow, care must be exercised so that the sampling device passes quickly through the entire streamflow and does not overflow. At least three separate passes shall be made with the sampling device

when obtaining a field sample. Each pass is an increment of the field sample.

Stockpile sampling of fine aggregate may be accomplished by either using a shovel or a sand probe. When obtaining a field sample by the stockpile method, a minimum of three increments at different locations around the pile shall be taken. Care should be used not to sample at the bottom of the stockpile. Stockpile sampling of coarse aggregate should be avoided. If it becomes absolutely necessary to obtain a sample from a stockpile, consult the District Materials Engineer to help you devise an adequate sampling plan.

### **Sampling Records**

It is the responsibility of the aggregate sampler to get all the necessary information to fill out report headings. This includes type of material, intended use, location of producer, source, project number (if one is available), contractor who will be receiving the material, and other general information. The information on the source itself should include section of the quarry or pit and the bed numbers (quarries) or working depths (pit). If special processing equipment is used, it should be noted on the reports.

Samples are taken for either 1) field testing or 2) Central Laboratory testing. Those samples which are forwarded to the Central Laboratory of the Iowa DOT should be placed in a standard canvas sack

*No less than three separate locations or passes should be used in obtaining one field sample.*

3a. Stockpile Sampling: Sand Tube



3b. Stockpile Sampling: Shovel



*It is not always easy to get a proper sample, but it is very important to use all the care you can. Always remember, if your sample is not representative, your test results are not worth the paper they are written on.*



and securely tied to prevent loss of material during shipping. Appropriate Form 82003 should be filled out completely and placed inside the sample sack. Other identification tags should be attached to the tie for shipping information.

use square headed shovels for sand sampling

## **Review**

**Before you start out to take a sample, you should ask yourself these questions:**


1. Are you sure that your plan for getting the sample is complete?
2. Have you checked on the approved method of taking the sample?
3. Do you know the weight of sample that is required?
4. Do you have the proper tools?
5. Do you have clean containers at hand for the sample?

**After you have obtained the sample, you should ask yourself these questions:**

1. Are you sure the sample really represents the material?
2. Should you divide the sample and retain part of it?
3. Is the sample completely identified?
4. Does your record show the nature of the material, its intended use, and exactly when, where, and how the sample was taken?
5. Do you know the proper action to take if the sample fails to meet specification requirements?



# NOTES





October 26, 1999  
Supersedes April 27, 1999

Matls. I.M. 208

---

## MATERIALS LABORATORY QUALIFICATION PROGRAM

### GENERAL

The FHWA has outlined a Laboratory Qualification Program in the Federal-Aid Policy Guide update published as 23 CFR 637 on June 29, 1995. The updated guide has requirements for laboratories performing testing on Federal-Aid highway projects on the National Highway System (NHS). The Iowa DOT must implement the program for laboratory qualification by June 29, 2000.

### LABORATORIES TO BE QUALIFIED

The following laboratories will be included in the qualification program for all projects on Interstate and primary routes:

Central Materials Laboratory  
6 Transportation Center (TC) Laboratories  
TC Area Laboratories  
Resident Construction Laboratories  
Aggregate Producer Laboratories

Ready Mix Laboratories  
PCC Contractor Laboratories  
ACC Contractor Laboratories  
Consultant and Commercial Laboratories \*  
City Laboratories \*

\* May be qualified at the time of a project.

### LABORATORY QUALIFICATION PROCESS

A two-level qualification system is required by the FHWA. Laboratories are either accredited or qualified. The accreditation process is more rigorous than the qualification process.

#### **Accredited Laboratory Process**

The Central Materials Laboratory and the six TC Laboratories will be accredited as outlined in the 23 CFR 637 guide. The Central Materials Laboratory is accredited through the AASHTO Materials Reference Laboratory Program. The TC Materials Laboratories will be accredited by using the Central Materials Staff and equipment to check testing and testing procedures and by using the same calibration and training documentation process. Laboratories will be accredited for a two-year period. In addition, an annual review will be made by the Central Office Staff. Appendix A contains the procedures for accrediting the Transportation Center Materials Laboratories.



---

### **Qualified Laboratory Process**

The remaining laboratories will be qualified as outlined below:

The Transportation Center Materials Offices will qualify laboratories. Laboratories will be qualified for a two-year period. In addition, an annual review will be made by TC Staff. Appendix B contains the procedures for qualifying materials laboratories.

Three laboratory types will be qualified, aggregate laboratories, PC Concrete laboratories and asphalt mix laboratories.

Qualified laboratories will have the following:

1. Current manuals and test methods to perform the qualified testing available.
2. A technician certified by the Iowa DOT to perform the qualified testing.
3. Proper equipment to perform the qualified testing (calibrated or checked annually according to Appendix B).
4. Satisfactory correlation and proficiency test results.
5. Documentation of equipment calibrations, equipment checks, and correlation results.

### **ADMINISTRATION OF THE PROCESS**

The Central Materials Laboratory will be responsible for implementation and operation of the Laboratory Qualification Program. The Central Materials Laboratory will accredit the TC Laboratories. The Transportation Center Materials Offices will qualify laboratories.

### **NON-COMPLIANCE/DISPUTE RESOLUTION**

A laboratory that does not meet the requirements of the I.M. is subject to elimination from the qualification program.

Disputes concerning calibration and correlation of equipment will be resolved by the office responsible for the qualification. For disputes that cannot be resolved at the Transportation Center, the Central Materials Laboratory will be the final authority.



---

**\*\*\*\*GENERAL RE-WRITE - PLEASE READ CAREFULLY\*\*\*\***

**APPENDIX A  
TC LABORATORY ACCREDITATION PROGRAM**

The Central Materials Laboratory (CML) will accredit the Transportation Center Materials Laboratories and maintain records of the accreditation for five years. The CML Staff will check the following prior to accrediting a laboratory:

1. Check for current manuals and test procedures covering the accredited testing.
2. Check the certification and training records of the testing personnel.
3. Document that proper equipment is available to perform qualified testing.
4. Check documentation system.

Scheduling of the annual accreditation review will be discussed with the laboratories needing accreditation.

Table 1 is the list of items to be reviewed.

An oral close out on any deficiencies will be held with the testing personnel. Written notice will be sent within two months of the inspection. CML personnel will re-inspect if necessary after correction of any deficiencies.

A report showing the laboratory, the date accredited, and the expiration date will be issued by the Materials Testing Engineer.

**NON-COMPLIANCE/ DISPUTE RESOLUTION**

A laboratory that does not meet the requirements of the I.M. is subject to elimination from the qualification program.

The CML and the Transportation Center Materials Engineer will resolve disputes concerning calibration and correlation of equipment.



**Table 1. Laboratory Accreditation Checklist**

	✓	<b>Minimum Calib./Verif. Interval</b>	<b>Calib./Verif. Procedure</b>
Tester Qualifications-Proper Iowa DOT certifications			
Current Written Test Procedures			
Current Calibration Procedures & Records			
Documentation of correlation results and corrective actions taken for previous construction season			
Balances		12 months	Iowa 917-A
Ovens		4 months	In-House Procedure #1
Mechanical Shakers		12 months	In-House Procedure #2
Marshall Compactor T-245		12 months	In-House Procedure #4
Gyratory Compactor TP-4		6 months	In-House Procedure #22
Marshall Molds T-245		12 months	In-House Procedure #23
Comp. Test Machine T-245		12 months	In-House Procedure #5
Sieves		6 months	In-House Procedure #6
Thermometers - Test		6 months	In-House Procedure #7
Thermometers - Ref.		12 months	In-House Procedure #7
Timers T-201, T-202		6 months	In-House Procedure #8
Sand Equivalent T-176		12 months	In-House Procedure #9
Gyratory Compactor Molds TP - 4		12 months	In-House Procedure #24
Vacuum Systems T-209		12 months	In-House Procedure #10
Pycnometers T-228, T209		12 months	In-House Procedure #18
Fine Aggregate Anularity TP33		12 months	In-House Procedure #25
Dynamic Shear Rheometer TP5-97		6 months	In-House Procedure #12
Balance Weights		12 months	In-House Procedure #30
Sample Splitters		12 months	



---

## **APPENDIX B LABORATORY QUALIFICATION PROGRAM**

The District (DISTRICT) Materials Office will qualify the other laboratories and maintain records of the qualification for three years. The District Staff will check the following prior to qualifying a laboratory:

1. Establish the type of laboratory (Aggregate, Asphalt Mix, PC Concrete).
2. Check for current manuals and test procedures covering the qualified testing.
3. Check the certification of the testing personnel.
4. Document that proper equipment is available to perform qualified testing.
5. Check documentation system.

Scheduling of the qualification review will be discussed with the laboratories seeking qualification. The District Materials Engineer should be contacted for laboratories that have been qualified in other states. The District Materials Office may qualify a laboratory based on an acceptable qualification report and qualification program from another state transportation agency.

Table 1 and the pages following cover the list of items to be reviewed.

An oral close out on any deficiencies will be held with the testing personnel. Written notice will be sent within two weeks of the inspection. District personnel will re-inspect after correction of any deficiencies.

A form showing the laboratory type, the date qualified, and the expiration date will be issued by the District Materials Engineer.

The list of Qualified Laboratories will be maintained on a database accessible by authorized Materials Personnel.

### **NON-COMPLIANCE/ DISPUTE RESOLUTION**

A laboratory that does not meet the requirements of the I.M. is subject to elimination from the qualification program.

The office responsible for the qualification will resolve disputes concerning calibration and correlation of equipment. For disputes that cannot be resolved at the District level, the Central Materials Laboratory will be the final authority.



**Table 1. Laboratory Qualification Checklist**

	<b>Calib./Verif. Interval</b>	<b>Calib./Verif. Procedure</b>
Tester Qualifications-Proper Iowa DOT certifications		
Current Written Test Procedures		
Current Calibration Procedures & Records		
Documentation of correlation results and corrective actions taken for previous construction season.		
<b>Aggregate Laboratory</b>		
Balances	12 months	Iowa 917-B
Sieves- wear, tear, size, and opening size	12 months	
Splitter- condition	12 months	
Mechanical Shakers- condition (if used)	12 months	
<b>ACC Laboratory</b>		
Balances- and water bath	12 months	Iowa 917-B
Sieves- wear, tear, size, and opening size	12 months	
Splitter- condition	12 months	
Mechanical Shakers- condition (if used)	12 months	
Rice equipment- vacuum and flask	12 months	IM 350
Thermometers	12 months	
Ovens- temperatures	12 months	
Gyratory Compactor and molds	12 months	Manufacturer Rec.
Marshall Hammer and molds	12 months	Correlation Checks
<b>PCC Laboratory</b>		
Balances	12 months	Iowa 917-B
Sieves- wear, tear, size, and opening size	12 months	
Splitter- condition	12 months	
Mechanical Shakers- condition (if used)	12 months	
Air Meter	12 months	IM 318
Slump Cone and equipment-condition	12 months	
Beam Breaker	12 months	Central Lab





**Iowa Department of Transportation**

**MATERIALS LABORATORY QUALIFICATION PROGRAM**  
Laboratory Inspection - per Materials Instructional Memorandum 208

Company Name: \_\_\_\_\_

Laboratory name: \_\_\_\_\_

Laboratory type:                      Aggregate                      ACC                      PCC                      (Circle one)

Laboratory location: \_\_\_\_\_

Laboratory contact person: \_\_\_\_\_

Laboratory technician:                      Certification number:                      Expires:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Current manuals and written test procedures available? \_\_\_\_\_

Current calibration procedures and records? \_\_\_\_\_

\_\_\_\_\_

Documentation of correlation results and corrective actions taken for previous construction season? \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Proper equipment available to perform qualified testing? \_\_\_\_\_

\_\_\_\_\_

Other remarks: \_\_\_\_\_

\_\_\_\_\_

Date of inspection: \_\_\_\_\_ Qualification expiration date: \_\_\_\_\_

Inspection performed by: \_\_\_\_\_

print name

sign name

Inspection received by: \_\_\_\_\_

print name

sign name

District Number \_\_\_\_\_

cc: Materials Engineer, Contractor/Producer, Ames, File



Iowa Department of Transportation

**AGGREGATE LABORATORY INSPECTION  
QUALITY CONTROL CHECKLIST**

Contractor/Producer: \_\_\_\_\_ Location: \_\_\_\_\_  
Certified Technician: \_\_\_\_\_ Certification No.: \_\_\_\_\_

Balances	(Iowa Test Method 917-B)	Yes	No
	Updated balance calibration records available?	_____	_____
	Check balance using 500 gm & 1000 gm calibrated weights?	_____	_____
	Is balance accurate to 0.1%?	_____	_____
Sieves			
	Is there adequate correlation history to qualify?	_____	_____
	Were go no-go gauges used to check accuracy?	_____	_____
	Are the sieves in good condition (no loose frames, holes, or tears.)	_____	_____
Splitter			
	Is the splitter in good condition? (i.e., missing chutes, cracked welds, or leaking seams)	_____	_____
Shaker			
	Is shaker apparatus secure and level?	_____	_____

Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

cc: Materials Engineer  
Contractor/Producer  
Ames  
File

Inspected By: \_\_\_\_\_

Date Inspected: \_\_\_\_\_





Iowa Department of Transportation

ACC LABORATORY INSPECTION  
QUALITY CONTROL CHECKLIST

Contractor/Producer: \_\_\_\_\_ Location: \_\_\_\_\_

Certified Technician: \_\_\_\_\_ Certification No.: \_\_\_\_\_

Thermometers ( I. M. 350 )	Yes	No
Thermometer Calibration and Documentation available?	_____	_____

Temperature of check: _____ ( 25 deg C. or 135 deg C.)		
state reference thermometer _____		
contractor reference thermometer _____		
difference _____		
Calibration Chart? _____	_____	_____

Rice Pycnometer ( I.M. 350 )	Yes	No
Calibration documentation available?	_____	_____
Equipment achieves less then 30mm of mercury vacuum?	_____	_____
Mercury is free of bubbles?	_____	_____

Gyratory/Marshall Compactor ( AASHTO TP - 4 )/(I. M. 325)	Yes	No
Calibration documentation available?	_____	_____
Is equipment generally clean?	_____	_____
Documentation of annual mold measurements?	_____	_____

Ovens ( I.M. 325 )	Yes	No
Documentation of temperature checks?	_____	_____
General condition satisfactory?	_____	_____
Do all parts work as intended?	_____	_____

Water Bath ( I.M. 321 )
Temperature? _____

Correlation	Yes	No
Lab Chief advised correlation results needed for following year?	_____	_____

Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

NOTE: ACC labs must also qualify as an aggregate Lab.

cc: Materials Engineer	Inspected By: _____
Contractor/Producer	
Ames	Date Inspected: _____
File	





Iowa Department of Transportation

READY MIX/PCC PAVING LABS  
QUALITY CONTROL CHECKLIST

Contractor/Producer : \_\_\_\_\_ Location: \_\_\_\_\_

Certified Technician : \_\_\_\_\_ Certification No : \_\_\_\_\_

Inspection Checklist Items:

Air Meter	(I.M. 318)	Yes	No
Check meter using approved 5% pugs. (optional)		_____	_____
Is air meter clean?		_____	_____
Proper rod and mallet.		_____	_____
Slump Cone	(I.M. 317)		
Interior of cone free of dents or projections.		_____	_____
5/8" by 24" tamping rod.		_____	_____
Rigid, nonabsorbent base.		_____	_____
Equipment clean and free of hardened concrete.		_____	_____
Beam Breaker	(I.M. 316)		
Current annual calibration sheet		_____	_____
Equipment clean.		_____	_____
Beam Molds	(I.M. 328)		
Molds clean and free of dents		_____	_____
General condition of molds good.		_____	_____

Comments \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

NOTE: PCC labs must also qualify as an aggregate Lab.

cc: Materials Engineer  
Contractor/Producer  
Ames  
File

Inspected By: \_\_\_\_\_  
Date Inspected: \_\_\_\_\_



---

## APPENDIX C INTERLABORATORY CORRELATION TESTING

### **GENERAL**

Each Transportation Center Laboratory shall establish and maintain their testing credibility by following the correlation-testing program described herein. The testing precision data listed in this I.M. shall apply to correlation of test results between the Iowa DOT and a contractor's laboratory.

### **CORRELATION SAMPLE**

The remaining portion of a project control sample may be submitted to the Central Laboratory for testing. This sample shall be re-identified showing the intended use to be: Correlation testing, project number, and department information.

### **CORRELATION FREQUENCY**

Each Transportation Center Laboratory shall correlate the following tests at a frequency of at least once per month. The frequency may be increased for problem situations at the discretion of the Transportation Center Materials Engineer.

1. Asphalt Cement
  - a. DSR Stiffness  $G^*/\sin \delta$
  - b. Specific Gravity @ 15.6°C (60°F)
2. Emulsified Asphalt
  - a. Percent Residue
3. Asphalt Mixtures
  - a. Gyratory Density
  - b. Gyratory Slope
  - c. Marshall Density
  - d. Maximum Specific Gravity



4. Aggregate
  - a. Gradation of Combined Aggregate
  - b. Specific Gravity of Aggregate for Mix Design
  - c. Absorption of Aggregate for Mix Design
  - d. Fine Aggregate Angularity

#### **TESTING PRECISION**

1. Asphalt Cement
  - a. Penetration. The two results shall not differ from their mean by more than 8 percent of their mean.
  - b. Absolute Viscosity. The two results shall not differ from their mean by more than 10 percent of their mean.
  - c. Specific Gravity. The two results shall not vary by more than 0.005.
  - d. DSR Stiffness. The two results shall not differ from their mean by more than 10 percent of their mean.
2. Emulsified Asphalt
  - a. Percent Residue. The two results shall not differ by more than 2 percent.
3. Cut-Back Asphalt

The two results shall not differ from their mean by more than 3 percent of their mean for material having a viscosity of less than 800 cst and 9 percent of their mean for material having viscosity between 800 to 6000 cst.
4. Asphalt Mixture
  - a. Asphalt Content by Extraction. The two results shall not differ by more than 0.3 percent.
  - b. Gradation of Extracted Aggregate. The two results shall meet the precision parameters prescribed in I.M. 216.
  - c. Asphalt Content by Nuclear Gauge. The two results shall not differ by more than 0.3 percent.
  - d. Marshall and Gyratory Density. The two results shall not differ by more than 0.02.
  - e. Maximum Specific Gravity. The two results shall not differ by more than 0.01.



5. Aggregate

- a. Gradation of Combined Aggregate. The two results shall meet the precision parameters prescribed in I.M. 216.
- b. Bulk Dry Specific Gravity for Mix Design. The difference between the two results shall not be more than 0.028.
- c. Absorption of Aggregate for Mix Design. The difference between the two results shall not be more than 0.37 percent.
- d. Apparent Specific Gravity for Mix Design. The difference between the two results shall not be more than 0.01.
- e. Fine Aggregate Angularity. The difference between the two results shall not be more than 0.5.

Other tests such as kinematic viscosity, specific gravity of asphalt cement and penetration of emulsion residue may be correlated at the discretion of the Transportation Center Materials Engineer.





# NOTES







---

## GENERAL AGGREGATE SOURCE INFORMATION

### GENERAL

Generally, only those sources, which have been sampled or tested within the last ten years, are listed. This listing additionally ranks sources in accordance with a frictional classification as defined herein for aggregates used in asphalt construction, and a durability class for coarse aggregates used in Portland Cement Concrete construction. Upon request, new sources or different combinations of beds within an existing source can be evaluated for classification for either type of use. These rankings do not in any way waive the normal quality requirements for the particular types of aggregates indicated in contract documents.

### PORTLAND CEMENT CONCRETE AGGREGATES

Aggregates shall be produced from sources approved in accordance with the requirements of Office of Materials I.M. 409. The engineer may approve scalping of some portion of the coarser fraction.

All aggregates produced and inspected for intended use in contracts under Iowa Department of Transportation Specifications shall be stored in identifiable stockpiles unless they are being delivered as produced.

### DURABILITY CLASSIFICATION

The coarse aggregates have been divided into three classes in accordance with their durability level as determined by performance or laboratory testing.

Class 2 durability aggregates will produce no deterioration of pavements of the non-interstate segments of the road system after 15 years and only minimal deterioration in pavements after 20 years.

Class 3 durability aggregates will produce no deterioration of pavements of non-interstate segments of the road system after 20 years of age and less than 5% deterioration of the joints after 25 years.

Class 3i durability aggregates will produce no deterioration of the interstate road system after 30 years of service and less than 5% deterioration of the joints after 35 years.

**NOTE:** Those sources with a "B" in their durability class designation may have ½ in. Bridge Deck Overlay/Repair material available.



---

## **ASPHALTIC CONCRETE AGGREGATES**

Aggregates for asphaltic construction have been classified into six main functional types in accordance with their frictional characteristics. Those aggregates with the potential to develop the greatest amount of friction under traffic conditions are classified as Type 1 with the potential for friction decreasing as the type number increases. One or more friction types may be specified for use in pavement surface courses. If a type is not specified in the contract documents, Type 5 or better will be acceptable.

When aggregates of friction Type 1 through Type 4 are specified for construction, a source approval including bed limitations is required for each project. Tentative bed limitations are shown in this publication.

The frictional classification types are listed and defined in order of descending quality as follows.

Type 1: Aggregates which are generally a heterogeneous combination of minerals with coarse-grained microstructure of very hard particles (generally, a Mohs hardness range of 7 to 9) bonded together by a slightly softer matrix. These aggregates are typified by those developed for and used by the grinding-wheel industry such as calcinated bauxite (synthetic) and emery (natural). They are not available from Iowa sources. Due to their high cost, these aggregates would be specified only for use in extremely critical situations.

Type 2: Natural aggregates in this class are crushed quartzite and granites. The mineral grains in these materials generally have a Mohs hardness range of 5 to 7. Synthetic aggregates in this class are some air-cooled steel furnace slags and others with similar characteristics.

Type 3: Natural aggregates in this class are crushed traprocks, and/or crushed gravels. The crushed gravels shall not contain more than 60 percent total carbonate. Synthetic aggregates in this class are the expanded shales with a Los Angeles abrasion loss less than 35 percent.

Type 4: Aggregates crushed from dolomitic or limestone ledges in which 80 percent of the grains are 20 microns or larger. The mineral grains in the approved ledges for this classification generally have a Mohs hardness range of 3 to 4. For natural gravels, the Type 5 carbonate (see below) particles, as a fraction of the total material, shall not exceed the non-carbonate particles by more than 20 percent.

Type 4D: A subgroup of the Type 4 category comprised of those aggregates near, but exceeding, the 20-micron minimal grain size. Type 4D aggregates are not acceptable for use in any asphalt cement concrete surface courses requiring the use of Type 4 or better material.

Type 5: Aggregates crushed from dolomitic or limestone ledges in which 20 percent or more of the grains are 30 microns or smaller.



## SOURCE LISTINGS - Explanation

The use of Xs in the PCC or AC columns indicates use where no classification is required or, if required, has not been made.

**NOTE:** - indicates top size limitation.

Bed numbers shown for PCC aggregate are those on the formal source approval letter. Beds shown for AC sources are those which have been used or have potential for use and are of the designated friction type.

Frictional Classification - as indicated on page 2  
Asphaltic Concrete - Type A and B

Durability Class for Portland Cement Concrete  
Coarse Aggregate      Fine Aggregate  
("B" indicates acceptability for Bridge  
Deck Overlay/Repair)

Source Code Number - Used to identify sources  
on test requests and for data storage.

Specific Gravity  
(DWU-Determine When Used)

CODE	OPERATOR	SOURCE NAME	LOCATION	SP GR	DUR POC CA FA	FRICT AC A B	BEDS
04	APPANOOSE SEITC	---CRUSHED STONE---					
A04004	L&W QUARRIES INC	MARTIN #3	E2 20 T070 R19W 2.70	2		4D 4D	1 - 3 :1
54	KEOKUK SEITC	---CRUSHED STONE---					
A54002	KASER CORP	KESWICK	NW 21 T077 R12W 2.61	2		4 4	:13 -15 :2
55	KOSSUTH NEITC	---SAND & GRAVEL---					
A55520	GIESE CONST CO	CONN	SE 35 T095 R29W DWU		X		:3
56	LEE SEITC	---CRUSHED STONE---					
A56004	CESSFORD CONST CO	FRANKLIN	NE 25 T068 R06W 2.49	2			12 :2

NOTES: 1 - AASHTO D-67, GRADATION #5, 40% MAXIMUM  
2 - AASHTO 57 GRADATION MAXIMUM  
3 - APPROVED ONLY FOR L-MIX PC CONCRETE



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
01	ADAIR	DIST. 4	---CRUSHED STONE---				
A01002	SCHILDBERG CONST CO INC	MENLO	SE 17 TO77 R31W	:	:	5 5 :15 -16 :	
A01004	SCHILDBERG CONST CO INC	JEFFERSON	NW 17 TO77 R31W	:	:	4 : 14 :	
A01006	SCHILDBERG CONST CO INC	HOWE	SW 01 TO76 R31W	:	:	5 : 25 :	
*****							
02	ADAMS	DIST. 4	---CRUSHED STONE---				
A02002	SCHILDBERG CONST CO INC	MT ETNA	SW 23 TO73 R34W	:	:	4 :11 -13 :	
A02004	SCHILDBERG CONST CO INC	CORNING	10 TO71 R34W	:	:	4 : 3 - 5 :	
---SAND & GRAVEL---							
A02502	SCHILDBERG CONST CO INC	MT ETNA	NW 23 TO73 R34W	2.67 : 2	:	4 4 :	
*****							
03	ALLAMAKEE	DIST. 2	---CRUSHED STONE---				
A03002	BRUENING ROCK PROD INC	WEXFORD	NE 36 TO98 R03W	2.70 : 3i	:	1C- 5 :	
A03008	BRUENING ROCK PROD INC	MCCABE	NE 06 TO97 R05W	:	:	4 : 1 - 8 :	
A03014	BRUENING ROCK PROD INC	HAMMELL-BOONIES	SW 02 TO99 R06W	:	X	4 : 4 : 5 - 6 :	
A03022	ROVERUD CONST INC	LIVINGOOD	SW 07 TO96 R06W	:	:	4 : 4 : 4 - 7 :	
A03028	ROVERUD CONST INC	WELPER-JOHNSON	SW 35 TO99 R04W	:	:	4 : 2 - 7 :	
A03034	BRUENING ROCK PROD INC	WILDE	SE 13 TO99 R05W	:	X	4 : 4 : 1 - 5 :	
A03038	BRUENING ROCK PROD INC	RHEIM	SE 07 T100 R04W DWU	:	3i	4 : 4 : 1 - 4 :	
A03040	BRUENING ROCK PROD INC	DEE	SE 21 TO99 R04W DWU	:	3iB	4 : 4 : 5A- 5D :	
A03042	NIEMANN CONST CO	CHURCHTOWN	SW 29 TO99 R04W	:	:	4 : 1 - 3 :	
A03046	BRUENING ROCK PROD INC	MOHS	SW 29 TO96 R04W DWU	:	2	5 : 5 : 1 - 2 :	
A03048	BRUENING ROCK PROD INC	POSTVILLE	SW 16 TO96 R06W	:	:	4 : 2 - 5 :	
A03050	BRUENING ROCK PROD INC	GREEN	NW 16 TO96 R06W	2.63 : 3	:	4 : 4 : 2 - 3 :	
A03052	BRUENING ROCK PROD INC	ROSSVILLE	NE 35 TO97 R05W DWU	:	:	4 : 4 : 1 - 5 :	
A03054	BRUENING ROCK PROD INC	WEST RIDGE	NE 08 TO98 R06W	:	:	:	
A03056	NIEMANN CONST CO	WAUKON	SW 05 TO97 R05W	:	:	:	
A03060	NIEMANN CONST CO	HANOVER	NE 36 TO99 R06W	:	:	:	
A03064	WILTGEN CONST CO	RAINBOW ACRES	SE 26 TO97 R02W	:	:	:	
A03066	WILTGEN CONST CO	ELSBERN	NW 29 TO97 R06W	:	:	:	
---SAND & GRAVEL---							
A03502	CARLSON MATERIALS CO	HARPERS FERRY	SW 07 TO97 R02W	2.67 : 3iB	:	3 3 :	
A03506	BRUENING ROCK PROD INC	HAMMELL-BOONIES	SW 02 TO99 R06W	2.67 :	X	:	
A03510	CARLSON MATERIALS CO	LONNING	SE 02 TO99 R06W	:	:	4 4 :	
A03512	ROVERUD CONST INC	ZEZULKA	NE 11 T100 R04W	DWU :	X	:	
*****							
04	APPANOOSE	DIST. 5	---CRUSHED STONE---				
A04004	L&W QUARRIES INC	MARTIN #3	E2 20 TO70 R19W	2.70 : 2	:	4D 4D: 1 - 3 :1	
A04016	L&W QUARRIES INC	LEMLEY EAST #5	CT 35 TO70 R19W	2.70 : 2	:	4D 4D: 1 - 3 :1	
A04018	L&W QUARRIES INC	CLARKDALE #8	SE 15 TO69 R18W	:	:	5 : 4 :	
*****							

NOTE:

1 - AASHTO 67, GRADATION #5, 40% MAXIMUM; RESTRICTION DOES NOT APPLY TO STRUCTURAL CONCRETE



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK		DUR	FRICT		
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD	PCC	CA	FA	AC	BEDS
*****									
05	AUDUBON	DIST. 4	---						
A05506	HALLETT MATERIALS CO	EXIRA	SW 08 TO78	R35W	2.64	:	3	:	4 4 :
					2.66	:		X :	:
*****									
06	BENTON	DIST. 6	---						
A06002	BASIC MATERIALS CORP	SMITH	NW 19 TO86	R12W	2.65	:	2	:	4 4 :21 -26 :
A06004	WENDLING QUARRIES INC	GARRISON A	SE 28 TO85	R11W	2.67	:	2	:	4 4 : 6 -16 :
A06006	WENDLING QUARRIES INC	GARRISON B	NE 33 TO85	R11W	2.64	:	2	:	4 4 : 6 -16 :
A06008	WENDLING QUARRIES INC	BALLHEIM	NE 17 TO86	R12W	:	:	:	:	X :
A06012	COOTS MATERIALS CO INC	JABENS	SW 07 TO85	R11W	DWU	:	2	:	6 -11 :
					2.63	:	2	:	4 4 : 12 :
					:	:	4	:	4 4 :10 -12 :
A06014	WENDLING QUARRIES INC	VINTON-MILROY	S2 10 TO85	R10W	:	:	:	:	4 :
A06016	COOTS MATERIALS CO INC	COOTS	SW 36 TO86	R11W	:	:	:	:	X :
A06018	WENDLING QUARRIES INC	PORK CHOP-EAST	NW 11 TO85	R09W	:	:	:	:	X :
A06020	WENDLING QUARRIES INC	PORK CHOP-WEST	NE 10 TO85	R09W	:	:	:	:	:
A06022	WENDLING QUARRIES INC	LONG	SE 13 TO84	R09W	:	:	:	:	X :
---SAND & GRAVEL---									
A06502	WENDLING QUARRIES INC	VINTON-MILROY	S2 10 TO85	R10W	:	:	:	:	4 4 :
					2.65	:		X :	:
A06504	COOTS MATERIALS CO INC	MT AUBURN	SW 31 TO86	R10W	:	:	:	:	4 4 :
					2.65	:		X :	:
A06506	WENDLING QUARRIES INC	PORK CHOP	CT 11 TO85	R09W	:	:	:	:	4 4 :
					DWU	:		X :	:
*****									
07	BLACK HAWK	DIST. 2	---						
A07004	BASIC MATERIALS CORP	WATERLOO SOUTH	NW 18 TO87	R12W	:	:	:	:	4 4 :17 -23 :
					:	:	:	4	4 :32 -36 :
					:	:	:	4	: 1 -16 :
A07006	BASIC MATERIALS CORP	YOKUM	NE 05 TO90	R14W	:	:	:	:	5 :11 -21 :
A07008	BASIC MATERIALS CORP	MORGAN	NE 15 TO89	R12W	:	:	:	:	5 : 1 - 3 :
					:	:	:	5	: 4A- 4B:
A07014	NIEMANN CONST CO	GLORY	NE 36 TO87	R11W	:	:	:	:	4 : 3 - 4 :
					:	:	:	5	: 1 - 4 :
A07018	BASIC MATERIALS CORP	RAYMOND-PESKE	SW 01 TO88	R12W	2.66	:	2	:	4 4 : 1B- 5 :
					:	:	:	4	4 : 6 -10 :
A07020	BASIC MATERIALS CORP	STEINBRON	SE 01 TO88	R11W	2.62	:	3i	:	X X : 1 :
---SAND & GRAVEL---									
A07504	BASIC MATERIALS CORP	WATERLOO SAND	SW 09 TO89	R13W	:	:	:	:	4 4 :
					2.65	:		X :	:
A07506	MANATTS INC	ASPRO	NW 01 TO88	R13W	:	:	:	:	4 4 :
					2.65	:		X :	:
A07508	BASIC MATERIALS CORP	GILBERTVILLE	16 TO88	R12W	:	:	:	:	4 4 :
					2.65	:		X :	:
A07512	ZEIEN S&G	ZEIEN	NW 23 TO87	R12W	:	:	:	:	:
A07518	NIEMANN CONST CO	JANESVILLE	NE 14 TO90	R14W	:	:	:	:	3 3 :
					2.66	:		X :	:
*****									
08	BOONE	DIST. 1	---						
A08520	MARTIN MARIETTA	LAUBE	36 TO85	R27W	:	:	:	:	4 4 :
A08524	HALLETT MATERIALS CO	JENKINS-STURTZ	W2 36 TO84	R27W	2.69	:	2	:	3 3 :
					2.66	:		X :	:
*****									



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK SSD	DUR PCC	FRICT AC			
CODE	OPERATOR	SOURCE NAME	LOCATION	SpGr	CA	FA	A	B	BEDS
*****									
09	BREMER	DIST. 2	---CRUSHED STONE---						
A09002	BASIC MATERIALS CORP	FREDERIKA	NE 12 T093	R13W	:	:	5	: 2 - 8 :	
A09004	NIEMANN CONST CO	DENVER-FOELSKE	NE 29 T091	R13W	:	:	4	4 : 4 - 9 :	
A09006	NIEMANN CONST CO	TRIPOLI-PLATTE	SW 36 T093	R13W 2.65	: 3i	:	4	4 : 1 - 3 :	
A09008	NIEMANN CONST CO	DENVER #2	NE 29 T091	R13W	:	:	:	:	
-----SAND & GRAVEL-----									
A09504	NIEMANN CONST CO	NOLTE	SE 31 T092	R11W	:	:	4	4 :	:
				2.65	:	X :	:	:	:
A09508	NIEMANN CONST CO	TRIPOLI-PLATTE	SW 36 T093	R13W	:	:	:	:	:
A09510	NIEMANN CONST CO	PLAINFIELD/ADAMS	NE 32 T093	R14W 2.66	:	X :	:	:	:
*****									
10	BUCHANAN	DIST. 6	---CRUSHED STONE---						
A10002	NIEMANN CONST CO	WESTON-LAMONT	NW 14 T090	R07W 2.61	: 3iB	:	:	1 - 6 :	:
				:	:	:	4	4 : 1 - 7 :	:
A10004	NIEMANN CONST CO	BLOOM-JESUP	SW 32 T089	R10W 2.63	: 3	:	:	2 - 5 :	:
				:	:	:	4	4 : 1 - 7 :	:
A10008	BRUENING ROCK PROD INC	OELWEIN	NW 02 T090	R09W 2.65	: 3i	:	4	4 : 4 - 5 :	:
				:	:	:	4	4 : 4 - 6 :	:
A10010	NIEMANN CONST CO	HAZELTON	NW 11 T090	R09W 2.65	: 3iB	:	4	4 :	4 :
A10012	NIEMANN CONST CO	INDEPENDENCE	NW 14 T088	R09W	:	:	5	:	:
A10014	NIEMANN CONST CO	OELWEIN #1	SW 02 T090	R09W	:	:	5	5 : 1 - 12 :	:
A10016	NIEMANN CONST CO	OELWEIN #2	SE 03 T090	R09W DWU	: 3i	:	4	4 : 13 - 16 :	:
A10018	NIEMANN CONST CO	EAST AURORA	SE 17 T090	R07W	:	:	4	4 : 1 - 5 :	:
A10022	BRUENING ROCK PROD INC	BROOKS	NW 02 T088	R09W 2.55	: 3i	:	4	4 : 7 :	:
				:	:	:	5	1 - 6 :	:
A10024	NIEMANN CONST CO	RASMUSSEN #2	SE 21 T088	R08W	:	:	5	:	:
A10026	NIEMANN CONST CO	BRANDON	SE 27 T087	R10W	:	:	5	:	:
A10028	NIEMANN CONST CO	HERTZBERGER	NE 36 T087	R10W	:	:	5	:	:
A10030	NIEMANN CONST CO	SOUTH AURORA	NW 19 T090	R07W 2.65	: 3iB	:	4	1 - 3 :	:
A10032	NIEMANN CONST CO	SELLS	NW 25 T088	R09W	:	:	5	:	:
A10034	NIEMANN CONST CO	TROY MILLS	SE 30 T087	R07W	:	:	:	:	:
A10036	WENDLING QUARRIES INC	KILER	NW 34 T087	R10W	:	:	4	:	:
A10038	BASIC MATERIALS CORP	WIDGER	SW 07 T088	R10W 2.61	: 3i	:	:	1B :	:
				:	:	:	4	4 : 1A - 1B :	:
-----SAND & GRAVEL-----									
A10502	MARTIN MARIETTA	COOK	SE 21 T088	R07W	:	:	4	4 :	:
A10504	NIEMANN CONST CO	WARD	NE 14 T090	R07W	:	:	4	4 :	:
				2.65	:	X :	:	:	:
A10506	MANATTS INC	GREENLEY	SE 29 T089	R09W	:	:	4	4 :	:
				2.64	:	X :	:	:	:
A10510	NIEMANN CONST CO	HUFFMAN	SE 02 T089	R08W	:	:	4	4 :	:
				2.65	:	X :	:	:	:
A10514	NIEMANN CONST CO	HOLLERMAN	SE 26 T090	R07W	:	:	4	4 :	:
A10516	NIEMANN CONST CO	MILLER	NW 14 T088	R09W 2.65	:	X :	:	:	:
A10518	MANATTS INC	YEAROUS	SE 19 T089	R10W 2.65	:	X :	:	:	:
*****									
11	BUENA VISTA	DIST. 3	---SAND & GRAVEL---						
A11502	ROHLIN CONST CO INC	ROHLIN	SW 02 T093	R38W	:	:	4	4 :	:
A11504	MARTIN MARIETTA	RAILROAD	NE 03 T093	R37W	:	:	3	3 :	:
A11506	MARTIN MARIETTA	LINN GROVE	NW 25 T093	R38W	:	:	4	4 :	:
A11508	WETHERALL CONST CO	NEWELL	NW 01 T090	R36W	:	:	4	4 :	:
A11510	MARTIN MARIETTA	SIOUX RAPIDS	05 T093	R36W	:	:	3	3 :	:
A11512	BUENA VISTA COUNTY	MARATHON	SE 19 T093	R35W	:	:	4	4 :	:
A11514	WETHERALL CONST CO	STORM LAKE	SW 18 T090	R36W	:	:	4	4 :	:
A11516	ROHLIN CONST CO INC	WERNIMONT	W2 12 T093	R37W	:	:	3	3 :	:
*****									



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK	DUR	FRICT				
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD	PCC	CA	FA	A	B	BEDS
*****										
12	BUTLER	DIST. 2	---CRUSHED STONE---							
A12004	GREENE LS CO	LUBBEN	NW 25 TO93	R17W	:	:	:	5	: 1	-21 :
A12008	GREENE LS CO	FLORRY-STEERE	CT 08 TO93	R17W	:	:	:	5	: 1	-11 :
A12010	CARLSON/BRUENING	CLARKSVILLE-ENGLE	NE 16 TO92	R15W	:	:	:	:	:	:
A12014	NIEMANN CONST CO	OLTMANN	SE 08 TO91	R16W	:	:	:	X	:	X :
A12016	GREENE LS CO	WIEGMANN-BRISTOW	SE 23 TO92	R18W	:	:	:	X	X	: 1 -11 :
A12018	GREENE LS CO	NEYMEYER	SW 28 TO90	R18W	:	:	:	:	:	:
A12020	GREENE LS CO	BRUNS #2	NW 21 TO91	R18W	:	:	:	:	:	:
---SAND & GRAVEL---										
A12502	KNOCKS BLDG SUPPLY	CLARKSVILLE-KNOCKS	NW 01 TO92	R16W	2.67 :	2	:	4	4	:
					2.67 :		X	:	:	:
A12504	SHELL ROCK S&G	BROOKS	NE 02 TO91	R15W	2.66 :	X	:	4	4	:
					2.67 :		X	:	:	:
A12508	GREENE LS CO	AUSTINVILLE	NW 23 TO90	R18W	:	:	:	:	:	:
A12514	GREENE LS CO	DE VRIES	SW 28 TO90	R18W	:	:	:	4	4	:
					2.63 :		X	:	:	:
A12516	GREENE LS CO	JENSEN	S2 18 TO93	R16W	:	:	:	4	4	:
A12518	NIEMANN CONST CO	SHELL ROCK-ADAMS	NE 03 TO91	R15W	:	:	:	3	3	:
					2.66 :		X	:	:	:
*****										
13	CALHOUN	DIST. 3	---SAND & GRAVEL---							
A13502	BECKER GRAVEL CO.	LAKE CITY	NW 23 TO86	R34W	:	:	:	4	4	:
*****										
14	CARROLL	DIST. 3	---SAND & GRAVEL---							
A14506	MARTIN MARIETTA	POUND	SE 18 TO85	R33W	:	:	:	4	4	:
A14510	TIEFENTHALER INC	LANESBORO	NW 17 TO85	R33W	2.72 :	2	:	4	4	:
					2.68 :		X	:	:	:
A14512	MARTIN MARIETTA	OPEN	SE 15 TO84	R34W	:	:	:	4	4	:
A14514	TIEFENTHALER INC	MACKE	06 TO85	R33W	2.69 :	2	:	4	4	:
					2.66 :		X	:	:	:
*****										
15	CASS	DIST. 4	---CRUSHED STONE---							
A15004	SCHILDBERG CONST CO INC	LEWIS	SE 17 TO75	R37W	:	:	:	4	:10	-11 :
A15008	SCHILDBERG CONST CO INC	ATLANTIC MINE	NE 13 TO79	R37W	:	:	:	:	:	:
---SAND & GRAVEL---										
A15502	SCHILDBERG CONST CO INC	LYMAN	NW 33 TO75	R36W	:	:	:	4	4	:
A15504	HALLETT MATERIALS CO	ATLANTIC	NE 06 TO76	R36W	2.67 :	2	:	4	4	:
					2.65 :		X	:	:	:
A15508	HALLETT MATERIALS CO	VALLEY	SW 01 TO77	R36W	2.66 :	3	:	4	4	:
					2.66 :		X	:	:	:
*****										
16	CEDAR	DIST. 6	---CRUSHED STONE---							
A16002	WENDLING QUARRIES INC	HUNT	SW 10 TO81	R04W DWU	:	3iB	:	4	4	:
A16004	WENDLING QUARRIES INC	LOWDEN-SCHNECKLOTH	NW 04 TO81	R01W DWU	:	3i	:	:	:	1 :
					:	:	:	4	4	: 1 - 3 :
A16006	WENDLING QUARRIES INC	STONEMILL	SE 14 TO80	R03W DWU	:	3iB	:	4	4	:
A16008	WENDLING QUARRIES INC	LIME CITY	NE 16 TO79	R02W DWU	:	3i	:	4	4	:
A16010	WENDLING QUARRIES INC	PEDEN	NE 10 TO79	R03W	:	:	:	5	5	:
A16012	WEBER STONE CO INC	ONION GROVE	SE 14 TO82	R02W	2.61 :	3i	:	4	4	: 1 - 7 :
A16014	WENDLING QUARRIES INC	TOWNSEND	NW 02 TO79	R02W	:	:	:	:	:	:
A16016	WENDLING QUARRIES INC	GAUL	NW 13 TO81	R04W	:	:	:	:	:	:
A16018	WENDLING QUARRIES INC	LOWDEN-MASSILLON	NW 23 TO82	R01W	:	:	:	:	:	:
A16020	WENDLING QUARRIES INC	ATALISSA	NE 34 TO79	R03W	:	:	:	:	:	:
A16022	WENDLING QUARRIES INC	TRICON	N2 09 TO82	R04W DWU	:	3i	:	4	4	:
A16024	WENDLING QUARRIES INC	THOMSEN	SW 05 TO79	R02W	:	:	:	:	:	:
---SAND & GRAVEL---										
A16502	WENDLING QUARRIES INC	SHARPLISS	NW 12 TO79	R03W	:	:	:	4	4	:
					2.65 :		X	:	:	:
A16506	WEBER STONE CO INC	ONION GROVE	SE 14 TO82	R02W	2.65 :		X	:	:	:
A16508	WENDLING QUARRIES INC	MASSILLON	CT 11 TO82	R01W	2.65 :		X	:	:	:
*****										



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
17	CERRO GORDO	DIST. 2	---CRUSHED STONE---				
A17008	MARTIN MARIETTA	PORTLAND WEST	NE 19 T096	R19W 2.75	: 3iB	: 4 4	: 1 - 8 :
A17012	MARTIN MARIETTA	LILLYBRIDGE-UBBEN	SW 26 T094	R20W 2.68	: 2	: 5 5	: 1 - 3 :
A17020	MARTIN MARIETTA	MASON CITY	NE 29 T097	R20W DWU	: 3i	: 7 - 9	: 7 :
				2.73	: 3	: X X	: 1 - 6 :
A17022	HOLNAM	HOLNAM	NE 19 T097	R20W DWU	: 2	: 11 - 13	: 1 - 4 :
				DWU	: 2	: 4 4	: 1 - 2 :
A17024	HEARTLAND ASPHALT	RIVERVIEW	NE 29 T096	R19W	:	: 4 4	: :
---SAND & GRAVEL---							
A17506	BECKER GRAVEL CO	NELSON-FORBES	SW 27 T096	R19W	:	: 4 4	: :
A17512	NORTH IOWA S&G INC	WEPKING	NE 15 T097	R21W DWU	: X	: :	: :
A17514	HOLNAM, INC	HOLNAM SAND	NE 19 T097	R20W DWU	: 2	: :	: :
				2.65	: X	: :	: :
A17516	MARTIN MARIETTA	RIPPEN	SE 20 T096	R19W 2.66	: X	: :	: :
*****							
18	CHEROKEE	DIST. 3	---SAND & GRAVEL---				
A18506	HALLETT MATERIALS CO	CHEROKEE SOUTH	NE 16 T091	R40W 2.70	: 2	: 3 3	: :
				2.69	: X	: :	: :
A18512	FABER & SON CONST CO	KILLIAM	SW 20 T093	R39W	:	: 4 4	: :
A18514	MARTIN MARIETTA	LARABEE	SE 20 T093	R39W	:	: 4 4	: :
A18516	MARTIN MARIETTA	WASHTA #1	NE 30 T090	R41W	:	: 3 3	: :
A18518	MARTIN MARIETTA	QUIMBY	SW 15 T090	R41W	:	: 3 3	: :
A18520	MARTIN MARIETTA	QUIMBY-EAST	NW 06 T090	R40W	:	: 3 3	: :
A18526	HALLETT MATERIALS CO	CHEROKEE NORTH	SW 23 T092	R40W 2.70	: 2	: 3 3	: :
				2.67	: X	: :	: :
A18528	BEDROCK GRAVEL	BEAZLEY	SW 31 T090	R41W DWU	: X	: 4 4	: :
A18530	BEDROCK GRAVEL	PATTERSON	32 T091	R40W 2.69	: 2	: :	: :
				DWU	: X	: :	: :
A18532	HODGEMAN & SONS INC	WALKER	31 T090	R41W	:	: :	: :
A18534	HALLETT MATERIALS CO	NELSON	CT 23 T092	R40W DWU	: 2	: :	: :
				DWU	: X	: :	: :
*****							
19	CHICKASAW	DIST. 2	---CRUSHED STONE---				
A19002	GREENE LS CO	TRACY	SE 29 T094	R14W 2.55	: 2	: 4 4	: 9 -10 :
A19004	BRUENING ROCK PROD INC	DEERFIELD-MAHONEY	SE 33 T097	R14W	:	: X	: :
A19006	GREENE LS CO	HUNT	NE 29 T094	R14W 2.57	: 2	: 4 4	: 9 -10 :
A19008	GREENE LS CO	BOICE	NE 16 T095	R14W	:	: 5	: :
---SAND & GRAVEL---							
A19504	GREENE LS CO	HUNT	NW 29 T094	R14W	:	: 4 4	: :
A19506	BLAZEK S&G CO	BLAZEK	NW 32 T096	R11W	:	: 4 4	: :
				2.66	: X	: :	: :
A19508	ROVERUD CONST INC	BUSTA	SE 23 T096	R11W	:	: 4 4	: :
				2.65	: X	: :	: :
A19510	RIVER BEND ENTERPRISES	NASHUA	NE 31 T094	R14W	:	: X X	: :
				2.66	: X	: :	: :
A19512	GREENE LS CO	PEARL ROCK	SE 31 T094	R14W	:	: 4 4	: :
				2.65	: X	: :	: :
A19514	BRUENING ROCK PROD INC	NASHUA	SW 33 T095	R14W DWU	: X	: :	: :
A19516	NIEMANN CONST CO	REWOLDT	NE 25 T094	R13W DWU	: X	: :	: :
A19518	CARLSON MATERIALS CO	AGGLAND	31 T096	R12W	:	: :	: :
*****							
20	CLARKE	DIST. 5	---CRUSHED STONE---				
A20002	MARTIN MARIETTA	OSCEOLA	NW 12 T072	R26W	:	: 5 : 1	: -10 :
					:	: X : 1	: - 4 : 1

NOTE:

1 - FRICTION TYPE TO BE DETERMINED WHEN USED ON WINTerset BEDS 1-4



RECENTLY ACTIVE

AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
21	CLAY	DIST. 3	--- <td></td> <td></td> <td></td> <td></td>				
A21504	HUMMEL S&G	ECKLEY	NW 16 T095	R35W DWU : 2	: 4	4 :	:
				DWU : X	: 3	3 :	:
A21506	DAVE'S S&G	EVERLY	SW 31 T097	R38W 2.70 : 2	: 3	3 :	:
				2.68 : X	: 4	4 :	:
A21508	MARTIN MARIETTA	SCHARNBURG	NE 11 T096	R38W :	: 3	3 :	:
A21510	NORGAARD S&G	DICKENS	NW 20 T096	R35W :	: 4	4 :	:
				2.70 : X	: 3	3 :	:
A21514	MARTIN MARIETTA	CORNELL	SW 27 T094	R36W :	: 4	4 :	:
A21516	SIEH S&G	SPENCER #1	SW 24 T096	R36W 2.69 : 2	: 3	3 :	:
				2.66 : X	: 4	4 :	:
A21518	HALLETT MATERIALS CO	SPENCER #2	SW 05 T097	R37W :	: 4	4 :	:
A21520	MARTIN MARIETTA	EVERLY	SE 06 T096	R38W :	: 4	4 :	:
A21522	BECKER GRAVEL CO	STAINS	30 T097	R38W :	: 4	4 :	:
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK		DUR	FRICT			
CODE	OPERATOR		SOURCE NAME	LOCATION	SSD	PCC	AC	BEDS		
22	CLAYTON	DIST. 2	---CRUSHED STONE---							
A22002	KUHLMAN	CONST CO	TWIN ROCK-SCHRADER	NW 14 T094 R05W	:	:	: 4 4 :	3 -11 :		
A22004	ROVERUD	CONST INC	BENTE-ELKADER-WATSON	SW 12 T093 R05W 2.66	: 2	:	:	: 4 4 :	1 -11 :	
A22006	BRUENING	ROCK PROD INC	MARQUETTE	NW 16 T095 R03W DWU	: 3i	:	:	: 4 4 :	1 - 9 :	
A22008	KUHLMAN	CONST CO	ANDEREGG	SE 32 T092 R02W DWU	:	:	:	: 4 4 :	2 - 8 :	
A22010	KUHLMAN	CONST CO	OSTERDOCK	SE 02 T091 R03W 2.67	: 2	:	:	:	: 3 - 5 :	
A22012	KUHLMAN	CONST CO	SCHMIDT	NE 33 T091 R01W 2.66	: 3i	:	:	:	: 4 4 :	
A22014	ROVERUD	CONST INC	BLUME	NE 09 T093 R03W 2.64	: 3i	:	:	:	: 4 4 :	
A22016	KUHLMAN	CONST CO	GISLESON	NW 06 T095 R04W 2.66	: 3i	:	:	:	: 4 4 :	
A22018	ROVERUD	CONST INC	ZURCHER	SE 01 T094 R05W	:	:	:	:	: 4 4 :	
A22020	KUHLMAN	CONST CO	MUELLER	NE 30 T094 R03W DWU	: 3i	:	:	:	: 4 4 :	
A22024	BRUENING	ROCK PROD INC	SPOOK CAVE	NE 21 T095 R04W	:	:	:	:	: 4 4 :	
A22026	KUHLMAN	CONST CO	DOERRING-LUANA	SE 05 T095 R05W	:	:	:	:	: 4 4 :	
A22030	KUHLMAN	CONST CO	EBERHARDT	NW 27 T093 R05W 2.72	: 3	:	:	:	: 4 4 :	
A22032	KUHLMAN	CONST CO	WELLMAN	NW 25 T092 R06W	:	X	:	X	: 4 4 :	
A22034	KUHLMAN	CONST CO	KRUSE	NW 17 T092 R04W 2.70	: 3B	:	:	:	: 4 4 :	
					2.70	: 2B	:	:	: 4 4 :	
A22038	KUHLMAN	CONST CO	FASSBINDER	SW 09 T092 R03W 2.67	: 3i	:	:	:	: 4 4 :	
A22040	KUHLMAN	CONST CO	HARTMAN	NW 29 T091 R06W 2.68	: 3i	:	:	:	: 4 4 :	
A22042	ROVERUD	CONST INC	MORAREND	CT 35 T092 R03W 2.67	: X	:	:	:	: 4 4 :	
A22044	KUHLMAN	CONST CO	BOGE	SW 18 T091 R02W	:	:	:	:	: 4 4 :	
A22046	KUHLMAN	CONST CO	JOY SPRINGS-BURRACK	NW 19 T091 R06W 2.65	: 3i	:	:	:	: 4 4 :	
A22056	ROVERUD	CONST INC	MCGREGOR	NE 34 T095 R03W	:	:	:	:	: 4 4 :	
A22058	ROVERUD	CONST INC	ST OLAF	SE 25 T094 R05W	:	:	:	:	: 4 4 :	
A22060	ROVERUD	CONST INC	JOHNSON	NW 26 T093 R04W 2.64	: 3i	:	:	:	: 4 4 :	
A22062	ROVERUD	CONST INC	SNY MAGILL	SE 22 T094 R03W DWU	: 3i	:	:	:	: 4 4 :	
A22066	ROVERUD	CONST INC	PETERSON	NW 09 T094 R06W	:	:	:	:	: 4 4 :	
A22068	RIVER CITY	STONE INC	MILLVILLE	NW 10 T091 R02W DWU	: 3i	:	:	:	: 4 4 :	
A22070	ROVERUD	CONST INC	BERNHARD	NW 35 T095 R04W	:	:	:	:	: 4 4 :	
A22072	PATTISON	BROS.	CLAYTON TERMINAL	07 T093 R02W	:	:	:	:	: 4 4 :	
A22074	RIVER CITY	STONE INC	STRAWBERRY POINT	NE 19 T091 R06W DWU	: 3i	:	:	:	: 4 4 :	
A22076	ROVERUD	CONST INC	LARSON	NW 08 T093 R05W	:	:	:	:	: 4 4 :	
A22078	ROVERUD	CONST INC	SMITH	07 T093 R06W	:	:	:	:	: 4 4 :	
A22080	KUHLMAN	CONST CO	HILINE	NW 08 T091 R03W	:	:	:	:	: 4 4 :	
-----SAND & GRAVEL-----										
A22510	ROVERUD	CONST INC	BENTE	SE 15 T093 R05W 2.66	: X	:	:	:	: 4 4 :	
A22512	KUHLMAN	CONST CO	FAIRGROUND	NE 26 T093 R05W	:	:	:	:	: 4 4 :	
A22514	KUHLMAN	CONST CO	JOY SPRINGS	SW 19 T091 R06W	:	:	:	:	: 4 4 :	
A22518	KUHLMAN	CONST CO	THURN	CT 25 T092 R05W	:	:	:	:	: 4 4 :	
A22520	KUHLMAN	CONST CO	WELTERLEN	SE 32 T091 R05W 2.65	: X	:	:	:	: 4 4 :	



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
23	CLINTON	DIST. 6	---CRUSHED STONE---				
A23002	WENDLING QUARRIES INC	BLOORE-ELWOOD	NW 08 TO83	R02E DWU : 3i	: 4	4 : 1 - 2 :	
A23004	WENDLING QUARRIES INC	BEHR	SW 02 TO81	R03E 2.61 : 3i	: 4	4 : 1 - 2 :	
A23006	WENDLING QUARRIES INC	SHAFFTON	NE 11 TO80	R05E DWU : 3i	: 4	4 : 16 -17 :	
				DWU : 3	: 4	4 : 3 -14 :	
A23010	WENDLING QUARRIES INC	GOOSE LAKE	SW 22 TO83	R05E	: 4	4 : 1 -10 :	
A23012	WENDLING QUARRIES INC	TEEDS GROVE	SW 03 TO83	R06E	: 4	: : : : :	
A23014	WENDLING QUARRIES INC	TORONTO	NW 29 TO82	R01E	: 4	: : : : :	
A23016	WENDLING QUARRIES INC	LYONS	NW 18 TO82	R07E	: 4	: : : : :	
A23018	WENDLING QUARRIES INC	KINGS	NW 06 TO80	R03E	: 4	: : : : :	
A23026	WENDLING QUARRIES INC	MILL CREEK	NE 22 TO82	R06E	: 4	: : : : :	
A23028	WENDLING QUARRIES INC	DELMAR	SE 06 TO83	R04E	: : : : :	: : : : :	
A23030	WENDLING QUARRIES INC	EDON VALLEY	04 TO83	R01E	: : : : :	: : : : :	
A23032	ANDERSON S&G	ANDERSON	23 TO81	R03E	: : : : :	: : : : :	
---SAND & GRAVEL---							
A23502	WENDLING QUARRIES INC	DOYLE	NE 30 TO83	R07E	: 4	4 : : : :	
				2.67 : X	: 4	: : : : :	
A23504	WENDLING QUARRIES INC	BEHR	SW 02 TO81	R03E 2.68 : 2	: 4	4 : : : :	
				2.68 : X	: 4	: : : : :	
A23506	WENDLING QUARRIES INC	SCHNECKLOTH	S2 10 TO80	R05E	: 4	4 : : : :	
				2.67 : X	: 4	: : : : :	
A23508	QUALITY READY MIX	GATEWAY	NE 27 TO81	R06E	: 4	4 : : : :	
				2.66 : X	: 4	: : : : :	
A23510	WENDLING QUARRIES INC	SHAFFTON	N2 11 TO80	R05E	: 4	4 : : : :	
				2.66 : X	: 4	: : : : :	
A23514	ANDERSON S&G	ANDERSON	NW 23 TO81	R03E 2.68 : X	: : : : :	: : : : :	
*****							
24	CRAWFORD	DIST. 3	---SAND & GRAVEL---				
A24512	HALLETT MATERIALS CO	DUNLAP	SE 27 TO82	R41W 2.70 : 2	: 3	3 : : : :	
				2.66 : X	: 3	: : : : :	
*****							
25	DALLAS	DIST. 4	---CRUSHED STONE---				
A25004	SCHILDBERG CONST CO INC	I-80	SW 33 TO78	R28W	: 5	: : : : :	
---SAND & GRAVEL---							
A25502	HALLETT MATERIALS CO	MESSERSCHMIDT	NW 28 TO79	R27W 2.70 : 2	: 4	4 : : : :	
				2.67 : X	: 4	: : : : :	
A25504	BOONEVILLE GRAVEL CO	BOONEVILLE	NW 30 TO78	R26W 2.66 : 2	: 4	4 : : : :	
				2.66 : X	: 4	: : : : :	
A25506	MARTIN MARIETTA	CROFT	NE 16 TO81	R27W	: 4	4 : : : :	
A25508	MARTIN MARIETTA	DUDLEY	NW 05 TO78	R29W	: 4	4 : : : :	
A25510	HALLETT MATERIALS CO	PERRY	NW 01 TO81	R29W 2.70 : 2	: 4	4 : : : :	
				2.67 : X	: 4	: : : : :	
A25512	HALLETT MATERIALS CO	VAN METER	SE 16 TO78	R27W 2.68 : 2	: 3	3 : : : :	
				2.66 : X	: 3	: : : : :	
*****							
26	DAVIS	DIST. 5	---CRUSHED STONE---				
A26004	DOUDS STONE INC	LEWIS	W2 02 TO69	R12W 2.60 : 3	: 4	4 : 1 : : :	
				: : 5 : 3 - 5 :	: 4	: 4 : 6 - 7 :	
A26006	DOUDS STONE INC	BROWN	SW NW 02 TO69	R12W	: : : : :	: : : : :	
*****							
27	DECATUR	DIST. 5	---CRUSHED STONE---				
A27002	MARTIN MARIETTA	GRAND RIVER	NW 22 TO70	R27W	: 5	: 12 -14 :	
A27008	MARTIN MARIETTA	DECATUR	SE 32 TO69	R26W	: X	: 7 : 1 :	
				: : 5 : 9 -15 :	: : : : :	: : : : :	

NOTE:  
1 - FRICTION TYPE TO BE DETERMINED WHEN USED



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
28	DELAWARE	DIST. 6	---CRUSHED STONE---				
A28002	KUHLMAN CONST CO	SEDGEWICK #2	SW 36 TO90	R06W 2.66	: 3iB	: 4 4	: 3 :
A28006	KUHLMAN CONST CO	SEDGEWICK #1	SW 36 TO90	R06W	:	: 4 4	: 1 - 3 :
A28008	KUHLMAN CONST CO	EDGEWOOD WEST	CT 04 TO90	R05W 2.67	: 3i	:	: 2 - 7 :
					:	: 4 4	: 1 - 7 :
A28010	KUHLMAN CONST CO	TIBBOTT	SW 23 TO90	R04W 2.70	: 3i	:	: 1 - 5 :
					:	: 4 4	: 1 - 7 :
A28012	KUHLMAN CONST CO	BAUL	SE 22 TO89	R06W 2.69	: 3i	: 4 4	: 1 - 4 :
A28014	KUHLMAN CONST CO	LOGAN	SW 10 TO88	R05W 2.69	: 3	:	: 2 - 8 :
					:	: 4 4	: 1 - 8 :
A28016	KUHLMAN CONST CO	WHITE	NW 02 TO88	R04W 2.72	: 3i	: 4 4	: 1 - 2 :
A28020	BARD CONCRETE CO	DEUTMEYER	SW 13 TO88	R03W DWU	: 3i	: 4 4	: 2 - 6 :
A28030	KUHLMAN CONST CO	GRIEF	NE 18 TO87	R03W	:	:	: 4 :
A28032	RIVER CITY STONE INC	SCHNITTJER-DELHI	NE 35 TO88	R04W	:	:	: 4 :
A28038	KUHLMAN CONST CO	KUHLMAN	NW 06 TO90	R04W 2.70	: 3i	: 4 4	: 1B- 5 :
A28040	BARD CONCRETE CO	KRAPFL	SE 23 TO89	R03W 2.69	: 3i	: 4 4	: 4 :
A28042	KUHLMAN CONST CO	WALSTON-MASONVILLE	SE 21 TO89	R06W 2.69	: 3i	:	: 1 - 4 :
					:	: 4 4	: 1 - 6 :
A28044	NIEMANN CONST CO	DUNDEE	NE 20 TO90	R06W	:	: 4	: 4 :
A28046	KUHLMAN CONST CO	PINS	NW 27 TO88	R03W	:	:	: 4 :
A28050	KUHLMAN CONST CO	BUCK CREEK	NW 20 TO87	R04W	:	:	: 4 :
A28052	RIVER CITY STONE INC	MANCHESTER	SW 09 TO88	R05W DWU	: 3	:	: 5 - 8 :
A28054	RIVER CITY STONE INC	WINCH	NW SW 02 TO87	R04W	:	:	: 4 :
A28056	RIVER CITY STONE INC	THORPE	NW 33 TO90	R05W	:	:	: 4 :
		---SAND & GRAVEL---					
A28502	KUHLMAN CONST CO	SEDGEWICK	SW 36 TO90	R06W	:	: 4 4	: 4 :
				2.65	: X	: 4 4	: 4 :
A28504	BARD CONCRETE CO	TEGLER	NE 36 TO89	R03W	:	: 4 4	: 4 :
				2.65	: X	: 4 4	: 4 :
A28506	BARD CONCRETE CO	DYERSVILLE	NW 26 TO89	R03W	:	: 4 4	: 4 :
				2.65	: X	: 4 4	: 4 :
A28510	KUHLMAN CONST CO	LOGAN	SW 10 TO88	R05W 2.65	: X	: 4 4	: 4 :
A28514	KUHLMAN CONST CO	FERGESEN	NE 32 TO89	R06W	:	: 4 4	: 4 :
				DWU	: X	: 4 4	: 4 :
A28520	RIVER CITY STONE INC	MANCHESTER	SW 10 TO88	R05W 2.65	: X	: 4 4	: 4 :
*****							
29	DES MOINES	DIST. 5	---CRUSHED STONE---				
A29002	L&W QUARRIES INC	MEDIAPOLIS-LEONARD	SE 01 TO71	R04W 2.65	: 3	:	: 15 :1
					:	: 4 4	: 15 -18 :
					:	: 5 5	: 20 :
A29008	CESSFORD CONST CO	NELSON	NE 26 TO72	R02W 2.62	: 3	:	: 21 -24 :
					:	: 4 4	: 7 -20 :
					:	: 4 4	: 15 -24 :
					:	: 5 5	: 24 -27 :
A29012	CESSFORD CONST CO	GEODE	NE 01 TO69	R05W	:	: 4 4	: 11 -12 :
					:	: 5 5	: 9 -13 :
		---SAND & GRAVEL---					
A29502	CESSFORD CONST CO	SPRING GROVE	SW 36 TO69	R03W	:	: 4 4	: 4 :
				2.66	: X	: 4 4	: 4 :
A29504	SHIPLEY CONST CO	SHIPLEY	26 TO69	R03W 2.68	: X	: 4 4	: 4 :
*****							
30	DICKINSON	DIST. 3	---SAND & GRAVEL---				
A30502	CONCRETE SAND & MATERIALS	MILFORD	12 TO98	R37W 2.70	: 2	: 3 3	: 3 :
				2.66	: X	: 3 3	: 3 :
A30504	ROHLIN CONST CO INC	ROHLIN	NE 06 TO98	R36W	:	: 3 3	: 3 :
A30506	HUMMEL S&G	FOSTORIA	NE 26 TO98	R37W	:	: 4 4	: 4 :
A30508	ROHLIN CONST CO INC	LOST	32 TO98	R37W 2.71	: 3	: 3 3	: 3 :
				2.67	: X	: 3 3	: 3 :
A30510	CEMSTONE S&G	EAST	NE 07 TO98	R36W 2.71	: 2	: 3 3	: 3 :
				2.66	: X	: 3 3	: 3 :
A30512	DICKINSON CO	WESTPORT	NE 17 TO98	R38W	:	: 4 4	: 4 :
A30514	ROHLIN CONST CO INC	LEITH	NE 04 TO98	R37W	:	: 4 4	: 4 :

NOTE:  
1 - AASHTO 57 GRADATION MAXIMUM



RECENTLY ACTIVE

AGGREGATE SOURCES

AGGREGATE SOURCES				BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
CODE	OPERATOR	SOURCE NAME	LOCATION				
*****							
31	DUBUQUE	DIST. 6	---CRUSHED STONE---				
A31002	RIVER CITY STONE INC	ROSE SPUR	27 TO90	R02E 2.66	: 3i	:	: 1 - 8 :
A31006	KUHLMAN CONST CO	DYERSVILLE-SUNDHEIM	SE 32 TO89	R02W 2.66	: 3i	:	: 4 4 : 1 -15 :
A31008	RIVER CITY STONE INC	KLEIN-RICHARDSVILLE	NW 33 TO90	R01E DWU	: 3i	:	: 4 4 : 1 - 8 :
A31010	RIVER CITY STONE INC	BROWN	NW 33 TO89	R02E 2.68	: 3i	:	: 4 4 : 3A- 4B:
A31014	BARD CONCRETE CO	KURT	N2 35 TO87	R02W 2.70	: 3iB	:	: 4 4 : 1 - 4 :
A31018	RIVER CITY STONE INC	MELOY	NW 23 TO87	R01E DWU	: 3i	:	: 4 4 : 2 - 9 :
A31020	RIVER CITY STONE INC	SCHLITCHE	SE 11 TO89	R02W DWU	: 3i	:	: 4 4 : 1 - 3 :
A31022	RIVER CITY STONE INC	SIMPSON FURNACE-ASBURY	SW 07 TO89	R02E 2.67	: 3i	:	: 4 4 : 1 - 4 :
A31024	KUHLMAN CONST CO	JOHNS CREEK	SW 36 TO88	R02W 2.69	: 3i	:	: 4 4 : 3B- 9 :
A31026	WENDLING QUARRIES INC	ARNSDORF	SE 25 TO87	R02E DWU	: 3i	:	: 4 4 : 3 - 4 :
A31028	RIVER CITY STONE INC	THOLE	NW 21 TO87	R02E DWU	: 3i	:	: 4 4 : 1 - 4 :
A31030	RIVER CITY STONE INC	KEMP	NE 09 TO89	R01W	:	:	: 4 4 : 1 - 2 :1
A31034	RIVER CITY STONE INC	HERMSEN	NE 33 TO90	R02W	:	:	: 4 4 : 1 - 2 :
A31036	RIVER CITY STONE INC	BALLTOWN	SE 05 TO90	R01E	:	:	: 4 4 : 1 - 2 :
A31038	RIVER CITY STONE INC	HARTBECKE	SW 21 TO88	R01W	:	:	: 4 4 : 1 - 2 :
A31040	RIVER CITY STONE INC	KENNEDY	NW 03 TO88	R01W	:	:	: 4 4 : 1 - 2 :
A31042	RIVER CITY STONE INC	GANSEN	NW 09 TO87	R02E	:	:	: 4 4 : 1 - 2 :
A31044	RIVER CITY STONE INC	GASSMAN	SE 07 TO88	R03E 2.67	: 3i	:	: 4 4 : 5 - 9 :
A31046	WENDLING QUARRIES INC	DECKER	SE 24 TO87	R02E DWU	: 3i	:	: 4 4 : 1 - 5 :
A31048	RIVER CITY STONE INC	MCDERMOTT	NE 35 TO88	R01W 2.65	: 3i	:	: 4 4 : 2 - 5 :
A31050	RIVER CITY STONE INC	PLOESSEL-DYERSVILLE	N2 07 TO88	R02W 2.74	: 3i	:	: 4 4 : 3 - 5 :
A31052	KUHLMAN CONST	EPWORTH-KIDDER	SW 02 TO88	R01W	:	:	: 4 4 : 3 - 5 :
A31054	RIVER CITY STONE INC	MERRITT	SE 05 TO89	R02E	:	:	: 4 4 : 3 - 5 :
A31056	RIVER CITY STONE INC	RUBIE	SE 06 TO88	R03E	:	:	: 4 4 : 3 - 5 :
A31058	RIVER CITY STONE INC	HOLY CROSS	SW 12 TO90	R02W	:	:	: 4 4 : 3 - 5 :
A31060	BARD CONCRETE CO	EAST CASCADE	SE 22 TO87	R01W 2.71	: 3i	:	: 4 4 : 2 - 5 :
A31064	RIVER CITY STONE INC	WEBER	NW 32 TO89	R02E 2.64	: 3i	:	: 4 4 : 3 - 9A:
A31066	RIVER CITY STONE INC	FILLMORE	SW 26 TO87	R01W 2.70	: 3i	:	: 4 4 : 2 - 4 :
-----SAND & GRAVEL-----							
A31502	AGGREGATE MATERIALS-FLYNN	NINE MILE ISLAND	NE 24 TO88	R03E 2.66	: 3i	:	: 3 3 : :
A31504	BARD CONCRETE CO	SAUSER PROPERTY	NW 36 TO87	R02W	:	:	: 4 4 : :
A31512	MOLO S&G CO	BURKLE-MOLO	SW 19 TO89	R02W 2.66	: X	:	: 4 4 : :
A31514	RIVER CITY STONE INC	FILLMORE	CT 26 TO87	R01W 2.66	: X	:	: 4 4 : :
*****							
32	EMMET	DIST. 3	---SAND & GRAVEL---				
A32502	ESTHERVILLE ROCK&GRAVEL	ESTHERVILLE	N2 03 TO99	R34W 2.70	: 2	:	: 3 3 : :
A32506	EMMET COUNTY	FREY	NW 21 T100	DWU	:	:	: 4 4 : :
A32514	BOGESS CONST	WALLINGFORD	07 TO98	R33W	:	:	: 4 4 : :
A32518	ROHLIN CONST CO INC	EGELAND	20 TO98	DWU	:	:	: 4 4 : :
A32520	ROHLIN CONST CO INC	YOUNG	NE 19 TO98	R33W	:	:	: 4 4 : :
A32522	ESTHERVILLE ROCK&GRAVEL	OLD ESTHERVILLE S&G	30 TO99	R32W	:	:	: 4 4 : :
A32524	EMMET COUNTY	PETERSON	SW 34 T100	R33W	:	:	: 4 4 : :
A32526	ROHLIN CONST CO INC	DAVID YOUNG	NE 29 TO98	R34W	:	:	: 4 4 : :
A32530	L.C. KRUSE & SONS	WHITE	SW 16 T100	R33W	:	:	: 4 4 : :
A32534	ROHLIN CONST CO INC	ENERSON	28 T100	R34W DWU	: 2	:	: 4 4 : :
A32538	ESTHERVILLE ROCK&GRAVEL	JENSEN	NW 03 T099	DWU	:	:	: 4 4 : :
*****							

NOTE:

1 - TOP 17.0' ONLY OF BED 2



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
33	FAYETTE	DIST. 2	---CRUSHED STONE---				
A33002	NIEMANN CONST CO	ELDORADO-JACOBSEN	SW 17 T095	R08W 2.69	: 3iB	: 5 5 : 4 - 6B:	
A33004	NIEMANN CONST CO	HOUH	SW 11 T094	R08W	:	: 5 5 : 1 - 9 :	
A33006	NIEMANN CONST CO	MARYVILLE	SE 24 T091	R07W 2.69	: 3i	: 4 4 : 1 - 2 :	
A33010	NIEMANN CONST CO	VOSHELL	NW 21 T093	R07W	:	: X X : 1 - 4 :	
A33016	NIEMANN CONST CO	MAYNARD	NE 23 T092	R09W	:	: X X :	
A33018	NIEMANN CONST CO	FAIRBANK	SW 28 T091	R10W	: X	: 4 4 : 5 :	
A33020	NIEMANN CONST CO	YEAROUS	SW 19 T093	R08W	:	: 4 4 : 1 - 5 :	
A33022	NIEMANN CONST CO	MILLER	SW 35 T095	R10W	:	: 4 4 : 1 - 8 :	
A33024	NIEMANN CONST CO	WAUCOMA	NW 25 T095	R10W 2.69	: 3iB	: 5 5 : 2 - 4 :	
A33026	WILTGEN CONST CO	LYNCH	NW 05 T095	R10W	:	: 4 4 : 1 - 5 :	
A33030	NIEMANN CONST CO	SCHWEMMAN-ST LUCAS	NE 29 T095	R09W	:	: X X :	
A33032	BRUENING ROCK PROD INC	LANDIS	SE 12 T093	R08W	: X	: 4 4 : 1 - 5 :	
A33034	NIEMANN CONST CO	MCDONOUGH	SE 36 T094	R08W	:	: X X :	
A33036	NIEMANN CONST CO	GRAHAM-HAWKEYE	SW 06 T094	R09W	: X	: 4 4 : 1 - 4 :	
A33038	NIEMANN CONST CO	PAPE	NE 28 T095	R08W DWU	: 3i	: 5 5 : 3 - 5 :	
---SAND & GRAVEL---							
A33506	NIEMANN CONST CO	ALPHA	NW 03 T094	R10W 2.64	: X	: 4 4 :	
A33508	CARLSON MATERIALS CO	DURSCHER	NW 03 T094	R07W	:	: 4 4 :	
A33510	ZUPKE S&G	RANDALIA	NW 29 T093	R09W	:	: 4 4 :	
A33512	NIEMANN CONST CO	WADENA	NE 25 T093	R07W	: 2.66	: X :	
A33518	KUHLMAN CONST CO	BASSETT	SE 11 T091	R07W	: 2.66	: X :	
A33520	BRUENING ROCK PROD INC	OELWEIN SAND	NE 09 T091	R09W 2.65	: X	: 4 4 :	
A33522	BRUENING ROCK PROD INC	PAPE	SE 08 T095	R08W 2.65	: X	: 4 4 :	
A33524	CROELL REDI-MIX	ROGERS	04 T094	R07W 2.66	: X	: 4 4 :	
*****							
34	FLOYD	DIST. 2	---CRUSHED STONE---				
A34002	GREENE LS CO	CARVILLE-BUNN	SW 23 T095	R15W 2.63	: 2	: 4 4 : 1 - 4 :	
A34004	GREENE LS CO	MAXON	SE 07 T094	R17W 2.68	: 2	: 5 5 : 4C-19 :	
A34006	GREENE LS CO	JOHLAS	SW 07 T094	R15W	:	: X X :	
A34008	GREENE LS CO	WARNHOLTZ	SW 09 T096	R16W 2.70	: 3i	: 5 5 : 1 - 4 :	
A34010	GREENE LS CO	LACOSTA	SE 25 T097	R17W DWU	: 3i	: 5 5 : 1 - 4 :	
A34012	GREENE LS CO	WILLIAMS	NW 29 T096	R18W	:	: 5 5 : 1 - 8 :	
A34014	BRUENING ROCK PROD INC	HANNMANN	NE 20 T094	R15W	:	: 4 4 : 9 -14 :	
---SAND & GRAVEL---							
A34502	GREENE LS CO	ROCKFORD	SE 15 T095	R18W 2.68	: 2	: 3 3 :	
A34506	GREENE LS CO	LENT	NE 08 T096	R16W	: 2.65	: X :	
A34510	GREENE LS CO	BRACKEL	NE 17 T094	R17W	:	: 4 4 :	
A34514	GREENE LS CO	LITTLE CEDAR	NW 01 T095	R15W 2.65	: X	: 4 4 :	
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
35	FRANKLIN DIST. 2	---CRUSHED STONE---					
A35002	MARTIN MARIETTA	DOWS	NE 30 TO91 R22W	:	:	4 4 : 1 - 4 :	
				:	:	5 5 : 5 - 6 :	
				:	:	4 4 : 7 - 12 :	
A35006	MARTIN MARIETTA	HIBNESS	SE 22 TO91 R20W 2.58	: 3	:	: 1 - 4A :	
				:	:	4 4 : 1 - 12 :	
A35010	GREENE LS CO	MILLER	NE 13 TO91 R19W	:	:	4 : 1 - 5 :	
A35016	GREENE LS CO	AYRES	01 TO92 R19W	:	:	:	
---SAND & GRAVEL---							
A35502	CARLSON MATERIALS CO	GENEVA	SW 07 TO91 R19W 2.68	: 2	:	3 3 :	
				2.66	:	X :	
A35508	MARTIN MARIETTA	STUCK	SW 30 TO91 R22W	:	:	4 4 :	
A35512	MARTIN MARIETTA	ANDERSON-POPEJOY	NW 27 TO90 R22W 2.68	:	X	3 3 :	
A35514	CARLSON MATERIALS CO	KOCH	SW 08 TO91 R19W	:	:	4 4 :	
				2.69	:	X :	
A35516	BECKER GRAVEL CO	PETERS	SW 04 TO92 R20W	:	:	3 3 :	
				2.65	:	X :	
A35518	BECKER GRAVEL CO	REINKE	SW 22 TO91 R20W	:	:	4 4 :	
A35520	BECKER GRAVEL CO	BRANDT	N2 34 TO90 R19W	:	:	4 4 :	
				2.68	:	X :	
*****							
36	FREMONT DIST. 4	---CRUSHED STONE---					
A36002	SCHILDBERG CONST CO INC	THURMAN	NW 23 TO70 R43W	:	:	4 :	
*****							
37	GREENE DIST. 1	---SAND & GRAVEL---					
A37502	HALLETT MATERIALS CO	BEAZOR	SW 02 TO83 R31W 2.69	: 2	:	4 4 :	
				2.68	:	X :	
A37504	HALLETT MATERIALS CO	JEFFERSON	SW 04 TO83 R31W 2.66	: 2	:	4 4 :	
				2.64	:	X :	
A37510	MARTIN MARIETTA	POUND	NW 20 TO84 R29W	:	:	4 4 :	
A37514	ARCADIA LIMESTONE CO	WRIGHT	NW 05 TO84 R32W	:	:	4 4 :	
				2.66	:	X :	
A37516	GREENE CO. REDI MIX	SHADE TREE	NW 20 TO83 R30W	:	:	4 4 :	
				2.67	:	X :	
A37518	BECKER GRAVEL CO	P&M	30 TO82 R32W 2.69	:	X	:	
*****							
38	GRUNDY DIST. 1	---CRUSHED STONE---					
A38002	GREENE LS CO	REIKEN	NE 15 TO89 R18W	:	:	4 4 : 2 - 5 :	
---SAND & GRAVEL---							
A38504	CARLSON MATERIALS CO	HERONIMOUS	SE 35 TO88 R17W 2.65	:	X	:	
*****							
39	GUTHRIE DIST. 4	---SAND & GRAVEL---					
A39502	MARTIN MARIETTA	MONTEITH	SW 29 TO79 R30W	:	:	4 4 :	
A39504	SCHILDBERG CONST CO INC	SMITH	NW 34 TO79 R30W	:	:	4 4 :	
A39506	BUTTLE CONST CO	BAYARD	NE 22 TO81 R32W	:	:	4 4 :	
*****							
40	HAMILTON DIST. 1	---CRUSHED STONE---					
A40004	MARTIN MARIETTA	COUNTY LINE	SE 34 TO86 R23W	:	:	4 4 :	
A40006	MARTIN MARIETTA	GRAND GEORGE	SE 18 TO89 R25W	:	:	:	
---SAND & GRAVEL---							
A40508	MARTIN MARIETTA	GRAND GEORGE	SE 18 TO89 R25W	:	:	4 :	
A40510	BECKER GRAVEL CO	MORTVEDT	SW 24 TO86 R24W 2.67	:	X	:	
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK	DUR	FRICT				
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD	PCC	AC	A	B	BEDS	
				SpGr	CA	FA				
*****										
41	HANCOCK	DIST. 2	---	CRUSHED STONE---						
A41002	BASIC MATERIALS CORP	GARNER NORTH	SE 11 T095	R24W	2.77	: 3iB	: 4	4	: 1 - 4 :	
					2.77	: 3i	: 4	4	: 6 :	
A41004	BASIC MATERIALS CORP	GARNER SOUTH-WIELAND	NW 13 T095	R24W	2.77	: 3iB	: 4	4	: 1 - 4 :	
					2.77	: 3i	: 4	4	: 6 :	
-----SAND & GRAVEL-----										
A41502	MARTIN MARIETTA	MEZVINSKI	SW 07 T097	R24W	:	:	4	4	: :	
A41504	HANCOCK COUNTY	HUTCHINS	E2 27 T096	R26W	:	:	:	4	: :	
A41506	HANCOCK COUNTY	KLEMME	26 T095	R24W	:	:	:	4	: :	
A41508	MARTIN MARIETTA	KIRSHBAUM	SW 18 T097	R24W	:	:	:	4	: :	
A41510	NUCKOLL'S CONCRETE SERVICES INC	BRITT	34 T096	R26W DWU	: 2	:	3	3	: :	
				DWU	:	X	:	:	: :	
A41512	WINNEBAGO COUNTY	CRYSTAL LAKE	SW 01 T097	R25W	:	:	4	4	: :	
A41518	LAHARV CONST CO INC	AUSTIN	NE 11 T097	R25W	:	:	:	:	: :	
*****										
42	HARDIN	DIST. 1	---	CRUSHED STONE---						
A42002	MARTIN MARIETTA	ALDEN	NW 20 T089	R21W	2.58	: 3i	: 4	4	: 0,1,3 :	
				DWU	: 3	:	:	:	: 0,1 :	
A42004	GERHKE, INC.	GIFFORD	NW 04 T086	R19W	:	:	:	5	: :	
A42006	RIEKENA	RIEKENA	NW 03 T088	R20W	:	:	:	:	: :	
-----SAND & GRAVEL-----										
A42502	WELDON BROS CONST CO	IOWA FALLS	NW 20 T089	R20W	2.65	: 2	: 4	4	: :	
					2.68	:	X	:	: :	
A42504		LYMAN	NE 28 T089	R20W	:	:	4	4	: :	
A42508	MARTIN MARIETTA	MCCORMICK	27 T087	R20W	:	:	4	4	: :	
A42510	MARTIN MARIETTA	JANSSEN	SE 34 T089	R20W	:	:	4	4	: :	
					2.65	:	X	:	: :	
A42512	HARDIN AGGREGATES INC	GIFFORD	SW 31 T087	R19W	:	:	4	4	: :	
					2.66	:	X	:	: :	
A42514	MARTIN MARIETTA	NERHING	NW 28 T087	R20W	:	:	4	4	: :	
A42516		IOWA FALLS	NW 17 T089	R20W	:	:	4	4	: :	
A42518	MARTIN MARIETTA	KLEIN	SW 35 T089	R20W	:	:	4	4	: :	
A42520	MARTIN MARIETTA	PETERSON	NW 32 T088	R22W	:	:	4	4	: :	
A42522	MARTIN MARIETTA	OBER	NW 32 T088	R22W	2.67	:	X	:	: :	
A42524	BECKER GRAVEL CO	GRIFFEL	SE 31 T089	R19W	:	:	3	3	: :	
A42526	BECKER GRAVEL CO	MEIER	NE 31 T087	R21W	:	:	:	:	: :	
A42528	BECKER GRAVEL CO	LLOYD	04 T086	R19W DWU	:	:	4	4	: :	
A42530	BECKER GRAVEL CO	BLOME	SE 32 T087	R21W	:	:	:	:	: :	
*****										
43	HARRISON	DIST. 4	---	CRUSHED STONE---						
A43002	SCHILDBERG CONST CO INC	LOGAN	19 T079	R42W	:	:	4D	4D:	25E:	
					:	:	5	5	: 25C-25E:	
					:	:	:	4	: 26 :	
A43004	WESTERN IOWA LIMESTONE	LOGAN	17 T079	R42W	:	:	4D	4D:	25E:	
					:	:	5	5	: 25C-25E:	
					:	:	:	4	: 26 :	
-----SAND & GRAVEL-----										
A43502	CLARK LS CO	WOODBINE	NW 23 T080	R42W DWU	: 3	:	3	3	: :	
				DWU	:	X	:	:	: :	
A43504	CLARK LS CO	PISGAH	NW 23 T081	R44W	:	:	4	4	: :	
				DWU	:	X	:	:	: :	
A43506	SCHEMMER LS INC	LOGAN	SE 08 T079	R42W	:	:	3	3	: :	
				DWU	:	X	:	:	: :	
A43510	HALLETT MATERIALS CO	WOODBINE	NE 31 T081	R41W	2.69	: 3	: 3	3	: :	
A43512	HALLETT MATERIALS CO	WOODBINE-MCCANN	SW 29 T081	R41W DWU	: 3	:	3	3	: :	
				DWU	:	X	:	:	: :	
*****										
44	HENRY	DIST. 5	---	CRUSHED STONE---						
A44002	COOTS MATERIALS CO INC	SMITH	SE 17 T071	R06W	:	:	:	:	: :	
A44006	HENRY COUNTY	LEEPER	NE 18 T071	R06W DWU	: 2	:	:	:	: 8 -11 :	
A44008	DOUDS STONE INC	TWEEDY	SW 36 T071	R06W	:	:	4	4	: 13 -14 :	
-----SAND & GRAVEL-----										
A44502	CESSFORD CONST CO	NORTH ROME	SW 29 T072	R07W	:	:	4	4	: :	
					2.66	:	X	:	: :	
A44504	IDEAL SAND CO	ENSMINGER-ROME	NE NW 32 T072	R07W	2.67	:	X	:	: :	
*****										



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK		DUR	FRIC			
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD	PCC	AC	A	B	BEDS	
*****										
45	HOWARD	DIST. 2	---CRUSHED STONE---							
A45002	ROVERUD CONST INC	ECKERMAN	NW 33 T100	R11W	2.61	:	2	:	X	X : 8 - 9 :
A45006	BRUENING ROCK PROD INC	NELSON	NE 33 TO99	R13W	2.54	:	2	:	4	4 : 1 - 3 :
					2.54	:	2	:	4	4 : 8 - 9 :
A45008	BRUENING ROCK PROD INC	DOTZLER	NE 23 TO99	R12W	2.56	:	3	:	4	4 : 7 -10A:
A45010	BRUENING ROCK PROD INC	DALEY	NE 11 TO98	R11W	2.59	:	3	:	4	4 : 9 -11 :
A45014	FALK CONST CO	CECELIA	SE 08 TO97	R14W	:	:	:	:	5	:
A45018	BRUENING ROCK PROD INC	LE ROY	NW 10 T100	R14W	:	:	:	:	X	:
A45020	BRUENING ROCK PROD INC	RIECKS	NW 24 T100	R11W	:	:	:	:	:	:
A45022	BRUENING ROCK PROD INC	MAUER	SE 13 T100	R13W	:	:	:	:	:	:
A45024	BRUENING ROCK PROD INC	MAPLE LEAF	SE 04 TO98	R13W	:	:	:	:	:	:
A45026	BRUENING ROCK PROD INC	BRUENING BROTHERS #1	SE 22 T100	R11W	:	:	:	:	:	1 - 3 :
A45028	BRUENING ROCK PROD INC	ELMA	NW 06 TO97	R13W	DWU	:	3	:	4	4 : 2 - 3B:
A45030	BRUENING ROCK PROD INC	DIEKEN-TANK	SE 24 T100	R13W	:	:	:	:	:	:
A45032	BILL KEIM	GANSEN	13 T100	R12W	:	:	:	:	:	:
-----SAND & GRAVEL-----										
A45502	BRUENING ROCK PROD INC	MAPLE LEAF-POTTER	SE 04 TO98	R13W	:	:	:	:	4	4 :
A45504	ROVERUD CONST INC	ECKERMAN	NW 33 T100	R11W	DWU	:	3	:	4	4 :
					2.65	:	:	:	X	:
A45508	CARLSON MATERIALS CO	SOVEREIGN	SW 01 TO98	R12W	DWU	:	3	:	3	3 :
					2.65	:	:	:	X	:
A45514	CARLSON MATERIALS CO	EASTLAND	NE 26 T100	R14W	:	:	:	:	3	3 :
A45516	CARLSON MATERIALS CO	FREIDERICH	NE 15 TO98	R14W	:	:	:	:	3	3 :
					2.67	:	:	:	X	:
A45518	BRUENING ROCK PROD INC	ELMA	NW 06 TO97	R13W	2.67	:	:	:	X	:
*****										
46	HUMBOLDT	DIST. 2	---CRUSHED STONE---							
A46004	MARTIN MARIETTA	GRIFFITH	SW 24 TO91	R30W	:	:	:	:	X	X :
A46006	MARTIN MARIETTA	HODGES	NE 32 TO92	R28W	2.60	:	3i	:	4	4 : 10 -18 :
					DWU	:	3i	:	5	5 : 4 - 8 :
A46014	MARTIN MARIETTA	PEDERSON	SW 28 TO92	R28W	DWU	:	3i	:	:	4 -10 :
A46016	BECKER GRAVEL CO	ERICKSON	30 TO94	R28W	:	:	:	:	:	:
-----SAND & GRAVEL-----										
A46504	MARTIN MARIETTA	PETERSON	SW 27 TO92	R29W	:	:	:	:	4	4 :
A46512	NORTHWEST MATERIALS	WARREN	SW 08 TO92	R30W	DWU	:	:	:	X	X :
A46516	BECKER GRAVEL CO	ERICKSON	30 TO94	R28W	:	:	:	:	:	:
A46518	MARTIN MARIETTA	PEDERSON	SW 28 TO92	R28W	:	:	:	:	:	:
*****										
47	IDA	DIST. 3	---SAND & GRAVEL---							
A47502	HALLETT MATERIALS CO	BATTLE CREEK	05 TO86	R41W	:	:	:	:	3	3 :
*****										
48	IOWA	DIST. 6	---SAND & GRAVEL---							
A48502	MARENGO READY MIX	KIMMICH	SE 24 TO81	R11W	:	:	:	:	4	4 :
					2.66	:	:	:	X	:
A48506	WENDLING QUARRIES INC	MARENGO	NW 22 TO81	R11W	2.66	:	:	:	X	:
A48508	MARENGO READY MIX	DISTERHOFF	SE 34 TO81	R10W	2.66	:	:	:	X	:
*****										



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK SSD	DUR PCC	FRICT AC			
CODE	OPERATOR	SOURCE NAME	LOCATION	SpGr	CA	FA	A	B	BEDS
*****									
49	JACKSON	DIST. 6	---	CRUSHED STONE---					
A49002	BELLEVUE S&G CO	BELLEVUE	SW 25 T087	R04E 2.67	: 3i	:	4	4	: 1 - 3 :
A49004	BELLEVUE S&G CO	LAMOTT	NW 02 T086	R03E	:	:	4	4	: 4 :
A49008	WEBER STONE CO INC	IRON HILL	SW 16 T085	R02E DWU	: 3i	:	4	4	: 3 - 6 :
A49010	WENDLING QUARRIES INC	ANDREW	NW 21 T085	R03E 2.70	: 3iB	:	4	4	: 1 - 6 :
A49012	WENDLING QUARRIES INC	FROST	SE 16 T084	R03E DWU	: 3iB	:	4	4	: 1 - 7 :
A49014	WENDLING QUARRIES INC	MAQUOKETA WEST	NE 13 T084	R02E DWU	: 3i	:	4	4	: 1 - 2 :
A49016	WENDLING QUARRIES INC	WEIS	SE 22 T085	R04E	:	:	4	4	: 1 - 5 :
A49018	WENDLING QUARRIES INC	PATASKA	NW 23 T085	R05E	:	:	4	4	: 1 - 7 :
A49020	WENDLING QUARRIES INC	PRESTON	SW 26 T084	R05E 2.67	: 3i	:	4	4	: 7 -10 :
A49021	PRESTON READY MIX	PRESTON R/M	SW 26 T084	R05E 2.67	: 3i	:	4	4	: 1 -10 :
A49022	WENDLING QUARRIES INC	BELLEVUE	SE 23 T086	R04E	:	:	4	4	: 1 -10 :
A49024	WENDLING QUARRIES INC	MAQUOKETA EAST	SW 07 T084	R03E 2.70	: 3i	:	4	4	: 7 - 8 :
A49026	WENDLING QUARRIES INC	MILES	SW 20 T084	R06E	:	:	4	4	: 7 - 10 :
A49028	WENDLING QUARRIES INC	FULTON	SW 25 T085	R02E DWU	: 3i	:	4	4	: 2 :
A49030	BELLEVUE S&G INC	SPRINGBROOK	15 T085	R04E	:	:	4	4	: 1 - 2 :
A49032	WENDLING QUARRIES INC	OTTER CREEK-GLAHN	CT 21 T086	R02E	:	:	4	4	: 1 - 2 :
A49034	WENDLING QUARRIES INC	KILBURG	NW 21 T085	R05E	:	:	4	4	: 1 - 2 :
A49036	WENDLING QUARRIES INC	ST DONATUS	SE 17 T087	R04E	:	:	4	4	: 1 - 3 :
A49040	WENDLING QUARRIES INC	JOINERVILLE-HAMANN	SE 20 T084	R02E	:	:	4	4	: 1 - 2 :
A49042	WENDLING QUARRIES INC	PETERSON	24 T084	R06E	:	:	4	4	: 1 - 2 :
A49044	WENDLING QUARRIES INC	FRANK	NW 14 T087	R04E	:	:	4	4	: 1 - 2 :
A49046	WENDLING QUARRIES INC	ROWAN	NE 25 T086	R03E	:	:	4	4	: 1 - 2 :
A49048	PRESTON READY MIX	DRURY	CT 32 T085	R06E	:	:	4	4	: 1 - 2 :
A49050	RIVER CITY STONE INC	MARSHALL	NW 01 T084	R06E	:	:	4	4	: 1 - 2 :
A49052	WENDLING QUARRIES INC	STILMUNKES	10 T085	R05E	:	:	4	4	: 1 - 2 :
A49054	DUANE KUNDE	KUNDE	E2 33 T084	R05E	:	:	4	4	: 1 - 2 :
A49058	WENDLING QUARRIES INC	61 ROAD CUT	N2 31 T084	R03E 2.67	: 3i	:	4	4	: 1 :
A49060	BELLEVUE S&G INC	ST DONATUS- BUSCH	18 T087	R04E	:	:	4	4	: 1 :
A49062	PRESTON READY MIX	JOHNSON	31 T084	R04E	:	:	4	4	: 1 :
A49064	BELLEVUE S&G CO	VEACH	01 T085	R02E	:	:	4	4	: 1 :
-----SAND & GRAVEL-----									
A49504	WENDLING QUARRIES INC	KNIPELMAYER	NE 36 T087	R04E	:	:	4	4	: 1 :
A49506	BELLEVUE S&G CO	BELLEVUE	E2 01 T086	R04E 2.64	: 3iB	:	3	3	: 1 :
A49510	WENDLING QUARRIES INC	MAQUOKETA	NE 13 T084	R02E 2.68	: X	:	4	4	: 1 :
A49516	WENDLING QUARRIES INC	TURNER	NE 07 T084	R07E 2.65	: X	:	4	4	: 1 :
A49520	WENDLING QUARRIES INC	BALDWIN	SW 28 T084	R01E 2.63	: 3iB	:	3	3	: 1 :
A49522	CENTURY READY MIX	EWING	NW 02 T084	R01E DWU 2.65	: X	:	4	4	: 1 :
A49524	BELLEVUE S&G CO	GRIEBEL	SE 25 T087	R04E DWU 2.67	: 3B	:	4	4	: 1 :
A49526	BELLEVUE S&G CO	BELLEVUE FARM	SE 25 T087	R04E DWU 2.67	: 3i	:	4	4	: 1 :
A49528	AGGREGATE MATERIALS CO	STEVENS	NW 02 T084	R01E DWU 2.65	: X	:	4	4	: 1 :
A49530	PRESTON READY MIX	PETERSEN	SW 18 T084	R07E DWU 2.65	: 3iB	:	4	4	: 1 :
A49532	WEBER STONE CO INC	IRON HILL	NE 16 T085	R02E DWU 2.65	: X	:	4	4	: 1 :
A49534	PRESTON READY MIX	MARBURGER	SE 13 T084	R07E	: X	:	4	4	: 1 :
*****									
50	JASPER	DIST. 1	---	CRUSHED STONE---					
A50002	MARTIN MARIETTA	SULLY MINE	SE 16 T079	R17W 2.54	: 3i	:	4	4	: 36 -41 :
-----SAND & GRAVEL-----									
A50502	MARTIN MARIETTA	COLFAX	NE 01 T079	R21W 2.68	: 2	:	3	3	: 1 :
A50504	MARTIN MARIETTA	REASNOR	NE 10 T078	R19W 2.66	: X	:	4	4	: 1 :
*****									



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B		BEDS
CODE	OPERATOR	SOURCE NAME	LOCATION					
*****								
52	JOHNSON	DIST. 6	---	CRUSHED STONE---				
A52002	WENDLING QUARRIES INC	FOUR CO.	NW 04 T081	R08W	:	:	X :	:
A52004	RIVER PRODUCTS CO	CONKLIN	NW 33 T080	R06W	2.66 : 3iB : 4 4 : 3 -10 :			
				DWU	: 3i : 5 5 :23 -24 :1			
					:	: 4 4 : 21 :		
A52006	RIVER PRODUCTS CO	KLEIN	NW 02 T079	R07W	2.66 : 3iB : 4 4 : 3 -10 :			
				DWU	: 3i : 5 5 :23 -24 :1			
					:	: 4 4 : 21 :		
A52008	WENDLING QUARRIES INC	ERNST	SW 20 T080	R05W	:	:	X :	:
-----SAND & GRAVEL-----								
A52502	S&G MATERIALS INC	SHOWERS	NE 27 T079	R06W	:	: 4 4 :	:	:
				2.65 :	X :	:	:	:
A52506	S&G MATERIALS INC	BUTLER	SW 33 T079	R06W DWU	:	X :	:	:
A52508	S&G MATERIALS INC	WILLIAMS	NW 34 T079	R06W DWU	:	X :	:	:
*****								
53	JONES	DIST. 6	---	CRUSHED STONE---				
A53002	BARD CONCRETE CO	FARMERS-BEHREND'S	NE 14 T086	R03W	2.64 : 3i : 4 4 : 1 - 5 :			
A53004	WENDLING QUARRIES INC	MONTICELLO	NE 24 T086	R04W	2.66 : 3i : 4 4 :			1 :
A53006	WENDLING QUARRIES INC	ANAMOSA	SE 13 T084	R04W DWU	: 3i : : 1 - 5 :			
					:	: 4 4 : 1 - 6 :		
A53010	WENDLING QUARRIES INC	BALLOU-OLIN	NE 24 T083	R03W DWU	: 3iB :	:	:	3 :
					:	: 4 4 : 1 - 3 :		
A53012	WENDLING QUARRIES INC	WYOMING	33 T084	R01W	2.69 : 3iB : 4 4 : 1 - 2C :			
A53014	WEBER STONE CO INC	JACOBS-SCOTCH GROVE	SW 07 T085	R02W	:	: 5 :	:	:
A53016	WEBER STONE CO INC	STONE CITY	5&6 T084	R04W DWU	: 3i : 4 4 : 2B- 3 :			
A53018	RIVER CITY STONE INC	FINN	NE 06 T085	R01W DWU	: 3i : 4 4 : 2 - 5 :			
A53020	WENDLING QUARRIES INC	CANTON	NE 24 T085	R01W	:	: X :	:	:
A53024	RIVER CITY STONE INC	SULLIVAN	NW 14 T086	R03W	:	:	:	:
A53026	RIVER CITY STONE INC	ANAMOSA	SW 15 T084	R04W	:	:	:	:
-----SAND & GRAVEL-----								
A53502	WENDLING QUARRIES INC	MONTICELLO	SE 07 T086	R03W	:	: 4 4 :	:	:
				2.66 :	X :	:	:	:
A53506	RIVER CITY STONE INC	FINN	N2 06 T085	R01W	:	: 4 4 :	:	:
				2.65 :	X :	:	:	:
A53508	WENDLING QUARRIES INC	ANAMOSA-VERNON	SW 13 T084	R04W	:	: 4 4 :	:	:
				2.66 :	X :	:	:	:
A53510	WENDLING QUARRIES INC	KNAPP	SE 27 T084	R03W	:	: 4 4 :	:	:
				2.65 :	X :	:	:	:
A53514	WENDLING QUARRIES INC	FLEMING	NE 12 T083	R03W	:	: 4 4 :	:	:
				2.66 :	X :	:	:	:
A53516	WENDLING QUARRIES INC	OXFORD MILLS	SE 21 T083	R01W	:	: 4 4 :	:	:
				2.65 :	X :	:	:	:
A53522	WEBER STONE CO INC	WEBER	SE SW 05 T084	R04W	2.66 :	X :	:	:
A53526	BARD CONCRETE CO	STEPHENS	NW 34 T086	R03W	:	: 4 4 :	:	:
				2.66 :	X :	:	:	:
A53528	WEBER STONE CO INC	ANAMOSA	NE 14 T084	R04W	2.65 :	X :	:	:
A53530	RIVER CITY STONE INC	ANAMOSA-WOOD'S	CT 15 T084	R04W	2.66 :	X :	:	:
*****								
54	KEOKUK	DIST. 5	---	CRUSHED STONE---				
A54002	MARTIN MARIETTA	KESWICK	NW 21 T077	R12W	2.61 : 2 : 4 4 :13 -15 :1			
					:	: 4 4 :13 -18 :		
A54004	MARTIN MARIETTA	OLLIE	SW 01 T074	R11W	2.66 : 3 : 4 4 :13 -18 :			
				2.60 : 3 :	:	:27 -29 :1		
					:	: 4 4 :13 -19 :		
					:	: 4 4 :27 -30 :		
A54008	MARTIN MARIETTA	HARPER	SE 11 T076	R11W	:	: 4 4 :15 -24 :		
					:	: 4 4 :32 -37 :		
					:	: 4 4 :38 -40 :		
A54010	DOUDS STONE INC	LYLE	NW 13 T074	R13W DWU	: 3 : 4 4 : 36 :			
				DWU	: 2 : 5 5 : 11 :			
					:	: X : 9 -13 :		
					:	: 4 :36 -38 :		
-----SAND & GRAVEL-----								
A54502	WINN S&G	WINN	SE 06 T074	R10W	2.66 : X :	:	:	:
*****								
NOTE: 1 - 1.25 INCH MAXIMUM TOP SIZE								

NOTE: 1 - 1.25 INCH MAXIMUM TOP SIZE



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
55	KOSSUTH DIST. 2	---SAND & GRAVEL---					
A55506	KOSSUTH COUNTY	WHITTEMORE	NW 16 TO95 R30W	:	:	4 4 :	:
A55508	KOSSUTH COUNTY	IRVINGTON	NW 36 TO95 R29W	:	:	4 4 :	:
A55510	HODGEMAN & SONS INC	SENECA	SE 08 TO98 R30W	:	:	4 4 :	:
A55518	REDING S&G	REDING	02 TO94 R29W	:	:	:	:
A55520	GIESE CONST CO	CONN	SE 35 TO95 R29W	:	:	4 4 :	:
				DWU :	X :	:	:1
*****							
56	LEE DIST. 5	---CRUSHED STONE---					
A56002	CESSFORD CONST CO	HAWKEYE	NE 10 TO68 R06W	:	:	5 : 1 -21 :	:
A56004	CESSFORD CONST CO	FRANKLIN	NE 25 TO68 R06W 2.49	:	2 :	4 4 :22 -27 :	:
A56006	CESSFORD CONST CO	ARGYLE	SE 18 TO66 R06W	:	:	4 4 :12 -14 :	:
A56008	CESSFORD CONST CO	DONNELLSON	SE 05 TO67 R06W	:	:	5 : 4 -12 :	:
A56012	CESSFORD CONST CO	VINCENNES	NW 19 TO66 R06W	:	:	4 4 :13 -17 :	:
---SAND & GRAVEL---							
A56504	CESSFORD CONST CO	VINCENNES	SE 32 TO66 R06W	:	:	4 4 :	:
A56506	BROCKMAN SAND CO	FT MADISON	SW 11 TO67 R05W	2.67 :	X :	:	:
				2.67 :	X :	:	:
*****							
57	LINN DIST. 6	---CRUSHED STONE---					
A57002	WENDLING QUARRIES INC	BETENBENDER-COGGON	SW 03 TO86 R06W DWU	: 3i :	:	8 - 9 :	:
A57004	WENDLING QUARRIES INC	PLOWER	SE 36 TO86 R06W 2.62	: 3 :	:	8 -10 :	:
A57006	WENDLING QUARRIES INC	ROBINS	NE 21 TO84 R07W 2.57	: 3i :	:	9 -11 :	:
A57008	WENDLING QUARRIES INC	BOWSER-SPRINGVILLE	SW 29 TO84 R05W DWU	: 3i :	:	4 4 : 1 -10 :	:
A57010	WENDLING QUARRIES INC	TROY MILLS	SE 09 TO86 R07W	:	:	4 4 : 6 - 7 :	:
A57012	WENDLING QUARRIES INC	MORGAN CREEK	SE 22 TO83 R08W	:	:	X X :	:
A57014	WENDLING QUARRIES INC	SWEETING	NW 18 TO85 R08W	:	:	X X :	:
A57016	WENDLING QUARRIES INC	ALICE	NW 08 TO85 R07W	:	:	4 :	:
A57018	MARTIN MARIETTA	CEDAR RAPIDS	NE 15 TO82 R06W 2.64	: 3i :	:	2 - 9 :3	:
A57020	WENDLING QUARRIES INC	LISBON	NW 24 TO82 R05W DWU	: 3iB :	:	4 4 : 2 -14 :	:
A57022	CRAWFORD QUARRY CO	LEE CRAWFORD	NW 23 TO83 R08W 2.55	: 3i :	:	4 4 :	8 :
A57026	NIEMANN CONST CO	COOK	NW 10 TO86 R07W	:	:	:	:
A57028	WENDLING QUARRIES INC	BEVERLY	NW 07 TO82 R07W DWU	: 3i :	:	4 4 :	6 :
A57030	BRUENING ROCK PROD INC	HENNESSEY	NE 01 TO82 R07W DWU	: 3i :	:	4 4 : 4 - 5 :	:
A57032	WENDLING QUARRIES INC	BOWSER SOUTH	SW 29 TO84 R05W DWU	: 3i :	:	4 4 : 6 - 7 :	:
---SAND & GRAVEL---							
A57502	WENDLING QUARRIES INC	SWEETING	NE 18 TO85 R08W	:	:	4 4 :	:
A57506	WENDLING QUARRIES INC	CEDAR RAPIDS	NE 27 TO84 R08W	2.64 :	X :	:	:
A57508	WENDLING QUARRIES INC	EAST MARION	NE 36 TO84 R06W	2.65 :	X :	4 4 :	:
A57516	MARTIN MARIETTA	CEDAR RAPIDS SAND	SW 35 TO83 R07W 2.65	:	X :	:	:
A57520	WENDLING QUARRIES INC	IVANHOE	NW 29 TO82 R05W	:	:	4 4 :	:
A57522	WENDLING QUARRIES INC	CENTRAL CITY	NE 10 TO85 R06W	2.66 :	X :	:	:
A57524	WENDLING QUARRIES INC	COGGON	NW 11 TO86 R06W	2.65 :	X :	4 4 :	:
A57526	WENDLING QUARRIES INC	TROY MILLS	SE 09 TO86 R07W 2.65	:	X :	:	:
A57528	AGGREGATES INC	AGGREGATES INC	SW 26 TO84 R08W DWU	: 2B :	:	:	:
A57530	WENDLING QUARRIES INC	HESS	SW 04 TO82 R06W DWU	:	X :	:	:

NOTE: 1 - APPROVED ONLY FOR L-MIX PC CONCRETE  
2 - AASHTO 57 GRADATION MAXIMUM  
3 - 1.25 INCH MAXIMUM TOP SIZE



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK	DUR	FRICT			
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD SpGr	PCC CA FA	AC A B	BEDS		
*****									
58	LOUISA	DIST. 5	---CRUSHED STONE---						
A58002	RIVER PRODUCTS CO	COLUMBUS JCT.	NW 03 TO74	R05W 2.55	: 3	:	:16 -19	:1	
				:	:	: 4 4	:15 -19	:	
-----SAND & GRAVEL-----									
A58504	RIVER PRODUCTS CO	FREDONIA A INLAND PUMPING	SW 17 TO75	R04W	:	:	: 4 4	:	
				2.66	:	X :	:	:	
				FREDONIA B RIVER PUMPING	SW 17 TO75	R04W	:	: 4 4	:
				2.66	:	X :	:	:	
*****									
60	LYON	DIST. 3	---SAND & GRAVEL---						
A60502	PETTENGILL CONC & GRAVEL	ROCK RAPIDS #1	NW 33 T100	R45W 2.69	: 2	:	: 3 3	:	
				2.67	:	X :	:	:	
A60504	PETTENGILL CONC & GRAVEL	ROCK RAPIDS #2	NE 09 TO99	R45W	:	:	: 3 3	:	
A60506	PETTENGILL CONC & GRAVEL	ROCK VALLEY	17 T100	R45W	:	:	: 4 4	:	
A60508	DIETER PIT	DIETER	SE 24 T100	R49W	:	:	: 4 4	:	
A60510	HODGEMAN & SONS INC	EGBEO	NW 21 TO99	R48W	:	:	: 4 4	:	
A60512	JOE'S READY MIX INC	LITTLE ROCK	NW 03 TO99	R43W	:	:	: 4 4	:	
				2.66	:	X :	:	:	
A60514	MARTIN MARIETTA	DOON	21 TO98	R45W	:	:	: 3 3	:	
A60516	MARTIN MARIETTA	OPEN	SW 24 TO98	R46W	:	:	: 3 3	:	
A60518	ROCK VALLEY GRAVEL CO	OPEN	NW 17 TO99	R48W	:	:	: 4 4	:	
A60520	HOGAN	WINTER	SE 18 TO99	R43W	:	:	: 4 4	:	
A60522	HYMANS CONST CO	OPEN	17 TO98	R44W	:	:	: 4 4	:	
A60524	MARTIN MARIETTA	OPEN	29 TO98	R45W	:	:	: 4 4	:	
A60528	HYMANS CONST CO	RUDD	20 T100	R45W	:	:	: 4 4	:	
A60530	HODGEMAN & SONS INC	KOOIKER	28 TO99	R45W	:	:	: 4 4	:	
A60532	HODGEMAN & SONS INC	LEMS	24 TO98	R49W	:	:	: 4 4	:	
A60534	HODGEMAN & SONS INC	HORN	16 TO99	R48W	:	:	: 4 4	:	
A60536	ROHLIN CONST CO	VAN ENGEN	SW 35 TO98	R46W	:	:	:	:	
A60538	HODGEMAN & SONS INC	HARMSON	SE 04 TO99	R45W	:	:	:	:	
A60540	HODGEMAN & SONS INC	KANANGEITER	SE 04 TO99	R43W	:	:	:	:	
*****									
61	MADISON	DIST. 4	---CRUSHED STONE---						
A61002	SCHILDBERG CONST CO INC	EARLY CHAPEL-DAGGETT	NW 10 TO76	R29W	:	:	: 5 5	: 15	:
				:	:	:	: 4D:	: 12	:
				:	:	:	: 4 :	: 14B:	:
A61006	SCHILDBERG CONST CO INC	STANZEL	SW 05 TO75	R29W	:	:	: 5 5	: 15	:
A61010	MARTIN MARIETTA	EARLHAM	N2 09 TO77	R28W	:	:	: 4D:	: 25E:	:
A61012	MARTIN MARIETTA	WINTERSET NORTH	SE 27 TO76	R27W	:	:	: 5	: 25	:
A61013	SCHILDBERG CONST CO INC	WINTERSET WEST	SW 28 TO76	R27W	:	:	: 5	: 25	:
A61014	SCHILDBERG CONST CO INC	92 QUARRY	NW 34 TO76	R27W	:	:	: 5	: 25	:
A61016	MARTIN MARIETTA	JONES CREEK	NE 27 TO75	R27W	:	:	: 5	: 25	:
A61018	MARTIN MARIETTA	PAMMEL	08 TO75	R28W	:	:	: 5 5	: 15	:
A61020	MARTIN MARIETTA	PERU	NW 10 TO74	R27W	:	:	: 5	: 25	:
A61022	SCHILDBERG CONST CO INC	GARDNER	NW 34 TO76	R27W	:	:	: 5	: 25	:
A61024	MARTIN MARIETTA	PENN-DIXIE	SW 32 TO76	R27W	:	:	: 5	: 25	:
A61026	MARTIN MARIETTA	MASON	SW 16 TO77	R28W	:	:	: 4	: 20	:
				:	:	:	: 5	: 25	:
A61028	GRIMES ASPHALT & PAVING	GRIMES ASPHALT & PAVING	SE 04 TO74	R27W	:	:	: 5	: 25	:
A61030	MARTIN MARIETTA	WINTERSET SOUTH	NW 34 TO76	R27W	:	:	: 5	: 25	:
*****									
62	MAHASKA	DIST. 5	---CRUSHED STONE---						
A62008	MARTIN MARIETTA	GIVEN #2	SE 14 TO74	R16W	:	:	:	:	
-----SAND & GRAVEL-----									
A62502	SKYLINE CONST CO	G71	SW 15 TO74	R16W 2.67	:	X :	:	:	
*****									
NOTE: 1 - AASHTO 57 GRADATION MAXIMUM									

NOTE: 1 - AASHTO 57 GRADATION MAXIMUM



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
CODE	OPERATOR	SOURCE NAME	LOCATION				
*****							
63	MARION	DIST. 5	---CRUSHED STONE---				
A63002	MARTIN MARIETTA	DURHAM MINE	NE 08 TO75	R18W 2.51 : 3i	:	4 4 :	101 :
				2.62 : 2	:	4 4 :88	-95 :1
				:	:	4 4 :95	-96 :2
A63010	BRUENING ROCK PROD INC	S&S	SE 25 TO75	R20W	:	4 :	:
-----SAND & GRAVEL-----							
A63502	PELLA CONST CO LTD	BEAN PROPERTY	NE 02 TO75	R18W	:	4 4 :	:
				2.67 :	X :	:	:
A63506	MARTIN MARIETTA	KAMMERICK	NE 03 TO75	R18W	:	4 4 :	:
				2.67 :	X :	:	:
A63512	MARTIN MARIETTA	NEW HARVEY	NW 12 TO75	R18W 2.67 :	X :	:	:
*****							
64	MARSHALL	DIST. 1	---CRUSHED STONE---				
A64002	MARTIN MARIETTA	FERGUSON	SW 05 TO82	R17W 2.66 : 3	:	4 4 : 8	-21 :
				DWU : 2	:	4 4 : 2	-17 :
				:	:	4 4 : 1	-18 :
A64004	CESSFORD CONST CO	LE GRAND	SW 36 TO84	R17W 2.58 : 3i	:	5 5 : 1	-7 :
				:	:	4 4 : 8	-27 :
-----SAND & GRAVEL-----							
A64502	MARTIN MARIETTA	MARSHALLTOWN	SW 29 TO84	R17W 2.66 : 2	:	4 4 :	:
				2.65 :	X :	:	:
A64504	HALLETT MATERIALS CO	BROMLEY-CLEMONS	NE 02 TO84	R20W 2.65 : 2	:	4 4 :	:
				2.65 :	X :	:	:
*****							
65	MILLS	DIST. 4	---CRUSHED STONE---				
A65002	SCHILDBERG CONST CO INC	FOLSOM-GLENWOOD	NW 29 TO73	R43W	:	5 :	:
*****							
66	MITCHELL	DIST. 2	---CRUSHED STONE---				
A66002	FALK CONST CO	DUENOW	SE 08 TO99	R17W 2.77 : 3iB	:	4 4 : 1	-5 :
				:	:	4 4 : 7	-13 :
A66006	FALK CONST CO	WILDE	NE 07 TO98	R18W	:	5 :	:
A66014	FALK CONST CO	STAFF	NE 17 TO97	R17W DWU : 3i	:	3 :	:
A66016	FALK CONST CO	LESCH	SW 12 TO97	R17W	:	5 5 : 1	-8 :
				:	:	4 4 : 9	-14 :
A66018	FALK CONST CO	DYNES	SW 30 TO99	R15W	:	:	:
A66020	FALK CONST CO	ASPEL	NE 03 TO99	R15W	:	:	:
A66022	FALK CONST CO	WAGNER	NW 29 TO98	R16W	: X	X X :	:
-----SAND & GRAVEL-----							
A66502	FALK CONST CO	OSAGE-SCHMIDT	NW 01 TO97	R17W	2.63 :	4 4 :	:
				:	X :	:	:
A66504	FALK CONST CO	ST ANSGAR-BLAZEK	SW 36 TO99	R18W	:	3 3 :	:
A66510	FALK CONST CO	NEWBURG	NW 26 TO99	R18W	:	3 3 :	:
A66512	FALK CONST CO	KLAAHSEN	SW 36 TO99	R18W	:	:	:
A66514	FALK CONST CO	LOVIK	SE SW 12 TO97	R17W DWU	: X	:	:
*****							
67	MONONA	DIST. 3	---SAND & GRAVEL---				
A67506	HARGRAVE	HARGRAVE	NE 31 TO85	R46W	:	4 4 :	:
A67508	MIDWEST PAVING CO	ONAWA	SW 09 TO82	R45W	:	4 4 :	:
*****							
68	MONROE	DIST. 5	---CRUSHED STONE---				
A68002	MARTIN MARIETTA	EDDYVILLE NORTH	NE 02 TO73	R16W	:	5 : 2	-4 :
A68004	MARTIN MARIETTA	EDDYVILLE SOUTH	SW 02 TO73	R16W	:	:	:
*****							
69	MONTGOMERY	DIST. 4	---CRUSHED STONE---				
A69002	SCHILDBERG CONST CO INC	STENNETT	NE 27 TO73	R38W	:	4 :16	-17 :
-----SAND & GRAVEL-----							
A69504	HALLETT MATERIALS CO	ELLIOT	13 TO73	R38W	:	4 4 :	:
*****							

NOTES: 1 - TOP 6.0' ONLY OF BED 95  
2 - BOTTOM 5.0' ONLY OF BED 95



RECENTLY ACTIVE

AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
70	MUSCATINE DIST. 5	---CRUSHED STONE---					
A70002	WENDLING QUARRIES INC	MOSCOW	NW 08 TO78	R02W 2.66 : 3i : 5 5 :11 -17 :			
				2.67 : 3iB : 4 4 :21A-24 :			
				:	:	5 : 1 - 9 :	
A70006	HARSCO CORP/HECKETT DIV	WILTON	SE 02 TO78	R02W	:	2 2 :	
A70008	HARSCO CORP/HECKETT DIV	MONTPELIER	SE 11 TO77	R01E	:	2 2 :	
-----SAND & GRAVEL-----							
A70504	WENDLING QUARRIES INC	ATALISSA-MCKILLIP	NW 20 TO78	R02W	:	4 4 :	
				2.66 :	X :	:	
A70506	ACME FUEL AND MATERIALS	ACME	SE 22 TO76	R02W 2.65 :	X :	:	
A70508	HAHN S&G	HAHN	SE 16 TO76	R02W	:	:	
A70510	NORTHERN GRAVEL CO	NORTHERN	15 TO76	R02W	:	:	
*****							
71	O'BRIEN DIST. 3	---SAND & GRAVEL---					
A71508	MARTIN MARIETTA	SHELDON	SW 16 TO97	R42W	:	4 4 :	
A71510	MARTIN MARIETTA	OPEN	SE 29 TO97	R42W	:	4 4 :	
A71512	MARTIN MARIETTA	SANBORN	SW 04 TO96	R41W	:	4 4 :	
A71514	MARTIN MARIETTA	PAULLINA	SE 23 TO95	R41W	:	4 4 :	
A71516	MARTIN MARIETTA	OPEN	SE 01 TO94	R41W	:	4 4 :	
A71518	MARTIN MARIETTA	OPEN	17 TO95	R39W	:	4 4 :	
A71520	MARTIN MARIETTA	PRIMGHAR	NW 04 TO95	R39W	:	4 4 :	
A71522	FABER & SON CONST CO	SHELDON	SE 19 TO97	R42W	:	4 4 :	
A71524	FLOYD RIVER S&G INC	ITTER	SE 11 TO97	R42W 2.69 : 2 : 3 3 :			
				2.66 :	X :	:	
A71526	MARTIN MARIETTA	OPEN	SE 20 TO97	R42W	:	4 4 :	
A71528	O'BRIEN COUNTY	COUNTY	NW 27 TO95	R39W	:	4 4 :	
A71530	ROHLIN CONST CO	ROHLIN	14 TO97	R42W	:	4 4 :	
A71532	BECKER GRAVEL CO	DOUMA	SE 05 TO96	R41W	:	:	
*****							
72	OSCEOLA DIST. 3	---SAND & GRAVEL---					
A72504	NORTHWEST R/M CONCRETE INC	OCHEYEDAN	SE 15 SW 14 TO99	R40W 2.71 : 2 : 3 3 :			
				2.68 :	X :	:	
A72506	HALLETT MATERIALS CO	ASHTON	SW 28 TO98	R42W 2.69 : 2 : 3 3 :			
				2.69 :	X :	:	
A72508	MARTIN MARIETTA	THOMAS	NW 36 TO99	R40W	:	4 4 :	
A72514	MARTIN MARIETTA	OPEN	NW 31 T100	R40W	:	4 4 :	
A72518	FABER & SON CONST CO	VASS	19 T100	R42W	:	4 4 :	
A72520	NORTHWEST R/M CONCRETE INC	OCHEYEDAN NORTH	NE 23 TO99	R40W	:	4 4 :	
A72522	MARTIN MARIETTA	KAPPES	NE 11 TO98	R42W	:	:	
A72524	BECKER GRAVEL CO	BOERHAVE	SE 21 TO98	R42W	:	:	
A72526	NORTHWEST R/M CONCRETE INC	OCHEYEDAN SOUTH	19 TO99	R39W	:	:	
A72528	BECKER GRAVEL CO	DIRKS	SW 36 TO99	R40W	:	:	
A72530	NORHTWEST R/M CONCRETE INC	BOYD	NW 36 TO99	R40W DWU : 2 : :			
				DWU :	X :	:	
*****							
73	PAGE DIST. 4	---CRUSHED STONE---					
A73002	SCHILDBERG CONST CO INC	BRADDYVILLE	NE 15 TO67	R36W	:	4 :	
A73004	SCHILDBERG CONST CO INC	SHAMBAUGH	SW 20 TO67	R36W	:	:	
-----SAND & GRAVEL-----							
A73504	HALLETT MATERIALS CO	SHENANDOAH	NW 17 TO69	R39W 2.63 : 2 : 3 3 :			
				2.63 :	X :	:	
*****							
74	PALO ALTO DIST. 3	---SAND & GRAVEL---					
A74502	MARTIN MARIETTA	EMMETSBURG S&G	36 TO96	R33W 2.71 : 2 : 3 3 :			
				2.64 :	X :	:	
A74504	MARTIN MARIETTA	DORWEILLER	SW 05 TO94	R31W	:	3 3 :	
				2.67 :	X :	:	
A74506	MARTIN MARIETTA	WEST BEND	NW 08 TO94	R31W	:	3 3 :	
A74508	MARTIN MARIETTA	OPEN	NW 10 TO97	R33W	:	4 4 :	
A74509	HOFFERT S&G	EMMETSBURG	NW 22 TO96	R33W 2.69 : 2 : 4 4 :			
				2.66 :	X :	:	
A74512	ROHLIN CONST CO INC	KAY	SW 20 TO96	R31W	:	:	
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
75	PLYMOUTH	DIST. 3	---SAND & GRAVEL---				
A75502	HIGMAN S&G	AKRON	NW 01 TO92	R49W 2.70 : 2	: 3	3 :	:
				2.67 : X	:	:	:
A75503	EVERIST INC	AKRON	NE 01 TO92	R49W 2.69 : 2	: 3	3 :	:
				2.67 : X	:	:	:
A75506	MARTIN MARIETTA	REMSEN	SE 03 TO92	R44W	:	4 4 :	:
A75508	MARTIN MARIETTA	ASPEN	NE 11 TO92	R49W	:	3 3 :	:
A75510	MARTIN MARIETTA	KINGSLEY	NE 35 TO90	R44W	:	4 4 :	:
A75512	HYMANS CONST CO	KINGSLEY	NE 13 TO90	R44W	:	4 4 :	:
A75514	WALKERS EXCAVATING CO	OYENS	05 TO92	R44W	:	3 3 :	:
A75516	HALLETT MATERIALS CO	BRUNSVILLE	03 TO92	R46W	:	4 4 :	:
A75518	HALLETT MATERIALS CO	HINTON	NW 16 TO90	R46W DWU	: 3	3 3 :	:
A75520	HALLETT MATERIALS CO	MERRILL	02 TO91	R46W	:	4 4 :	:
A75522	ROHLIN CONST CO INC	THOMS	26 TO92	R46W	:	:	:
A75524	L&M SAND & GRAVEL INC	G DIRKSEN #2	31 TO93	R44W DWU	: X	:	:
*****							
76	POCAHONTAS	DIST. 3	---CRUSHED STONE---				
A76002	MARTIN MARIETTA	GILMORE CITY	NE 36 TO92	R31W 2.64 : 3iB	: 5	5 : 1A- 3 :	:
				:	:	4 4 : 1B- 3 :	:
A76004	MARTIN MARIETTA	MOORE	SW 25 TO92	R31W 2.65 : 3iB	: 5	5 : 1A- 3 :	:
				:	:	4 4 : 1B- 3 :	:
					:	4 4 : 4 -10 :	:
					:	5 5 : 4 -12 :	:
-----SAND & GRAVEL-----							
A76506	MARTIN MARIETTA	EGLE	NE 02 TO90	R31W	:	4 4 :	:
A76508	MARTIN MARIETTA	OPEN	NE 07 TO91	R33W	:	4 4 :	:
A76510	MARTIN MARIETTA	ZEAMAN	SE 13 TO92	R31W	:	4 4 :	:
A76512	MARTIN MARIETTA	LIZARD CREEK	13 TO90	R31W	:	4 4 :	:
A76514	ROHLIN CONST CO INC	MILLER	12 TO93	R31W	:	:	:
*****							
77	POLK	DIST. 1	---SAND & GRAVEL---				
A77502	MARTIN MARIETTA	JOHNSTON	NW 17 TO79	R24W DWU : 2	: 3	3 :	:
				2.66 : X	:	:	:
A77504	HALLETT MATERIALS CO	DENNY-JOHNSTON	08 TO79	R24W 2.70 : 2	: 3	3 :	:
				2.67 : X	:	:	:
A77514	WEST DES MOINES SAND CO	FLINT	SE 29 TO78	R25W 2.65 : 2	: 4	4 :	:
				2.66 : X	:	:	:
A77518	HALLETT MATERIALS CO	ARMY POST ROAD	SE 30 TO78	R25W 2.69 : 2	: 3	3 :	:
				2.67 : X	:	:	:
A77520	MARTIN MARIETTA	ARMY POST ROAD	SW 29 TO78	R25W 2.65 : 2	: 3	3 :	:
				2.65 : X	:	:	:
A77522	HALLETT MATERIALS CO	EDM #2-VANDALIA	NE 07 NW 08 TO78	R23W 2.69 : 2	: 3	3 :	:
				2.65 : X	:	:	:
A77524	HALLETT MATERIALS CO	UNIVERSITY PLANT	SE 33 TO79	R23W 2.69 : 2	: 3	3 :	:
				2.65 : X	:	:	:
A77526	HALLETT MATERIALS CO	ARMY POST EAST	SE 29 TO78	R25W 2.66 : 2	: 3	3 :	:
				2.65 : X	:	:	:
A77528	HALLETT MATERIALS CO	PLEASANT HILL	08 TO78	R23W 2.68 : 2	: 3	3 :	:
				2.66 : X	:	:	:
A77530	HALLETT MATERIALS CO	NORTH DES MOINES	NE 16 TO79	R24W 2.67 : 2	:	:	:
				2.66 : X	:	:	:
*****							
78	POTTAWATTAMIE	DIST. 4	---CRUSHED STONE---				
A78002	SCHILDBERG CONST CO INC	CRESCENT	35 TO76	R44W	:	4 4 : 25B-25E:	:
				:	:	4 : 25A-25C:	:
				:	:	4D: 25F:	:
				:	:	4 : 26A-26E:	:
				:	:	4 : 27A-27B:	:
A78004	SCHILDBERG CONST CO INC	SILVER CITY	SE 31 TO74	R41W	:	4 :	:
A78006	SCHILDBERG CONST CO INC	MACEDONIA-K&S	NE 28 TO74	R40W	:	4 :	:
-----SAND & GRAVEL-----							
A78502	HALLETT MATERIALS CO	AVOCA	29 TO77	R39W 2.65 : 3	: 3	3 :	:
				2.65 : X	:	:	:
A78504	HALLETT MATERIALS CO	OAKLAND	SW 23 TO75	R40W 2.65 : 3	: 4	4 :	:
				2.65 : X	:	:	:
A78506	SCHILDBERG CONST CO INC	CRESCENT	NE 34 TO76	R44W	:	4 4 :	:
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
CODE	OPERATOR	SOURCE NAME	LOCATION				
*****							
79	POWESHIEK	DIST. 1	---	CRUSHED STONE-----			
A79002	MALCOM STONE CO	MALCOM MINE	SE 04 T080	R15W	2.60 : 2	: 4	4 : 10 -13 :
*****							
80	RINGGOLD	DIST. 4	---	CRUSHED STONE-----			
A80002	MARTIN MARIETTA	WATTERSON	SE 19 T067	R29W	:	:	5 : 5 - 7 :
*****							
81	SAC	DIST. 3	---	SAND & GRAVEL-----			
A81502	HALLETT MATERIALS CO	SACTON-LAKEVIEW	S2 08 T086	R36W	2.72 : 3	: 3	3 : : :
A81504	MARTIN MARIETTA	AUBURN	NW 02 T086	R35W	2.67 : 2	X : 4	4 : : :
A81506	WIRTJERS TRUCKING	SAC CITY	NW 36 T088	R36W	2.68 : 2	X : 4	4 : : :
A81508	LAKE VIEW CONCRETE PROD	LAKEVIEW	SE 05 T086	R36W	DWU : :	X : 4	4 : : :
A81514	TIEFENTHALER INC	CARNARVON S&G	NE 16 T086	R36W	2.68 : 2	: 3	3 : : :
A81520	BECKER GRAVEL CO	UREN	SE 11 T087	R36W	2.66 : :	X : 3	3 : : :
A81522	HALLETT MATERIALS CO	ULMER	SW 28 T087	R35W	2.67 : :	X : 4	4 : : :
A81524	BECKER GRAVEL CO	NO NAME	SE 04 T087	R37W	:	:	4 4 : : :
A81526	MARTIN MARIETTA	BETTIN	19 T087	R36W	:	:	4 4 : : :
A81528	BEDROCK GRAVEL	WALL LAKE	NW 18 T086	R36W	2.70 : 3	: 4	4 : : :
A81530	J.W. READY MIX & CONST	LEITZ NORTH	SE 29 T087	R35W	DWU : :	X : :	: : : :
A81532	MARTIN MARIETTA	EARLY-THORPE	22 T089	R37W	DWU : 2	: 4	4 : : :
A81534	MARTIN MARIETTA	SAC COUNTY S&G	SE SE 22 T089	R37W	2.66 : :	X : :	: : : :
A81536	TIEFENTHALER INC	DAIKER	NE 12 T086	R35W	2.68 : :	X : :	: : : :
A81538	BEDROCK GRAVEL CO	HEIM	SE 12 T086	R35W	DWU : :	X : :	: : : :
*****							
82	SCOTT	DIST. 6	---	CRUSHED STONE-----			
A82002	MOLINE CONSUMERS CO	MCCAUSLAND	W2 17 T080	R04E	DWU : 3i	: 4	4 : 17 -19 : 1
A82004	MOLINE CONSUMERS CO	NEW LIBERTY	NE 33 T080	R01E	DWU : 3iB	: 4	4 : 1 -16 : 1
A82006	MOLINE CONSUMERS CO	LECLAIRE	NW 35 T079	R05E	2.71 : 3i	:	: 14- 27 : 1
					DWU : 3i	:	: 28 -29 : 1
					DWU : 3	:	: 2 -13 : 1
A82008	LINWOOD MINING & MINERALS	LINWOOD MINE	SW 13 T077	R02E	2.67 : 3i	: 4	4 : 1 -28 : 1
					2.69 : 3i	: 5	5 : 20 -25 : 1
					DWU : 3i	: 4	4 : 27 -30B : 1
					DWU : 3	: 5	5 : 33 -41 : 1
						: 4	4 : 19 : 1
						: 4	4 : 24 -25 : 1
-----SAND & GRAVEL-----							
A82502	MOLINE CONSUMERS CO	MCCAUSLAND	SW 17 T080	R05E	2.66 : :	X : 4	4 : : :
*****							
83	SHELBY	DIST. 4	---	SAND & GRAVEL-----			
A83504	HALLETT MATERIALS CO	HARLAN	NE 36 T079	R39W	2.67 : 3	: 3	3 : : :
*****							
84	SIOUX	DIST. 3	---	SAND & GRAVEL-----			
A84502	ROCK VALLEY GRAVEL CO	VANZEE	NW 20 T097	R46W	2.69 : 2	: 3	3 : : :
A84504	HYMANS CONST CO	VANDERESCH	SW 20 T096	R47W	2.67 : 2	X : 3	3 : : :
A84506	JOE'S READY MIX INC	HUDSON-OSTERCAMP	SE 07 T096	R47W	2.69 : :	X : 3	3 : : :
A84508	JOE'S READY MIX INC	SIOUX CENTER	NW 33 T095	R45W	DWU : :	X : 4	4 : : :
A84510	EVERIST INC	HAWARDEN-NORTH	S2 NW 22 T095	R48W	2.70 : 2	: 3	3 : : :
A84511	HYMANS CONST CO	HAWARDEN	NE 01 T095	R48W	2.67 : 2	X : 3	3 : : :
A84514	BOYDEN	COUNTY	35 T097	R44W	:	:	4 4 : : :
A84516	MARTIN MARIETTA	NO NAME	25 T097	R48W	:	:	: : : : :
A84518	MARTIN MARIETTA	ALTON	SE 15 T094	R44W	:	:	4 4 : : :
A84520	COUNTY PIT	CHATSWORTH	SW 28 T094	R48W	:	:	4 4 : : :
A84522	HYMANS CONST CO	HYMAN	SW 31 T096	R47W	:	:	: : : : :
A84524	VAN ZEE	FAIRVIEW	NW 36 T097	R48W	:	:	4 4 : : :
A84526	BEDROCK GRAVEL	JONAS	NE 36 T094	R44W	DWU : :	X : 4	4 : : :
A84528	HIGMAN S&G	HIGMAN-CHATSWORTH	W2 28 T094	R48W	2.69 : 2	: 4	4 : : :
A84530	ROCK VALLEY BLOCK & TILE	GROENWEG	NW 15 T097	R46W	DWU : 2	: 3	3 : : :
					DWU : :	X : :	: : : : :
					DWU : 2	: 3	3 : : :
					DWU : :	X : :	: : : : :

NOTE: 1 - 1.25 INCH MAXIMUM TOP SIZE



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
85	STORY	DIST. 1	---CRUSHED STONE---				
A85006	MARTIN MARIETTA	AMES MINE	SW 24 TO84	R24W 2.57 : 3i	: 5 5 :19 -25 :		
				2.68 :	: 4 4 :26,28 -39:1		
-----SAND & GRAVEL-----							
A85502	HALLETT MATERIALS CO	CHRISTENSEN	SE 22 TO84	R24W	: : 4 4 :		
				2.68 :	X : : :		
A85510	HALLETT MATERIALS CO	AMES SOUTH	18 TO83	R23W 2.66 : 2	: 3 3 :		
				2.65 :	X : : :		
*****							
86	TAMA	DIST. 1	---CRUSHED STONE---				
A86002	WENDLING QUARRIES INC	MONTOUR	NW 09 TO83	R16W 2.63 : 3i	: 5 5 :1 -7 :		
				2.63 : 3i	: 4 4 :13 -20 :		
				:	: 4 4 :8 -12 :		
-----SAND & GRAVEL-----							
A86502	MANATTS INC	FLINT	NW 03 TO82	R15W	: : 3 3 :		
				2.65 :	X : : :		
A86504	MARTIN MARIETTA	LE GRAND	NE 16 TO83	R16W	: : 4 4 :		
*****							
87	TAYLOR	DIST. 4	---CRUSHED STONE---				
A87004	SCHILDBERG CONST CO INC	102 QUARRY	NE 32 TO68	R34W	: : 4 :		
*****							
88	UNION	DIST. 4	---CRUSHED STONE---				
A88002	SCHILDBERG CONST CO INC	THAYER	NE 35 TO72	R28W	: : 5 :25A-25E:		
				:	: : 4D: 25E:		
*****							
89	VAN BUREN	DIST. 5	---CRUSHED STONE---				
A89002	DOUDS STONE INC	DOUDS MINE	SE 25 TO70	R11W 2.51 : 2	: 4 4 :6- 13 :		
A89006	CESSFORD CONST CO	FARMINGTON-COMANCHE	NE 05 TO67	R08W 2.69 : 3i	: 5 5 :3 :		
				2.52 : 2	: 4 4 :16 -17 :		
				:	: 4 :18 -22 :		
				:	: 5 5 :5 -12 :		
A89008	DOUDS STONE INC	SELMA-GARDNER	NW 16 TO70	R11W 2.69 : 3	: 4 4 :11 :		
				:	: 5 :7 -11 :		
				:	: 4 4 :14 -21 :		
				:	: 4 4 :22 -31 :		
*****							
90	WAPELLO	DIST. 5	---SAND & GRAVEL---				
A90504	MARTIN MARIETTA	HOFFMAN	SE 10 TO72	R14W	: : 4 4 :		
				2.67 :	X : : :		
*****							
92	WASHINGTON	DIST. 5	---CRUSHED STONE---				
A92002	MARTIN MARIETTA	WEST CHESTER	NE 19 TO76	R08W 2.64 : 3	: 4 4 :5 -7 :		
A92006	MARTIN MARIETTA	COPPOCK	NE 30 TO74	R07W	: : 5 5 :3 -4 :		
A92008	RIVER PRODUCTS CO	PEPPER-KEOTA FIELD	SW 31 TO76	R09W	: : :		
-----SAND & GRAVEL-----							
A92502	RIVER PRODUCTS CO	RIVERSIDE	NE 10 TO77	R06W	: : 4 4 :		
				2.65 :	X : : :		
*****							
94	WEBSTER	DIST. 1	---CRUSHED STONE---				
A94002	MARTIN MARIETTA	FT DODGE MINE	SW 24 TO89	R29W 2.66 : 3iB	: 4 4 :36 -42 :		
A94006	MARTIN MARIETTA	YATES	SW 01 TO89	R29W	: : 5 :		
-----SAND & GRAVEL-----							
A94502	NORTHWEST MATERIALS	YATES	SW 01 TO89	R29W	: : 4 4 :		
				2.66 :	X : : :		
A94506	MARTIN MARIETTA	GILPIN	NW 02 TO89	R30W	: : 4 4 :		
A94514	MARTIN MARIETTA	HUDSON-OTHO	SW 14 TO88	R28W	: : 4 4 :		
A94520	MARTIN MARIETTA	WREDE	NE 05 TO86	R27W	: : 4 4 :		
A94522	AUTOMATED S&G	CROFT	NW 14 TO89	R29W 2.65 :	X : : :		
A94526	BECKER GRAVEL CO	BUSKE	SE 36 TO90	R29W	: : 3 3 :		
				2.67 :	X : : :		
A94528	BECKER GRAVEL CO	CONDON	NW 19 TO90	R30W	: : :		
*****							

NOTE:

1 - THE CONTENT OF BED 26 SHALL NOT BE MORE THAN 25% IN THE OVERALL PRODUCT.



RECENTLY ACTIVE  
AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
96	WINNESHIEK	DIST. 2	---CRUSHED STONE---				
A96002	ROVERUD CONST INC	KENDALLVILLE	NE 33 T100	R10W 2.68	: 3B	: 4 4 : 3 - 7 :	
					:	: 4 : 1 - 7 :	
A96003	WILTGEN CONST CO	BROWN	NW 08 T099	R10W	:	:	:
A96004	ROVERUD CONST INC	HOVEY	SW 28 T098	R08W DWU	: 3B	: 5 5 : 1 - 4 :	
					:	: 4 4 : 1 - 6 :	
A96005	BRUENING ROCK PROD INC	MC GEE	NW 19 T099	R10W	:	:	:
A96008	BRUENING ROCK PROD INC	WELKEN	SW 04 T098	R07W 2.71	: 3i	: 4 4 : 4 - 8 :	
A96010	ROVERUD CONST INC	ANDERSON	SW 22 T100	R10W 2.65	: 3B	: 5 5 : 1 - 4 :	
A96014	NIEMANN CONST CO	FESTINA	SW 26 T096	R09W	: X	: 5 5 : 1 - 3 :	
A96016	BRUENING ROCK PROD INC	SKYLINE A	SE 10 T098	R08W 2.66	: 3B	: 5 5 : 1 - 3 :	
					:	: 4 4 : 4 - 8 :	
A96017	BRUENING ROCK PROD INC	SKYLINE B	CT 10 T098	R08W	: 3B	: 5 5 : 1 - 3 :	
					:	: 4 4 : 4 - 11 :	
A96022	WILTGEN CONST CO	MADISON #2	NE 18 T098	R08W	:	: 5 :	:
A96025	WILTGEN CONST CO	MADISON #1	NW 17 T098	R08W	:	: 4 :	:
A96030	ROVERUD CONST INC	ASK	NE 27 T098	R07W	:	: 4 :	:
A96032	ROVERUD CONST INC	BRUVOLD	NW 20 T098	R07W	:	: X :	:
A96034	BRUENING ROCK PROD INC	THOMPSON	SE 29 T098	R09W	:	:	:
A96038	ROVERUD CONST INC	NORDNESS	SE 09 T097	R08W	:	: X :	:
A96040	ROVERUD CONST INC	LOCUST	NE 11 T099	R08W	:	: X :	:
A96046	BRUENING ROCK PROD INC	SERSLAND-SMORSTAD	SE 09 T097	R07W	:	: X X :	:
A96048	NIEMANN CONST CO	LOVE #1	NW 30 T096	R10W	:	: X :	:
A96049	NIEMANN CONST CO	LOVE #2	SW 30 T096	R10W	:	: X : 1 - 10 :	
A96050	BRUENING ROCK PROD INC	BULLERMAN-FESTINA	SE 14 T096	R09W	:	: 4 : 1 - 3 :	
A96052	ROVERUD CONST INC	ESTREM	SW 04 T097	R07W 2.63	: 3B	: : 1 - 6 :	
					:	: 5 5 : 1 - 8 :	
A96054	ROVERUD CONST INC	HORSESHOE BEND	SW 20 T097	R09W	:	: X :	:
A96058	BRUENING ROCK PROD INC	BROGHAMMER	SE 26 T099	R08W	:	: X :	:
A96060	ROVERUD CONST INC	BURR OAK	SE 23 T100	R09W	:	: 4 4 :	:
A96062	ROVERUD CONST INC	HOLT HAUS	SE 28 T098	R08W	:	: X :	:
A96064	ROVERUD CONST INC	STIKA	NW 15 T097	R10W	: 3i	: 4 4 : 1 - 4A :	
A96066	BRUENING ROCK PROD INC	KROSHUS	SW 13 T100	R07W	:	: X :	:
A96068	BRUENING ROCK PROD INC	HOLKESVIK	SW 01 T099	R08W	:	:	:
A96070	WILTGEN CONST CO	KUHN	NW 33 T096	R08W	:	:	:
A96072	BRUENING ROCK PROD INC	MCKENNA NORTH	SW 34 T100	R09W	:	:	:
A96074	WILTGEN CONST CO	BUSHMAN	SW 21 T096	R08W	:	:	:
A96076	ROVERUD CONST INC	PRASKA	NE 19 T097	R10W	:	:	:
A96078	BRUENING ROCK PROD INC	BUSTA	NW 30 T096	R10W	:	:	:
A96082	WILTGEN CONST CO	CROW	SW 17 T097	R10W	:	:	:
A96084	WILTGEN CONST CO	YOUNG	SE 28 T100	R08W	:	:	:
A96086	BRUENING ROCK PROD INC	BRUVOLD	NE 29 T098	R07W	:	:	:
A96090	BRUENING ROCK PROD INC	MCKENNA SOUTH	SE 28 T099	R09W DWU	: 3	: 5 5 : 1 - 5 :	
A96092	ROVERUD CONST INC	HANSON	SE 26 T100	R08W	:	:	:
A96094	ROVERUD CONST INC	CAROLAN	SE 27 T099	R09W	:	:	:
A96100	WILTGEN CONST CO	YOUNG	NE 05 T098	R07W	:	:	:
---SAND & GRAVEL---							
A96502	CARLSON MATERIALS CO	DECORAH	NE 22 T098	R08W	:	: 4 4 :	:
				2.63	: X :	:	:
A96506	ROVERUD CONST INC	FREEMPORT	NE 07 T098	R07W 2.65	: X :	:	:
A96514	ROVERUD CONST INC	ELSBERND	NE 16 T096	R09W	:	: 4 4 :	:
				2.66	: X :	:	:
A96520	CARLSON MATERIALS CO	SWEDES BOTTOM	NE 06 T098	R08W 2.63	: X :	: 4 4 :	:
A96522	BRUENING ROCK PROD INC	WOHLSEORS	NW 17 T098	R10W	:	:	:
A96526	ROVERUD CONST INC	STIKA	NW 15 T098	R08W	:	:	:
A96528	BRUENING ROCK PROD INC	GJETLEY	NE 08 T098	R07W	:	: 4 4 :	:
A96530	CARLSON MATERIALS CO	CARLSON-FREEMPORT	NE 13 T098	R08W 2.63	: X :	:	:
A96532	WILTGEN CONST CO	SCHMITT	NE 34 T096	R09W DWU	: X :	:	:
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

				AGGREGATE SOURCES				BULK SSD SpGr		DUR PCC CA FA		FRICT AC A B		BEDS	
CODE	OPERATOR	SOURCE NAME	LOCATION												
*****															
97	WOODBURY	DIST. 3	---SAND & GRAVEL---												
A97502	HALLETT MATERIALS CO	CORRECTIONVILLE-BUCK	NW 13 T089	R42W	:	:	:	:	:	:	:	:	:	:	:
					DWU	:	:	:	:	:	:	:	:	:	:
A97508	MARTIN MARIETTA	CORRECTIONVILLE #2	NW 35 T089	R42W	:	:	:	:	:	:	:	:	:	:	:
A97510	HALLETT MATERIALS CO	CORRECTIONVILLE-COCKBURN	SE 11 T088	R43W	:	:	:	:	:	:	:	:	:	:	:
A97514	PERSINGER S&G	SMITHLAND	NW 25 T086	R44W	:	:	:	:	:	:	:	:	:	:	:
					DWU	:	:	:	:	:	:	:	:	:	:
A97516	HALLETT MATERIALS CO	ANTHON	05 T087	R43W	2.72	:	:	:	:	:	:	:	:	:	:
					2.67	:	:	:	:	:	:	:	:	:	:
A97518	HALLETT MATERIALS CO	SMITHLAND	35 T086	R44W	2.69	:	:	:	:	:	:	:	:	:	:
					2.67	:	:	:	:	:	:	:	:	:	:
A97520	HALLETT MATERIALS CO	CORRECTIONVILLE-BREESIE	01 T088	R43W	:	:	:	:	:	:	:	:	:	:	:
A97526	FLEWELLING S&G	FLEWELLING	NW 10 T089	R44W	2.67	:	:	:	:	:	:	:	:	:	:
A97528	HALLETT MATERIALS CO	EDWARD	SE 23 T089	R42W	:	:	:	:	:	:	:	:	:	:	:
*****															
98	WORTH	DIST. 2	---CRUSHED STONE---												
A98002	MARTIN MARIETTA	HARRIS	SW 29 T100	R20W	DWU	:	:	:	:	:	:	:	:	:	:
					2.73	:	:	:	:	:	:	:	:	:	:
					DWU	:	:	:	:	:	:	:	:	:	:
A98010	BASIC MATERIALS CORP	FERTILE	SW 36 T098	R22W	2.75	:	:	:	:	:	:	:	:	:	:
					:	:	:	:	:	:	:	:	:	:	:
A98014	FALK CONST CO	STEVENS	NW 01 T098	R20W	2.77	:	:	:	:	:	:	:	:	:	:
					:	:	:	:	:	:	:	:	:	:	:
A98016	ULLAND BROS CONST	EMIL OLSON-BOLTON	SW 10 T099	R20W	:	:	:	:	:	:	:	:	:	:	:
					:	:	:	:	:	:	:	:	:	:	:
					:	:	:	:	:	:	:	:	:	:	:
*****															
			---SAND & GRAVEL---												
A98502	RANDALL TRANSIT MIX	RANDALL TRANSIT MIX	NW 31 T100	R20W	:	:	:	:	:	:	:	:	:	:	:
					2.66	:	:	:	:	:	:	:	:	:	:
A98504	BASIC MATERIALS CORP	FERTILE	NW 36 T098	R22W	:	:	:	:	:	:	:	:	:	:	:
					2.65	:	:	:	:	:	:	:	:	:	:
A98506	MARTIN MARIETTA	KNUTSON	SW 30 T100	R20W	:	:	:	:	:	:	:	:	:	:	:
A98516	LAHARV CONST CO INC	BANG	SE 30 T098	R22W	:	:	:	:	:	:	:	:	:	:	:
A98518	FALK CONST CO	COOPER	NE 12 T098	R20W	:	:	:	:	:	:	:	:	:	:	:
A98520	LAHARV CONST CO INC	WADDINGTON	SE 26 T098	R22W	:	:	:	:	:	:	:	:	:	:	:
A98522	ULLAND BROS CONST	EMIL OLSON-BOLTON	SW 10 T099	R20W	:	:	:	:	:	:	:	:	:	:	:
*****															
99	WRIGHT	DIST. 2	---CRUSHED STONE---												
A99002	BECKER GRAVEL	VOSS	36 T090	R26W	:	:	:	:	:	:	:	:	:	:	:
*****															
			---SAND & GRAVEL---												
A99502	WRIGHT MATERIALS	WRIGHT	NW 12 T093	R24W	2.70	:	:	:	:	:	:	:	:	:	:
					2.66	:	:	:	:	:	:	:	:	:	:
A99510	MARTIN MARIETTA	MEINEKE	NE 14 T090	R23W	:	:	:	:	:	:	:	:	:	:	:
A99512	MARTIN MARIETTA	JACOBSON	SW 01 T090	R25W	:	:	:	:	:	:	:	:	:	:	:
A99514	BECKER GRAVEL	VOSS	36 T090	R26W	:	:	:	:	:	:	:	:	:	:	:
A99516	GIESE CONST CO	MCALPINE	24 T092	R24W	:	:	:	:	:	:	:	:	:	:	:
A99518	BECKER GRAVEL	REICHTER	SE 06 T092	R26W	:	:	:	:	:	:	:	:	:	:	:
*****															



RECENTLY ACTIVE

AGGREGATE SOURCES

				BULK	DUR	FRICT			
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD SpGr	PCC CA FA	AC A B	BEDS		
*****									
IL	ILLINOIS	---CRUSHED STONE---							
AIL002	CESSFORD CONST CO	BIGGSVILLE, HENDERSON CO.	17 TO10	R04W	:	: 4	4 :	:	
AIL004	RIVER CITY STONE INC	MCCARTHY, JO DAVIESS CO.	NW 34 TO29	R02W 2.68	: 3i	: 4	4 : 1 - 5	:	
AIL006	MOLINE CONSUMERS CO	MIDWAY, ROCK ISLAND CO.	SW 16 TO18	R02E DWU	: 3iB	: 4	4 : 1 - 5	:	
AIL008	MOLINE CONSUMERS CO	MCMAHON, WHITESIDE CO.	NE 11 TO20	R02E	:	:	:	:	
AIL010	MOLINE CONSUMERS CO	MILAN, ROCK ISLAND CO.	14 TO17	R02W DWU	: 3i	: 4	4 : 18	:	
				2.69	: 3	: 5	5 : 7 -13	:	
				DWU	: 3	:	: 14	:	
				2.72	: 3	: 4	4 :16 -17	:	
AIL012	MATERIAL SERVICES	OTTAWA-LIGHTWEIGHT			:	: 4	4 :	:	
AIL014	CESSFORD CONST CO	DALLAS CITY, HENDERSON CO.	SW 36 TO08	R07W 2.63	: 3i	: 4	4 : 5B:1	:	
					:	: 4	2 - 3	:	
AIL016	MOLINE CONSUMERS CO	CLEVELAND, HENRY CO.	SW 31 TO17	R02E DWU	: 3i	: 4	4 :	:	
AIL018	MEDUSA AGGREGATES	KANKAKEE, KANKAKEE CO.	NW 07 TO30	R14W DWU	: 2	:	:	:	
AIL020	GRAY QUARRIES/W.L. MILLER	HAMILTON, HANCOCK CO.	NE 31 TO05	R08W 2.65	: 3	: 4	4 : 2 :1	:	
					: 3	: 4	: 4 :	:	
AIL026	REIN SCHULTZ & DAHL	EMERSON	SE 13 TO21	R06E	:	:	4 :	:	
AIL028	WENDLING QUARRIES INC	TURNBAUGH-MT CARROLL, ILL.	SW 10 TO24	R04E DWU	: 3	: 4	4 : 3 - 7	:	
AIL030	WENDLING QUARRIES INC	HUIZENGA	NW 21 TO21	R03E	:	:	4 :	:	
AIL032	GALENA STONE CO	EUSTICE, JO DAVIESS CO.	NE 16 TO27	R02E	:	:	:	:	
AIL034	GALENA STONE CO	VIRTUE, JO DAVIESS CO.	W2 24 TO28	R02W	:	:	:	:	
AIL036	HARSCO CORP/HECKETT DIV	STERLING, WHITESIDE CO.			:	: 2	2 :	:	
AIL038	COOTS MATERIALS CO INC	ROTH, JO DAVIESS CO.	SW 35 TO29	R02W	:	:	:	:	
---SAND & GRAVEL---									
AIL502	MOLINE CONSUMERS CO	ALBANY, ROCK ISLAND CO.	SW 34 TO20	R02E 2.65	: 3i	: 3	3 :	:	
				2.67	:	X	:	:	
AIL504	GENERAL S&G CO	MILAN-BIG ISLAND, ROCK IS. CO.	16 TO17	R02W 2.67	: 3	: 3	3 :	:	
				2.67	:	X	:	:	
AIL506	ILLINOIS-WISCONSIN S&G	SOUTH BELOIT	NW 08 TO16	R02E	:	: 4	4 :	:	
AIL508	GENERAL S&G CO	BARSTOW, ROCK ISLAND CO.	NE 34 TO18	R01E	:	: 4	4 :	:	
AIL510	NELSON S&G CO	WHITESIDE COUNTY-SAND	SW 29 TO21	R07E	:	: 4	4 :	:	
AIL514	MIDWEST S&G	HENRY PIT, MARSHALL CO.	NW 03 TO13	R10E DWU	:	X	:	:	
AIL516	BUILDERS S&G	CORDOVA, ROCK ISLAND CO.	SE 33 TO21	R02E DWU	: 3i	: 4	4 :	:	
				DWU	:	X	:	:	
AIL518	WENDLING QUARRIES INC	THOMPSON	SE 02 TO23	R03E DWU	:	X	:	:	
AIL520	MOLINE CONSUMERS CO	CORDOVA, ROCK ISLAND CO.	S2 05 TO20	R02E DWU	:	X	:	:	
*****									
KS	KANSAS	---CRUSHED STONE---							
AKS002	BINGHAM S&G	BAXTER SPRINGS, CHEROKEE CO.	22 TO29	R23E	:	:	:	:	
*****									

NOTE: 1 - AASHTO 57 GRADATION MAXIMUM



RECENTLY ACTIVE

AGGREGATE SOURCES

CODE	OPERATOR	SOURCE NAME	LOCATION	BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B	BEDS
*****							
MN	MINNESOTA	---CRUSHED STONE---					
AMN002	HECTOR CONST CO	NEW ALBIN, HOUSTON CO.	NW 09 T101	R04W	: X	: X X :	:
AMN004	ROVERUD CONST INC	POOL HILL, HOUSTON CO.	SW 33 T101	R04W	: X	: X X :	:
AMN006	ROVERUD CONST INC	OTTERNESS, FILLMORE CO.	E2 11 T101	R08W 2.75	: 3i	: X X :	1 - 2 :
AMN008	NEW ULM QUARTZITE QUARRY	QUARTZITE, BROWN CO.	SW 35 T110	R31W	:	: 2 2 :	:
AMN012	ROVERUD CONST INC	NEWBURG, FILLMORE CO.	NE 08 T101	R08W	: X	: X X :	:
AMN014	PEDERSEN BROS	BIG SPRINGS, FILLMORE CO.	SW 09 T101	R10W	:	: 4 1 - 6 :	:
AMN016	ROVERUD CONST INC	EITZEN, HOUSTON CO.	SE 20 T101	R05W	: X	: X X :	:
AMN018	OSMUNDSON BROS CONST	GRAND MEADOW, MOWER CO.	NE 09 T103	R14W	:	: X X :	:
AMN020	ED BUNNE	LEROY, MOWER CO.	NE 27 T101	R14W	:	: X X :	:
AMN022	ROVERUD CONST INC	UNDERPASS	NE 20 T101	R07W	:	: :	:
AMN024	MERIDIAN AGGREGATE CO	GRANITE FALLS, YLW MED CO.	SW 28 T116	R39W	:	: 2 2 :	:
AMN026	ORTONVILLE STONE CO	BIG STONE, BIG STONE CO.	26 T121	R46W DWU	: 3i	: 2 2 :	:
AMN030	ROVERUD CONST INC	GENGLER, HOUSTON CO.	SW 16 T102	R05W DWU	: 3B	: 4 4 1 - 2 :	:
AMN032	SIOUX ROCK PRODUCTS	COTTONWOOD, COTTONWOOD CO.	SE 08 T107	R35W DWU	: 3i	: 2 2 :	:
AMN034	ROVERUD CONST INC	ENGRAV, HOUSTON CO.	NE 24 T101	R08W	:	: :	:
AMN036	MATHY CONST CO INC	GOLDBERG, OLMSTEAD CO.	SW 36 T108	R14W	:	: 4 4 :	:
AMN038	MATHY CONST CO INC	RIFLE HILL, FILLMORE CO.	NW 35 T102	R12W	:	: :	:
---SAND & GRAVEL---							
AMN504	BRUENING ROCK PROD INC	NEW ALBIN, HOUSTON CO.	09 T101	R04W	:	: 4 4 :	:
AMN506	HECTOR CONST CO	LUTCHENS, HOUSTON CO.	NW 23 T101	R04W 2.63	: 2B	: 4 4 :	:
				2.68	: X	: :	:
AMN508	HODGEMAN & SONS INC	HODGEMAN, JACKSON CO.	NE 34 T101	R34W	:	: 4 4 :	:
AMN510	WILLET	WILLET, JACKSON CO.	SW 25 T102	R35W	:	: 4 4 :	:
AMN512	MARTIN MARIETTA	MAUDLIN, NOBLES CO.	SE 26 T101	R42W	:	: 4 4 :	:
AMN516	ULLAND BROS	OLSON, FREEBORN CO.	NW 31 T102	R20W DWU	: X	: :	:
AMN518	CARLSON MATERIALS CO	LANESBORO, FILLMORE CO.	SE 07 T104	R10W DWU	: X	: :	:
AMN520	BUNNE & RANNELL	BUNNE & RANNELL, FILLMORE CO.	SE 33 T101	R13W DWU	: X	: :	:
AMN522	HOLST EXCAVATING	PRAIRIE ISLAND #3, GOODHUE CO.	23 T114	R15W	:	: :	:
AMN524	HOLST EXCAVATING	HASTINGS #2, DAKOTA CO.	02 T114	R17W	:	: :	:
AMN526	NORTHWESTERN AGGREGATES	LAKEVILLE, DAKOTA CO.	01 T114	R20W	:	: :	:
AMN528	HANCOCK CONCRETE CO	POPE, POPE CO.	NW 08 T125	R37W	:	: :	:
AMN532	ULLAND BROS	LARSON, FREEBORN CO.	25 T102	R21W	:	: :	:
*****							
MO	MISSOURI	---CRUSHED STONE---					
AMO002	L&W QUARRIES INC	KAHOKA, CLARK CO.	NE 17 TO65	R07W DWU	: 2	: 4 4 : 2A- 3B:	:
					:	: 4 4 : 14 -16 :	:
AMO004	MARTIN MARIETTA	MERCER, MERCER CO.	SE 22 TO66	R23W	:	: 5 3 - 5 :	:
AMO006	GREENE LS CO	TURNER PROP, NODAWAY CO.	SW 31 TO67	R34W	:	: 5 :	:
AMO008	MARTIN MARIETTA	ALLENDAL-LEMB, WORTH CO.	NW 03 TO66	R30W	:	: 5 :	:
AMO010	MARTIN MARIETTA	ALLENDAL-KING, WORTH CO.	SE 34 TO66	R30W	:	: 5 :	:
AMO012	MARTIN MARIETTA	DR. JEFFERIES, HARRISON CO.	NW 03 TO66	R26W	:	: 5 5 : 2 - 8 :	:
AMO014	CARTER-WATERS CORP	EXPANDED SHALE, NEW MARKET MO.		DWU	: 2	: 3 3 :	:
AMO016	MARTIN MARIETTA	BETHANY, HARRISON CO.	SW 09 TO63	R28W	:	: 5 5 :	:
AMO018	MARTIN MARIETTA	ROUTE C, DAVIESS CO.	NE 30 TO61	R28W	:	: 5 5 : 2 - 5 :	:
AMO020	MARTIN MARIETTA	RIDGEWAY, HARRISON CO.	NE 01 TO64	R27W	:	: 5 5 :	:
AMO022	IRON MT TRAP ROCK CO	IRON MT-ST FRANCOIS CO.			:	: 3 3 :	:
AMO024	CENTRAL STONE CO	HUNTINGTON, RALLS CO.	NE 17 TO56	R06W 2.68	: 3i	: 6 - 9 :	:
				2.68	: 3	: 4 4 : 6 -11 :	:
AMO026	MISSOURI PORTABLE STONE	WARRENTON, WARREN CO.	15 TO46	R02W	:	: 3 3 :	:
AMO027	ST JOE LEAD	PEA RIDGE MINE, WASH. CO.			:	: 3 3 :	:
AMO028	PLATTIN MTRLS CO	PLATTIN, ST GENEVIEVE CO.	09 TO39	R07W	:	: :	:
AMO030	KNOX COUNTY STONE CO	EDINA, KNOX CO.	NE 25 TO62	R12W	:	: 4 4 : 1 - 9 :	:
AMO032	SCHILDBERG CONST CO INC	GRAHAM, NODAWAY CO.	NW 36 TO63	R37W	:	: 4 4 : 2 - 3 :	:
AMO038	CENTRAL STONE CO	GREENSBURG, SCOTLAND CO.	22 TO64	R12W	:	: :	:
AMO040	S&A CONSTRUCTION	SOUTH ALLENDALE, WORTH CO.	NW SW 17 TO65	R30W	:	: :	:
AMO042	TRAGER	GALLATIN, DAVIESS CO.	13 TO58	R28W	:	: :	:
---SAND & GRAVEL---							
AMO502	IDEAL SAND CO	WAYLAND, CLARK CO.	SW 21 TO65	R06W	: 2.66	: X	: 4 4 :
					:	: :	:
AMO504	MEDUSA AGGREGATES	ALBANY, GENTRY CO.	27 TO63	R31W	:	: 4 4 :	:
AMO506	MILBURN CO	GALLITIN, DAVIESS CO.	CT 16 TO59	R27W	:	: 4 4 :	:
AMO510	TURNER QUARRIES	CLEARMONT, NODAWAY CO.	SW 34 TO66	R37W	:	: 4 4 :	:
AMO516	STONER SAND CO	MOUNT MORIAH, HARRISON CO.	12 TO64	R26W 2.65	: X	: :	:
*****							



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK	DUR	FRICT			
CODE	OPERATOR	SOURCE NAME	LOCATION	SSD	PCC	AC	A	B	BEDS
SpGr CA FA A B									
*****									
NE	NEBRASKA	---	CRUSHED STONE---						
ANE002	MARTIN MARIETTA	WEeping WATER MINE, CASS CO.	03 TO10	R11E	2.69	: 3iB	: 5	5	: 10
ANE004	KERFORD LS CO	WEeping WATER MINE, CASS CO.	SE 32 TO11	R11E	2.69	: 3iB	: 5	5	: 10
ANE010	FORT CALHOUN STONE CO	FT CALHOUN, WASHINGTON CO.	SE 01 TO17	R12E	:	:	: 4D	4D:25C-25E:	:
						:	:	4D:25A-25C:	:
						:	:	4D: 25F:	:
						:	:	4D:26A-26E:	:
						:	:	4D:27A-27B:	:
ANE012	CITY WIDE S&G	WHITNEY, SARPY CO.	28 TO13	R12E	:	:	:	:	:
-----SAND & GRAVEL-----									
ANE512	LYMAN-RICHEy S&G	WATERLOO #14, DOUGLAS CO.	NE 20 TO15	R20E	:	:	: 4	4	:
				2.62	:	X	:	:	:
-----CLASS V AGGREGATE FOR CONCRETE-----									
ANE502	LYMAN-RICHEy S&G	CULLOM #5, CASS CO.	SW 26 TO13	R12E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE504	LYMAN-RICHEy S&G	WATERLOO #10, DOUGLAS CO.	SE 17 TO15	R10E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE506	HARTFORD S&G	VALLEY, DOUGLAS CO.	NW 18 TO15	R10E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE508	LYMAN-RICHEy S&G	VALLEY #11, DOUGLAS CO.	SE 35 TO16	R09E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE510	HARTFORD S&G	VALLEY, DOUGLAS CO.	SW 22 TO16	R09E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE514	LYMAN-RICHEy S&G	OREAPOLIS #8, CASS CO.	SE 34 TO13	R13E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE526	WESTERN S&G	FREMONT, DODGE CO.	36 TO08	R17E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE530	WESTERN S&G	SOUTH BEND, CASS CO.	SW 13 TO12	R10E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE532	WESTERN S&G	ABEL SPUR, SAUNDERS CO.	SW 30 TO13	R09E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE534	MALLARD S&G	SPRINGFIELD #3, SARPY CO.	32 TO13	R12E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE536	MARTIN MARIETTA	GRETNA, SARPY CO.	17 TO13	R10E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE538	STALP S&G	WEST POINT, CUMING CO.	SE 28 TO22	R06E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE540	ALL SPEC S&G	ALL SPEC S&G, DOUGLAS CO.	SW 14 TO15	R10E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
ANE542	LYMAN-RICHEy S&G	PLANT #47, DODGE CO.	35 TO16	R09E	2.64	: 3	: 4	4	:
				2.64	:	X	:	:	:
ANE544	MALLARD S&G	VALLEY, DOUGLAS CO.	NE 06 TO15	R10E	2.62	: 3	: 4	4	:
				2.62	:	X	:	:	:
*****									
SD	SOUTH DAKOTA	---	CRUSHED STONE---						
ASD002	EVERIST INC	DELL RAPIDS EAST MINNEHAHA CO	SW 10 T104	R49W	2.64	: 3iB	: 2	2	:
ASD004	CONCRETE MATERIALS CO	SIOUX FALLS QUARTZITE	13 T101	R50W	2.64	: 3iB	: 2	2	:
ASD006	MYRL & ROY'S PAVING INC	EAST SIOUX, MINNEHAHA CO.	SE 27 T101	R48W	DWU	: 3i	: 2	2	: 1
ASD008	SPENCER QUARRIES INC	SPENCER, HANSON CO.	24 T103	R57W	:	:	: 2	2	:
ASD010	EVERIST INC	DELL RAPIDS WEST MINNEHAHA CO	NW 16 T104	R49W	2.64	: 3iB	: 2	2	:
-----SAND & GRAVEL-----									
ASD502	BOYER MATERIALS	BOYER, UNION CO.	10 TO95	R48W	DWU	: 2	: 4	4	:
ASD504	MIDWEST PAVING CO	HAWARDEN, UNION CO.	SW 15 TO95	R48W	:	:	: 4	4	:
ASD506	MIDWEST PAVING CO	RICHLAND, UNION CO.	SW 20 TO92	R49W	:	:	: 4	4	:
ASD508	CONCRETE MATERIALS CO	CANTON, LINCOLN CO.	17 TO89	R48W	:	:	: 4	4	:
				2.68	:	X	:	:	:
ASD510	CONCRETE MATERIALS CO	MINNEHAHA CO.	02 T101	R49W	:	:	:	:	:
ASD514	HIGMAN S&G	HUDSON, UNION CO.	02 TO95	R48W	DWU	: 2	: 4	4	:
ASD516	HIGMAN S&G	VOLIN, CLAY CO.	12 TO94	R54W	:	:	:	:	:
*****									



RECENTLY ACTIVE  
AGGREGATE SOURCES

				BULK SSD SpGr	DUR PCC CA FA	FRICT AC A B		BEDS
CODE	OPERATOR	SOURCE NAME	LOCATION					
*****								
WI	WISCONSIN	---CRUSHED STONE---						
AWI002	BRYAN DRESSER TRAP ROCK	DRESSER-TRAPROCK			:	:	3 3	:
AWI004	MARTIN MARIETTA	CNWRR-ROCK SPRINGS			:	:	2 2	:
AWI006	KIELER KOWALSKI	TENNYSON, GRANT CO.			DWU	: 3i	: 4 4	:
AWI008	QUALITY STONE INC	WETZEL, CRAWFORD CO.	NE 31 TO07	R06W DWU	: 3i	:	4 4	7 :
AWI010	ED KRAEMER & SONS INC	RICHARDS, GRANT CO.	SW 21 TO01	R02W DWU	: 3i	:	4 4	:
AWI012	SCARPELLI MATERIALS	WATERLOO QRTZ, DODGE CO.	27,28,33,34 TO08	R13E	:	:	2 2	:
AWI018	RIVER CITY STONE INC	FREESE, GRANT CO.	NW 28 TO01	R02W	:	:	:	:
AWI020	MATHY CONST CO INC	MEDARY, LA CROSSE CO.	NW 27 TO16	R07W	:	:	4 4	:
AWI022	MATHY CONST CO INC	KINGS BLUFF, LA CROSSE CO.	NE 25 TO18	R08W DWU	: 3	:	4 4	2 - 4 :
AWI030	HAVERLAND STONE CO	HAVERLAND, GRANT CO.	NW 26 TO02	R02W	:	:	:	:
AWI034	ED KRAEMER & SONS INC	HOUSEHOLDER, RICHLAND CO.			:	:	:	:
-----SAND & GRAVEL-----								
AWI502	PRAIRIE S&G CO	PRAIRIE DU CHIEN, CRAWFORD CO.	24 TO07	R07W	2.67 : 3i	:	4 4	:
					2.67 :	X :	:	:
AWI504	DUBUQUE S&G CO	VOGT FARM, GRANT CO.	17 TO90	R03E	2.67 : 3i	:	3 3	:
					2.67 :	X :	:	:
AWI506	PRAIRIE S&G CO	KRAMER, CRAWFORD CO.	NE 12 TO07	R07W DWU	: X	:	3 3	:
					2.68 :	X :	:	:
AWI508	PRAIRIE S&G CO	BARN	SE 12 TO07	R07W	2.68 : X	:	:	:
					2.69 :	X :	:	:
AWI510	RIVER CITY STONE INC	KRUG, GRANT CO.	SW 17 TO01	R02W DWU	: X	:	:	:
AWI514	HOLST EXCAVATING	REDWING #7	NE 33 TO25	R18W	:	:	:	:
*****								



REVETMENT STONE  
SOURCE APPROVAL

CODE	OPERATOR	SOURCE NAME	LOCATION	BEDS	REVETMENT CLASS
*****					
DIST. 1					
A40006	MARTIN MARIETTA	GRAND GEORGE	SW 18 T089	R25W 3-5	D
A42002	MARTIN MARIETTA	ALDEN	NW 20 T089	R21W 3	D, E
A50002	MARTIN MARIETTA	SULLY	SE 16 T079	R17W 36-41	E
				42-47	E
A64002	MARTIN MARIETTA	FERGUSON	SW 05 T082	R17W 8-21	E
A86002	WENDLING QUARRIES INC	MONTOUR	NW 09 T083	R06W 8-12	D, E
A94002	MARTIN MARIETTA	FORT DODGE MINE	SW 24 T089	R29W 36-42	D, E
DIST. 2					
A03002	BRUENING ROCK PROD INC	WEXFORD	NE 36 T098	R03W 1B-8	A, B, D, E
A03028	ROVERUD CONST CO	WELPER-JOHNSON	SW 35 T099	R04W FULL FACE	A, B, D, E
A03040	BRUENING ROCK PROD INC	DEE	SE 21 T099	R04W 5A-5D	A, B, D, E
A03050	BRUENING ROCK PROD INC	GREEN	NW 16 T096	R06W 1-3	A, B, D, E
A07004	BASIC MATERIALS CORP	WATERLOO SOUTH	NW 18 T087	R12W 1-23	A, B, D, E
				17-23	A, B, D, E
A07014	NIEMANN CONST CO	GLORY	NE 36 T087	R11W 1-TOP 5' OF BED4	D
A07018	BASIC MATERIALS CORP	RAYMOND-PESKE	SW 01 T088	R12W 1B- 5	A, B, D, E
				1B-10	A, B, D, E
				6-10	A, B, D, E
A09004	NIEMANN CONST CO	DENVER-FOELSKE	NE 29 T091	R13W BOTTOM 8'	A, B, D, E
				BED 12-TOP 9'	
				BED 13	
A12014	NIEMANN CONST CO	OLTMANN	SE 08 T091	R16W 1-TOP	D
				1/2 BED 10	
A22002	KUHLMAN CONST CO	TWIN ROCK-SCHRADER	NW 14 T094	R05W 3-11	A, B, D, E
A22004	ROVERUD CONST CO	BENTE/ELKADER/WATSON	SW 12 T093	R05W 5-9	A, B, D, E
A22008	KUHLMAN CONST CO	ANDEREGG	SE 32 T092	R02W 2-8	A, B, D, E
A22010	KUHLMAN CONST CO	OSTERDOCK	SE 02 T091	R03W 3-8	A, B, D, E
A22012	KUHLMAN CONST CO	SCHMIDT	NE 33 T091	R01W 2-6	A, B, D, E
A22014	ROVERUD CONST CO	BLUME	NE 09 T093	R03W 1-12	A, B, D, E
A22016	KUHLMAN CONST CO	GISLESON	NW 06 T095	R04W 1-15	A, B, D, E
A22020	KUHLMAN CONST CO	MUELLER	NE 30 T094	R03W 1-8	A, B, D, E
A22026	KUHLMAN CONST CO	DOERRING-LUANA	SE 05 T095	R05W 3-5	D
A22030	KUHLMAN CONST CO	EBERHARDT	NW 27 T093	R05W 1-6	A, B, D, E
A22034	KUHLMAN CONST CO	KRUSE	NW 17 T092	R04W 5-12	A, B, D, E
A22040	KUHLMAN CONST CO	HARTMAN	NW 29 T091	R06W 1-4	A, B, D, E
A22042	ROVERUD CONST CO	MORAREND	CT 35 T092	R03W 1-9	A, B, D, E
A22046	KUHLMAN CONST CO	JOY SPRINGS-BURRACK	NW 19 T091	R06W 1-2	A, B, D, E
A22048	ROVERUD CONST CO	TUCKER	SW 18 T091	R05W 1-3	D
A22060	ROVERUD CONST CO	JOHNSON	NW 26 T093	R04W 2-5	A, B, D, E
A22062	ROVERUD CONST CO	SNY MAGILL	SE 22 T094	R03W 6-10	A, B, D, E
A22070	ROVERUD CONST CO	BERNHARD/GIARD	NW 35 T095	R04W 1-3	A, B, D, E
A22074	RIVER CITY STONE CO	STRAWBERRY POINT	NE 19 T091	R06W 1-2	A, B, D, E
A33026	WILTGEN CONST CO	LYNCH	NW 05 T095	R10W 6-8	A, B, D, E
A33032	BRUENING ROCK PROD INC	LANDIS	SE 12 T093	R08W 1-5	A, B, D, E
A34004	GREENE LIMESTONE CO	MAXON	SE 07 T094	R17W 4C-19	A, B, D, E
A34008	GREENE LIMESTONE CO	WARNHOLTZ	SW 09 T096	R16W 5-16	D
				17-18	A, B, D, E
A35002	MARTIN MARIETTA	DOWS	NE 30 T091	R22W 1-12	A, B, D, E
A35006	MARTIN MARIETTA	HIBNESS	SE 22 T091	R20W 1-12A	A, B, D, E
A41002	BASIC MATERIALS CORP	GARNER NORTH	SE 11 T095	R24W 6	A, B, D, E
A41004	BASIC MATERIALS CORP	GARNER SOUTH-WIELAND	NW 13 T095	R24W 6	A, B, D, E
A45002	ROVERUD CONST CO	ECKERMAN	NW 33 T0100	R11W 7-9	A, B, D, E
A45006	BRUENING ROCK PROD INC	NELSON	NE 33 T099	R13W 8-9	A, B, D, E
A45010	BRUENING ROCK PROD INC	DALEY	NE 11 T098	R11W 9-10	A, B, D, E
A46006	MARTIN MARIETTA	HODGES	NE 32 T092	R28W 4-18	D
A76002	MARTIN MARIETTA	GILMORE CITY	NE 36 T092	R31W 1A-3	A, B, D, E
A76004	MARTIN MARIETTA	MOORE	SW 25 T092	R31W 1A-3	A, B, D, E
A96002	ROVERUD CONST CO	KENDALLVILLE	NE 33 T0100	R10W 2-9	A, B, D, E
A96004	ROVERUD CONST CO	HOVEY	SW 28 T098	R08W 2-6	A, B, D, E
A96017	BRUENING ROCK PROD INC	SKYLINE B	CT 10 T098	R08W 4-11	A, B, D, E
A96052	ROVERUD CONST CO	ESTREM	SW 04 T097	R07W 2-8	A, B, D, E
A96064	ROVERUD CONST CO	STIKA	NW 15 T097	R10W 5A-8B	A, B, D, E
A96017	BRUENING ROCK PROD INC	SKYLINE B	CT 10 T098	R08W 4-11	A, B, D, E
A98002	MARTIN MARIETTA	HARRIS	SW 29 T0100	R20W 6-11	A, B, D, E
A98010	BASIC MATERIALS	FERTILE	SW 36 T098	R22W 15-20	A, B, D, E
AMN004	ROVERUD CONST CO	POOL HILL	SW 33 T0101	R04W 1-8	A, B, D, E
AMN030	ROVERUD CONST CO	GENGLER	SW 16 T0102	R05W 1-4	A, B, D, E



REVTMENT STONE  
SOURCE APPROVAL

CODE	OPERATOR	SOURCE NAME	LOCATION	BEDS	REVTMENT CLASS
------	----------	-------------	----------	------	----------------

DIST. 3

AMN032	SIOUX ROCK PRODUCTS	COTTONWOOD, COTTONWOOD CO.	SE 08 T107	R35W	Entire ledge*	A,B,D,E
ASD002	EVERIST INC	DELL RAPIDS, MINNEHAHA CO.	SW 10 T104	R49W	Entire ledge*	A,B,D,E
ASD004	CONCRETE MATERIALS CO	SIOUX FALLS QUARTZITE	13 T101	R50W	Entire ledge*	A,B,D,E
ASD006	MYRL & ROY'S PAVING INC	EAST SIOUX, MINNEHAHA CO.	SE 27 T101	R48W	Entire ledge*	A,B,D,E
ASD008	SPENCER QUARRIES INC	SPENCER, HANSON CO.	24 T103	R57W	Entire ledge*	A,B,D,E

\*\*\*\*\*  
\*Isolated pockets of sandstone may be cause to reject all or portions of a shot, also, the pipestone deposits will define the lower limits of ledge. In both instances a visual examination will reveal the presence of either unconsolidated sandstone or pipestone material.  
\*\*\*\*\*

DIST. 4

A01002	SCHILDBERG CONST CO INC	MENLO	SE 17 TO77	R31W	15A-15C	D,E
A61002	SCHILDBERG CONST CO INC	EARLY CHAPEL-DAGGETT	NW 10 TO76	R29W	14B	D,E
A61024	MARTIN MARIETTA	PENN-DIXIE	SW 32 TO76	R27W	20A	D,E
A78002	SCHILDBERG CONST	CRESCENT	35 TO76	R24W	25B-25E	D,E
A88002	SCHILDBERG CONST	THAYER	NE 35 TO72	R28W	20B	D,E
					25B-25E	E
ANE002	MARTIN MARIETTA	WEEPING WATER NE	03 TO10	R11E	10A-10B	E
ANE004	KERFORD LIMESTONE	WEEPING WATER NE	SE 32 TO11	R11E	10A-10B	D,E
ANE010	FORT CALHOUN STONE	FORT CALHOUN NE	SE 01 TO17	R12E	26B-26E	D,E

DIST. 5

A04004	L&W QUARRIES	MARTIN #3	E2 20 TO70	R19W	1-3	D
					6	D,E
A04016	L&W QUARRIES	LEMLEY EAST #5	CT 35 TO70	R19W	1-3	D
					6	D,E
A04018	L&W QUARRIES	CLARKDALE #8	SE 15 TO69	R18W	1A	D,E
					1C	D,E
					4	D
A20002	MARTIN MARIETTA	OSCEOLA	NW 12 TO72	R26W	1-10	D
					20A	D
A26004	DOUDS STONE INC	LEWIS	W2 02 TO69	R12W	3-5	D
					6-7	D,E
A27002	MARTIN MARIETTA	GRAND RIVER	NW 22 TO70	R27W	17	D
A27008	MARTIN MARIETTA	DECATUR	SE 32 TO69	R27W	7	D
					13-14	D
A29002	L&W QUARRIES	MEDIAPOLIS	SE 01 TO71	R04W	15-18	D,E
A29008	CESSFORD CONST CO	NELSON	NE 26 TO72	R02W	7-14	D,E
					7-20	D,E
					15-20	D
					15-24	D
					21-24	D,E
					25-27	D
A29012	CESSFORD CONST CO	GEODE	NE 01 TO69	R05W	1-5	D,E
					9-13	D,E
A44008	DOUDS STONE INC	NELSON-TWEEDY	SW 36 TO71	R06W	9-14	D,E
					13-14	D,E
A54002	MARTIN MARIETTA	KESWICK	NW 21 TO77	R12W	13-15	D,E
					13-17	D
A54004	MARTIN MARIETTA	OLLIE	SW 01 TO74	R11W	9-13	D
					13-18	D,E
					19-27	D
					27-30	D,E
					30-33	D
A54008	MARTIN MARIETTA	HARPER	SE 11 TO76	R11W	13-22	D,E
					32-37	D,E
					38-40	D,E
A54010	DOUDS STONE INC	LYLE	NW 13 TO74	R13W	2-11	D
					9-13	D,E
					36-38	E
					40	E
A56002	CESSFORD CONST CO	HAWKEYE	NE 10 TO68	R06W	1-21	D
					22-27	D,E
A56008	CESSFORD CONST CO	DONNELLSON	SE 05 TO67	R06W	10-13	D,E
A62008	MARTIN MARIETTA	GIVEN #2	SE 14 TO74	R16W	2-6	D
A63002	MARTIN MARIETTA	DURHAM MINE	NE 08 TO75	R18W	88-95	D,E
					95-96	D,E
A63010	BRUENING ROCK PROD INC	S&S	SE 25 TO75	R20W	MASSIVE BEDS	D



REVETMENT STONE SOURCE APPROVAL					
CODE	OPERATOR	SOURCE NAME	LOCATION	BEDS	REVETMENT CLASS
*****					
DIST. 5					
A89002	DOUDS STONE INC	DOUDS MINE	SE 25 TO70	R11W 5-13	D,E
A89006	CESSFORD CONST CO	FARMINGTON-COMANCHE	NE 05 TO67	R08W 5-12	D
				14-15	D
				16-17	D,E
				18-23	D
A89008	DOUDS STONE INC	SELMA-GARDNER	NW 16 TO70	R11W 14-31	D,E
A92002	MARTIN MARIETTA	WESTCHESTER	NE 19 TO76	R08W 22-31	D,E
A92008	RIVER PRODUCTS CO	PEPPER-KEOTA FIELD	SW 31 TO76	R09W 15-16	D,E
AIL014	CESSFORD CONST CO	DALLAS CITY	SW 36 TO08	R07W 2-20	D
AIL020	GRAY QUARRY, INC	GRAY	NE 31 TO05	R08W 22-28	D
AMO002	L&W QUARRIES	KAHOKA	NE 17 TO65	R07W 29-36	D
AMO012	MARTIN MARIETTA	JEFFERIES	NW 03 TO66	R26W 5-6	D,E
AMO024	CENTRAL STONE	HUNTINGTON	NE 17 TO56	R06W 2A	D,E
				2A-3B	D,E
				25C-25D	D,E
				6-11	D,E
DIST. 6					
A06006	WENDLING QUARRIES INC	GARRISON B	NE 33 TO85	R11W 6-23	A,B,D,E
A06012	COOTS MATERIALS CO INC	JABENS	SW 07 TO85	R11W 6-11,12	A,B,D,E
A06016	COOTS MATERIALS CO INC	COOTS	SW 36 TO86	R11W 2A ON DOWN	D
A16004	WENDLING QUARRIES INC	LOWDEN-SCHNECKLOTH	NW 04 TO81	R01W 1	A,B,D,E
A16006	WENDLING QUARRIES INC	MCGUIRE	SE 14 TO80	R03W 4A-4D	A,B,D,E
A16008	WENDLING QUARRIES INC	LIME CITY	NE 16 TO79	R02W 2	A,B,D,E
A16012	WEBER STONE CO	ONION GROVE	SE 14 TO82	R02W 1-7	A,B,D,E
A16014	WENDLING QUARRIES INC	TOWNSEND	NW 02 TO79	R02W 2-10	A,B,D,E
A16022	WENDLING QUARRIES INC	TRICON	N2 09 TO82	R04W 1	A,B,D,E
A23002	WENDLING QUARRIES INC	BLOORE-ELWOOD	NW 08 TO83	R02E 1-2	A,B,D,E
A23004	WENDLING QUARRIES INC	BEHR	SW 02 TO81	R03E 1-2	A,B,D,E
A23006	WENDLING QUARRIES INC	SHAFFTON	NE 11 TO80	R05E 16-17	A,B,D,E
				3-14	D
A23010	WENDLING QUARRIES INC	GOOSE LAKE	SW 22 TO83	R05E 2-4	E
A23012	WENDLING QUARRIES INC	TEEDS GROVE	SW 03 TO83	R06E 2-4	A,B,D,E
A23016	WENDLING QUARRIES INC	LYONS	NW 18 TO82	R07E UPPER OR LOWER	E
				LEDGE	
A23018	WENDLING QUARRIES INC	KINGS	NW 06 TO80	R03E FULL FACE	E
A28008	KUHLMAN CONST	EDGEWOOD WEST	CT 04 TO90	R05W 2-7	A,B,D,E
A28010	KUHLMAN CONST	TIBBOTT	SW 23 TO90	R04W 1-5	A,B,D,E
A28014	KUHLMAN CONST	LOGAN	SW 10 TO88	R05W 2-8	A,B,D,E
A28016	KUHLMAN CONST	WHITE	NW 02 TO88	R04W 1-2	A,B,D,E
A28020	BARD CONCRETE	DEUTMEYER	SW 13 TO88	R03W 1-6	A,B,D
A28030	KUHLMAN CONST	GRIEF	NE 18 TO87	R03W 1-2	A,B,D,E
A28038	KUHLMAN CONST	EDGEWOOD EAST	NW 06 TO90	R04W 1B-5	A,B,D,E
				2-6	E
A28040	BARD CONCRETE	KRAPFL	SE 23 TO89	R03W 1-5	A,B,D
				4	E
A28052	RIVER CITY STONE CO	MANCHESTER	SW 09 TO88	R05W 6-8	A,B,E
				TOP LEDGES-NORTH	D
A28056	RIVER CITY STONE CO	THORPE	NW 33 TO90	R05W FULL FACE	A,B,D,E
A31006	KUHLMAN CONST	DYERSVILLE	SE 32 TO89	R02W 4-12	A,B,D,E
A31008	RIVER CITY STONE CO	KLEIN-RICHARDSVILLE	NW 33 TO90	R01E 2-4B	A,B,D
				3A-4B	E
A31010	RIVER CITY STONE CO	BROWN	NW 33 TO89	R02E FULL FACE	D
				3-9	A,B,E
A31014	BARD CONCRETE	KURT	N2 TO87	R02W 1-2	A,B,D,E
A31018	RIVER CITY STONE CO	MELOY	NW 23 TO87	R01E FULL FACE	A,B,D
				1-3	E
A31020	RIVER CITY STONE CO	SCHLITCHE	SE 11 TO89	R02W 1-4	A,B,D,E
A31026	WENDLING QUARRIES INC	ARNSDORF	SE 25 TO87	R02E 1-2	A,B,D,E
A31028	RIVER CITY STONE CO	THOLE	NW 21 TO87	R02E 2-3	A,B
				3	D,E
A31034	RIVER CITY STONE CO	HERMSEN	NE 33 TO90	R02W 1-2	A,B,D,E
A31036	RIVER CITY STONE CO	BALLTOWN	SE 05 TO90	R01E 1-7	A,B,D,E
A31040	RIVER CITY STONE CO	KENNEDY	NW 03 TO88	R01W FULL FACE	A,B,D,E



		REVETMENT STONE SOURCE APPROVAL				
CODE	OPERATOR	SOURCE NAME	LOCATION	BEDS	REVETMENT CLASS	
*****						
DIST. 6						
A31044	RIVER CITY STONE CO	GASSMAN	SE 07 T088	R03E	2-9	A
					2-10	B,D
					5-9	E
A31050	RIVER CITY STONE CO	PLOESSEL-DYERSVILLE	N2 07 T088	R02W	2-5	A,B,D
					3-5	E
A31052	WEBER STONE CO	EPWORTH-KIDDER	SW 02 T088	R01W	FULL FACE	A,B,D,E
A31056	RIVER CITY STONE CO	RUBIE	SE 06 T088	R03E	5-9	A,B,E
					FULL FACE	D
A31058	RIVER CITY STONE CO	HOLY CROSS	SW 12 T090	R02W	FULL FACE	A,B,D,E
A31060	BARD CONCRETE	CASCADE EAST	SE 22 T087	R01W	2-5	A,B,D,E
A31064	RIVER CITY STONE CO	WEBER	NE 32 T089	R02E	3-9A	A,B,D,E
A31066	RIVER CITY STONE CO	FILLMORE	SW 26 T087	R01W	FULL FACE	A,B,D
					2-4	E
A49008	WEBER STONE CO	IRON HILL	SW 16 T085	R02E	1-6	A,B,D,E
A49010	WENDLING QUARRIES INC	ANDREW	NW 21 T085	R03E	1B-5B	E
A49012	WENDLING QUARRIES INC	FROST	SE 16 T084	R03E	1A-1E	A,B,D,E
A49016	WENDLING QUARRIES INC	WEIS	SE 22 T085	R04E	7	A,B,D,E
A49018	WENDLING QUARRIES INC	PATASKA	NW 23 T085	R05E	1	A,B,D,E
A49020	WENDLING QUARRIES INC	PRESTON	SW 26 T084	R05E	1-10	E
A49022	WENDLING QUARRIES INC	BELLEVUE	SE 23 T086	R04E	1B-3	E
A49024	WENDLING QUARRIES INC	MAQUOKETA EAST	SW 07 T084	R03E	4-8	A,B,D,E
A49040	WENDLING QUARRIES INC	JOINERVILLE	SE 20 T084	R02E	1-3	A,B,D,E
A52002	WENDLING QUARRIES INC	FOUR COUNTY	NW 04 T081	R08W	9-16	D
A53002	BARD CONCRETE	FARMERS-BEHREND	NE 14 T086	R03W	1-5	A,B,D,E
A53004	WENDLING QUARRIES INC	MONTICELLO	NE 24 T086	R04W	FULL FACE	A,B,D,E
A53010	WENDLING QUARRIES INC	BALLOU-OLIN	NE 24 T083	R03W	FULL FACE	A,B,D,E
A53012	WENDLING QUARRIES INC	WYOMING	33 T084	R01W	1-2C	A,B,D,E
A53014	WEBER STONE CO	JACOBS-SCOTCH GROVE	SW 07 T085	R02W	FULL FACE	A,B,D,E
A53016	WEBER STONE CO	STONE CITY	E2 06 T084	R04W	1,3	A,B,D,E
A53018	RIVER CITY STONE CO	FINN	NE 06 T085	R01W	2-5	A,B,E
					FULL FACE	D
A53024	RIVER CITY STONE CO	SULLIVAN	NW 14 T086	R03W	FULL FACE	A,B,D,E
A53026	RIVER CITY STONE CO	ANAMOSA	SW 15 T084	R04W	REEF MATERIAL	A,B,D,E
A57002	WENDLING QUARRIES INC	BETENBENDER-COGGON	SW 03 T086	R06W	1-10	A,B,D,E
A57010	WENDLING QUARRIES INC	TROY MILLS	SE 09 T086	R07W	FULL FACE	D
A57014	WENDLING QUARRIES INC	SWEETING	NW 18 T085	R08W	1-4	D
A57028	WENDLING QUARRIES INC	CEDAR RAPIDS	NW 07 T082	R07W	6	A,B,D,E
A70002	WENDLING QUARRIES INC	MOSCOW	NW 08 T078	R02W	11-17	D,E
					21A-24	D,E



October 2, 2001  
Supersedes April 25, 2000

## APPROVED PRODUCERS

## WITH QC PROGRAMS

PRODUCER	STREET ADDRESS	CITY, STATE, ZIP	PHONE/FAX NUMBER
<b>A</b>			
ACME FUEL & MATERIALS CO.	2544 PETTIBONE AVE.	MUSCATINE, IA 52761	(319) 263-1105
AGGREGATE MATERIALS CO.	1400 E 12th STREET	DUBUQUE, IA 52001	(319) 583-6642
AGGREGATES, INC.	6101 BLAIRS FERRY ROAD NE	CEDAR RAPIDS, IA 52411	(319) 395-0050
ANDERSON SAND & GRAVEL CO.	2578 270th AVE	DEWITT, IA 52742	(319) 659-5506
ARCADIA LIMESTONE CO.	19011 CRYSTAL AVE.	ARCADIA, IA 51430	(712) 689-2299
<b>B</b>			
BARD CONCRETE	2021 325th AVE	DYERSVILLE, IA 52040	(319) 875-7145 Fax (319) 875-7860
BASIC MATERIALS CORP.	2625 W. AIRLINE HWY, BOX 2277	WATERLOO, IA 50704	(319) 235-6583 Fax (319) 235-7065
BECKER GRAVEL CO., INC	515 WILLOW ST, BOX 229	STRATFORD, IA 50249	(515) 838-2475 Fax (515) 838-2472
BEDROCK GRAVEL CO.	3527 320th STREET	AUBURN, IA 514333	(712) 688-2418
BELLCO OF NEBRASKA, INC.	2826 SOUTH AVE	COUNCIL BLUFFS, IA 51503	(712) 322-8501 Fax (712) 322-8526
BELLEVUE SAND & GRAVEL CO.	29427 HWY 52	BELLEVUE, IA 52031	(319) 872-3886
BLAZEK CORPORATION	1830 RIDGEWAY BLVD.	LAWLER, IA 52154	(319) 238-7150
BOGGESS CONSTRUCTION CO.	321 NORTH 17th COURT	ESTHERVILLE, IA 51334	(712) 867-4516
BOYER SAND & ROCK INC.	4162 BIRCH AVE	HAWARDEN, IA 51023	(712) 552-2308 Fax (712) 552-2677
BROCKMAN SAND CO.	2397 263rd AVE, BOX 312	FORT MADISON, IA 52627	(319) 372-7138
BRUENING ROCK PRODUCTS INC.	325 WASHINGTON ST., BOX 127	DECORAH, IA 52101	(319) 382-2933 Fax (319) 382-8375
BUILDERS SAND & CEMENT CO.	104 WESTERN AVENUE	DAVENPORT, IA 52801	(319) 322-1757
<b>C</b>			
CENTRAL STONE CO. #1	RR 1, BOX 236	HANNIBAL, MO 63401-9622	(573) 735-4525
CESSFORD CONST. CO.-SE DIV.	3808 OLD HWY 61	BURLINGTON, IA 52601	(319) 753-2297 Fax (319) 753-0926
CESSFORD CONST. CO.	2320 ZELLER AVE	LE GRAND, IA 50142	(641) 479-2695 Fax (641) 479-2003
COHRS CONSTRUCTION, INC.	15700 NORTH TRADEWIND DR	SPIRIT LAKE, IA 51360	(712) 832-3714
CONCRETE, INC.	BOX 54	GIFFORD, IA 50259	(641) 858-3637
CONCRETE MATERIALS	1201 WEST RUSSELL	SIOUX FALLS, SD	(605) 357-6000
CONRECO, INC.	4901 G STREET	OMAHA, NE 68117	(402) 733-4100 Fax (402) 733-5774
COOTS MATERIALS CO.	1700 WEST D STREET	VINTON, IA 52349	(319) 472-4480 Fax (319) 472-4485
CORELL RECYCLING	200 SOUTH 13TH STREET	WEST DES MOINES, IA 50265	(515) 223-8010
CRAWFORD QUARRY CO.	HWY 94 NORTHWEST, BOX 1027	CEDAR RAPIDS, IA 52046	(319) 396-5705
CROELL REDI MIX	P.O. BOX 146	SUMNER, IA 50674	(319) 578-3393
<b>D</b>			
DAVE'S SAND & GRAVEL, INC.	RR 2, BOX 58A	HARTLEY, IA 51346	(712) 834-2515
DOUDS STONE, INC.	13133 ANGLE ROAD, SUITE B, BOX 187	OTTUMWA, IA 52501	(641) 683-1671 Fax (641) 683-1673
<b>E</b>			
ESTHERVILLE SAND&GRAVEL CO.	P.O. BOX 97	ESTHERVILLE, IA 51344-0097	(712) 362-3506 T-F 1-800-379-7263



APPROVED PRODUCERS

WITH QC PROGRAMS

PRODUCER	STREET ADDRESS	CITY, STATE, ZIP	PHONE/FAX NUMBER
<b>F</b>			
FALK, L.R. CONSTRUCTION CO.	227 W. 4th ST., P.O. BOX 189	ST. ANSGAR, IA 50472-0189	(641) 736-4569
FLEWELLING SAND & GRAVEL	1157 HWY. 140	MOVILLE, IA 51039	(712) 873-3174
FRED CARLSON COMPANY	P.O. BOX 48	DECORAH, IA 52101	(319) 382-4249
FT. CALHOUN STONE CO.	1255 SOUTH STREET, PO BOX 284	BLAIR, NE 68008	(402) 426-4254
			(402) 468-5666
			(402) 426-4306
			Fax
FORT DODGE ASPHALT CO.	2516 7th AVE. SOUTH	FORT DODGE, IA 50501	(515) 573-3124
<b>G</b>			
GEHRKE QUARRIES, INC.	32215 290th ST.	GIFFORD, IA 50259	(641) 858-3821
			(641) 858-2564
			Fax
GRAY QUARRY INC.	P.O. BOX 386	HAMILTON, IL 62341	(217) 847-2712
GREENE LIMESTONE CO.	1211 SOUTH MAIN ST.	CHARLES CITY, IA 50616	(641) 228-4256
			(641) 228-4061
			Shop
<b>H</b>			
HAHN READY MIX	P.O. BOX 1107	MUSCATINE, IA 52761	(319) 263-6467
HALLETT MATERIALS CO.	5550 NE 22nd ST., BOX 3365	DES MOINES, IA 50316	(515) 266-9928
			(515) 266-9857
			Fax
			WIA
			1-800-838-2615
"HANK" STALP GRAVEL COMPANY	1598 RIVER ROAD	WEST POINT, NE 68788	(402) 372-5491
			1-800-372-5491
			(402) 372-5477
			T-F
			Fax
HECKETT-MULTISERV	C/O N.S.S., HWY 38 & GREENS RD.	WILTON, IA 52778	(319) 732-4010
			(319) 732-4011
			Fax
HECKETT-MULTISERV WEST	P.O. BOX 474, C/O N.S.W.	STERLING, IL 61081	(815) 626-3316
			(815) 626-9306
			Fax
HEARTLAND ASPHALT, INC.	2601 S. FEDERAL AVE.	MASON CITY, IA 50401	(641) 424-1733
HIGMAN SAND & GRAVEL INC.	16485 HWY 12, BOX 109	AKRON, IA 51001	(712) 568-2181
<b>I</b>			
IDEAL SAND CO.	P.O. BOX 416, 3902 MT PLEASANT ST.	W. BURLINGTON, IA 52655	(319) 754-4747
IRON MOUNTAIN TRAP ROCK CO.	P.O. BOX 9137	IRON MOUNTAIN, MO 63650-9137	(573) 734-6106
<b>J</b>			
J.W. READY MIX & CONST.	3111 270th ST.	SAC CITY, IA 50583	(712) 662-4239
<b>K</b>			
KERFORD LIMESTONE CO.	36110 FLETCHER ST.	WEeping WATER, NE 68463	(402) 267-2415
			(402) 267-5240
			Fax
KNOCKS BUILDING SUPPLIES	302 NORTH SIDE	PARKERSBURG, IA 50665	(319) 278-4868
KRUSE PAVING, INC.	P.O. BOX 899	LAKEFIELD, MN 56150	(507) 662-5205
			(507) 662-6725
			Fax
KRUSE ROCK & GRAVEL	1401 T AVENUE, P.O. BOX 466	MILFORD, IA 51351	(712) 338-9084
			1-888-808-7625
			(712) 338-2031
			T-F
			Fax
KUHLMAN CONSTRUCTION CO.	325 MAIN, BOX 126	COLESBURG, IA 52035	(319) 856-3535
			1-800-772-1731
			(319) 856-5505
			T-F
			Fax
<b>L</b>			
LESSARD COTRACTING INC.	P.O. BOX 705	SERGEANT BLUFF, IA 51054	(712) 252-4131
L.G. EVERIST INC.	P.O. BOX 9	DELL RAPIDS, SD 57022	(605) 428-5419
			(605) 428-3012
			Fax
L&M SAND & GRAVEL INC.	426 2nd AVENUE N.E.	LE MARS, IA 51031	(712) 546-5359
L&W QUARRIES INC.	P.O. BOX 335	CENTERVILLE, IA 52544	(641) 437-4830



APPROVED PRODUCERS  
WITH QC PROGRAMS

PRODUCER	STREET ADDRESS	CITY, STATE, ZIP	PHONE/FAX NUMBER
<b>L</b>			Fax (641) 437-4837
LA HARV CONST. CO. INC.	P.O. BOX 267	FOREST CITY, IA 50436	(641) 581-3643
LINWOOD MINING&MINERALS CORP	4321 EAST 60th ST.	DAVENPORT, IA 52807-9744	(319) 359-8251 T-F 1-800-798-8251 Fax (319) 359-8787
LYMAN-RICHEY SAND&GRAVEL CO.	4315 CUMING ST.	OMAHA, NE 68131	(402) 558-2727
<b>M</b>			
MALLARD SAND & GRAVEL MANATTS INC.	P.O. BOX 638, P.O. BOX 535, 1755 OLD 6 ROAD	VALLEY, NE 68064 BROOKLYN, IA 52211	(402) 359-5287 (641) 522-9206 Fax (641) 522-9407 Fax (641) 522-5594
MANATTS SAND & GRAVEL MARENGO READY MIX INC. MARTIN MARIETTA AGGREGATES	1928 340th ST., BOX 87 P.O. BOX 121 11252 AURORA AVENUE	TAMA, IA 52339 MARENGO, IA 52301-0121 DES MOINES, IA 50322	(641) 484-4022 (319) 642-3811 (515) 254-0030 T-F 1-800-332-5433 Fax (515) 254-0035
MARTIN MARIETTA AGGREGATES MATX, INC. MOBERLY STONE CO.	P.O. BOX 629 110 CLUBBRIDGE PLACE P.O. BOX 582	VALLEY, NE 68064 COLORADO SPRINGS, CO 80906 MOBERLY, MO 65270	(402) 359-4088 (660) 277-4419 Fax (660) 277-4790
MOLINE CONSUMERS CO.	1701 5th AVENUE	MOLINE, IL 61265	(309) 757-8250 Fax (309) 757-8257
MOLO SAND & GRAVEL CO. MYRL & ROY'S PAVING INC.	123 SOUTHERN AVENUE 1300 N. BAHNSON AVENUE	DUBUQUE, IA 52001 SIOUX FALLS, SD 57103	(319) 557-7540 (605) 334-3204 Fax (605) 334-0468
<b>N</b>			
NEW ULM QUARTZITE QUARRY	ROUTE 5, BOX 21	NEW ULM, MN 56073	(507) 354-2925 Fax (507) 359-7870
NORTH IOWA SAND&GRAVEL INC.	18237 KILLDEER AVENUE	MASON CITY, IA 50401	(641) 424-5591 Fax (641) 423-1894
NORTHWEST MATERIALS NORTHWEST R/M CONCRETE, INC.	1648 LAINSON AVENUE 6340 180th ST.	FORT DODGE, IA 50501 OCHEYEDAN, IA 51354	(515) 573-8921 (712) 758-3683
<b>O</b>			
ORTONVILLE STONE CO.	P.O. BOX 67	ORTONVILLE, MN 56278	(612) 839-6131
<b>P</b>			
PAUL NIEMANN CONST. CO.	24541 150th ST., BOX 128	SUMNER, IA 50674-0128	(319) 578-3261 Fax (319) 578-3263
PEDERSON BROTHERS PELLA CONST. CO. LTD. PERSINGER SAND & GRAVEL PETERSON CONTRACTORS, INC. PETTENGILL CONCRETE&GRAVEL, INC. PRESTON READY MIX CORP. PRAIRIE SAND & GRAVEL	P.O. BOX 606 BOX 25 3281 LUCAS AVE. 104 BLACKHAWK P.O. BOX A 800 N. BOONE P.O. BOX 399 P.O. BOX 210	HARMONY, MN 55939-0606 PELLA, IA 50219 SMITHLAND, IA 51056 REINBECK, IA 50669 ROCK RAPIDS, IA 51246 PRESTON, IA 52069 PRAIRIE DU CHIEN, WI 53821	(507) 498-3377 (641) 628-3840 (712) 889-2258 (319) 345-2713 (712) 472-2571 (319) 689-3381 (608) 326-6471
<b>Q</b>			
QUALITY CONCRETE CO.	327 17th AVENUE S.	CLINTON, IA 52732	(319) 242-3524
<b>R</b>			
RANDALL TRANSIT MIX CO. RECYCLED AGGREGATE PROD. CO. REILLY CONSTRUCTION CO.	1343 HWY 105, P.O. BOX 153 2131 18th ST. 110 MAIN ST., BOX 99	NORTHWOOD, IA 50459-0153 SIOUX CITY, IA 51105 OSSIAN, IA 52161	(641) 324-1063 (712) 252-7732 (319) 532-9211 Fax (319) 532-9759



APPROVED PRODUCERS

WITH QC PROGRAMS

PRODUCER	STREET ADDRESS	CITY, STATE, ZIP	PHONE/FAX NUMBER
<b>R</b>			
RIVER BEND ENTERPRISES	3000 ASHERTON AVE	NASHUA, IA 50658	(641) 435-2436
RIVER CITY STONE INC.	P.O. BOX 1430	DUBUQUE, IA 52001-1430	(608) 568-3433 Fax (608) 568-3472
RIVER PRODUCTS CO. INC.	103 E COLLEGE, SUITE 220	IOWA CITY, IA 52240-4086	(319) 338-1184 Fax (319) 338-8510
ROHLIN CONST. CO. INC.	P.O. BOX 137	ESTHERVILLE, IA 51344-0137	(712) 362-3549
ROVERUD CONST. CO. INC.	601 HWY. 44 EAST, BOX 606	SPRING GROVE, MN 55974	(507) 498-3376 (507) 498-3377 T-F 1-800-622-7625 Fax (507) 498-5835
RVBT-aka-ROCK VALLEY S & G	1315 17th AVENUE, BOX 9	ROCK VALLEY, IA 51247	(712) 476-2063
<b>S</b>			
S&A CONSTRUCTION LTD.	P.O. BOX 20	ALLENDALE, MO 64420	(660) 786-2233
S&G MATERIALS	4213 SAND ROAD SE	IOWA CITY, IA 52240	(319) 354-1667
SCHILDBERG CONSTRUCTION CO.	BOX 358	GREENFIELD, IA 50849	(641) 743-2131
SCHMILLEN CONSTRUCTION, INC	4772 C AVENUE	MARCUS, IA 51035-0488	(712) 376-2249
SIEH SAND&GRAVEL	101 W. 18th ST., BOX 1503	SPENCER, IA 51301	(712) 836-2244 (712) 262-4580
SHELL ROCK PRODUCTS	22281 WALNUT AVENUE	SHELL ROCK, IA 50670	(319) 885-4302
SPENCER QUARRIES	25341 430TH AVENUE	SPENCER, SD 57374	(605) 246-2344
STONER SAND	RR2	RIDGEWAY, MO 64481	(660) 824-4211
<b>T</b>			
TIEFENTHALER AG-LIME INC.	P.O. BOX 157, 11975 HAWTHORNE AVE.	BREDA, IA 51436	(712) 673-2686
<b>U</b>			
ULLAND BROTHERS, INC.	2400 MYERS ROAD	ALBERT LEE, MN 56007	(507) 373-1960 (507) 433-1819
<b>W</b>			
W. HODGEMAN & SONS INC.	1100 MARCUS ST., BOX 1100	FAIRMONT, MN 56031-1100	(507) 235-3321
WAYNE T. HANSEN CORP.	13 COUNTRY ESTATES	ALGONA, IA 50511	(515) 295-5573
WEBER STONE CO., INC.	12791 STONE CITY ROAD	ANAMOSA, IA 52205	(319) 462-3581 Fax (319) 462-3585
WELDEN AGGREGATES, INC.	P.O. BOX 832	IOWA FALLS, IA 50126	(641) 648-5142 Fax (641) 648-5142
WENDLING QUARRIES, INC.	P.O. BOX 120	DEWITT, IA 52742	(319) 659-9181 Fax (319) 659-3393
WEST DES MOINES SAND CO.	10500 SW 52nd ST.	DES MOINES, IA 50265	(515) 287-2340
WESTERN IOWA LIMESTONE	P.O. BOX 430	HARLAN, IA 51537	(712) 755-2563 Fax (712) 755-5344
WETHERELL EXCAVATING&TRUCKING	P.O. BOX 582	STORM LAKE, IA 50588	(712) 732-4059 (712) 732-2839
WILTGEN CONSTRUCTION CO.	113 E. MAIN ST., BOX 303	CALMAR, IA 52132	(319) 562-3301 T-F 1-800-365-3301
WINN CORP. SAND & GRAVEL	28825 290th ST.	OLLIE, IA 52576	(641) 667-3471
WRIGHT MATERIALS CO.	P.O. BOX 244, 1127 HWY 69	BELMOND, IA 50421	(641) 444-3920
<b>Z</b>			
ZUPKE SAND & GRAVEL	17963 150th ST.	RANDALIA, IA 52164	(319) 428-4444



# NOTES









October 2, 2001  
Supersedes April 25, 2000

Matls. I.M. 204

---

## INSPECTION OF CONSTRUCTION PROJECT SAMPLING AND TESTING

### **PURPOSE**

The purpose of this memorandum is to prescribe general objectives, policies, procedures, and guide schedules for sampling and testing materials and construction. Sampling and testing guides for certain types of construction are attached as appendices to this memorandum.

### **OBJECTIVES**

The objectives of sampling and testing are:

- A. To determine through process control, verification and/or acceptance sampling and testing whether the construction operations controlled by sampling and testing and materials used or proposed for use in the construction work are in reasonably close conformity with approved plans and specifications (including approved changes).
- B. To provide checks or reliability of acceptance sampling and testing through independent assurance sampling and testing by personnel not normally responsible for process control or acceptance.
- C. To provide opportunity for timely remedial action when results of sampling and testing indicate materials used or proposed for use and the construction work accomplished or in progress are not in reasonably close conformity with the approved plans and specifications (including approved changes).

### **PROCESS CONTROL, VERIFICATION, AND/OR ACCEPTANCE SAMPLING AND TESTING**

Process control, verification, and/or acceptance sampling and testing are required to ascertain whether the quality of materials being incorporated into the construction and the quality of construction work in progress are in reasonably close conformity with the plans and specifications. Results of these tests constitute the principal means of determining daily if materials and construction are satisfactory, or whether corrective action should be taken before work proceeds further. They serve as the principal basis for determining the acceptability of completed construction.

#### **Materials Inspection and Acceptance**

In order to provide the contractor the opportunity to construct a project with minimal sampling and testing delays, inspection is performed at the source. Source inspection may consist of inspecting process control, sampling for laboratory testing or a combination of these procedures. All source-inspected or certified materials are subject to inspection at the project site prior to being incorporated into the work. Project site inspections are for identification of materials with test reports and for any unusual alterations of the characteristics of the material due to handling or other causes. Supplemental monitor samples secured by project personnel of source-inspected, certified or project processed materials are also required for some materials in order to secure satisfactory evidence for acceptance.



---

## Source Inspection

Materials with characteristics, which do not easily change, will normally be accepted at the time of incorporation into the work on the basis of compliant source inspection test reports or certifications. This also applies to materials in which the packaging or form of shipment ensures proper identification of the materials and the original material characteristics.

Supplemental sampling and testing of source inspected material are required for some materials which are subject to change during delivery. This also applies to some materials, which are difficult to identify with source inspection test reports. Except for unusual situations, the contractor may, on the contractor's responsibility and at the contractor's risk, incorporate these materials into the work before completion of the required supplemental tests. Acceptance of these materials will be based on source inspection tests and tests of the supplemental samples.

In the case of aggregate quality, production from an approved source is required. The source approval includes the Quality Control operation and processing procedures established, and the ledges suitable for the production of crushed stone for the various quality requirements. Random source inspection is performed to detect any significant change in characteristics of a source and any variations of the established Quality Control and on processing procedures. Random sampling and testing is performed to monitor the quality of aggregate being produced from each source. For certain major types of construction, supplemental construction site verification and assurance sampling and laboratory testing for quality are required in addition to the above Quality Control inspection and testing prior to acceptance. The contractor may, on the contractor's responsibility and at the contractor's risk, incorporate these aggregates into the work before completion of supplemental tests. Acceptance for quality will be based on source monitoring and the test results on verification, assurance and/or project samples. Source approval and monitor inspections and tests will be the basis for acceptance of other aggregates.

Certified aggregate gradation tests by a certified aggregate technician in accordance with the requirements of Materials I.M. 209 and 210, are required by paragraph 1106.01 of the Standard Specification.

Certified source aggregate gradation tests will be considered advisory when the aggregate acceptance is determined by sampling and testing on the project in accordance with the appended sampling and testing guides. The advisory tested group is called **proportioned aggregate**. Source gradation tests may be considered the basis of acceptance for all other aggregates. The gradation tests are called certified gradation tests and the aggregates represented are called certified aggregates.

## Certification Procedures

In the case of many materials it is more economical, efficient, and practical to require certification procedures in lieu of source inspection. Certified test results are required for some materials and only a certificate of compliance is required for other materials. The acceptance of some proprietary materials is on an approved source or brand basis.



For many of the materials for which certification procedures are required, supplemental testing of samples secured by contractor process control personnel or project monitoring personnel and verification and/or assurance samples secured by District personnel are also required as part of the basis of acceptance. When certification procedures are required, the contractor may, on the contractor's own responsibility and at the contractor's risk, incorporate these materials into the work. Acceptance will be based on satisfactory certification and compliance of the test results of any supplemental samples. When supplemental samples are not required, acceptance will be based on satisfactory certification.

The certificate of compliance shall be signed by an authorized representative of the company.

### **Small Quantities of Materials**

When small quantities of construction materials are involved and the cost of sampling and testing would be excessive, or the performance of the material is not critical, visual inspection or compliance certificates may be the basis for acceptance.

### **Sampling & Testing Guides**

The appended sampling & testing guides schedule indicates the minimum inspection, sampling and testing procedures required within the guide policy and procedures for the process control, acceptance, verification and assurance of materials and construction work. **NOTE:** There are two sets of sampling & testing guides - One in S.I. units (metric) and one in U.S. units (in./lb.).

## **PROJECT PLANT, FIELD LABORATORY AND GRADE INSPECTION AND ACCEPTANCE**

The project inspectors and/or the contractor process control technicians shall identify and inspect all materials received on the project before the materials are incorporated into the work. They shall ascertain that proper inspection reports or certifications are on hand and there have been no unusual alterations in the characteristics of the materials due to handling or other causes. In the event they are unable to properly identify the materials delivered or that materials were not inspected before delivery, the District Materials Office shall be notified. Project plant, field laboratory, and grade control sampling and/or testing shall be performed by the contractor process control personnel or the contract authority personnel as outlined in the sampling and testing guides and all other applicable instructions. When certified plant inspection or sampling and testing are provided by the contractor, those tests shall be known as process control tests. The acceptance testing will be the responsibility of the contract authority. With documented and satisfactory correlation test results, a contractor's process control test results may be used as acceptance. Test results determined by the District or Central laboratories, which indicate specification noncompliance, will be promptly reported to the project engineer office by telephone or Fax.

When certified plant inspection is required, the contractor's process control test results for aggregate gradation shall be the basis of acceptance. This acceptance will be dependent on satisfactory correlation with the contract authority's test results, in accordance with I.M. 216. The minimum frequency, for acceptance testing, shall be in accordance with I.M. 204.

Acceptance sampling and testing shall be performed by personnel that are certified by the Iowa



**Department of Transportation, Office of Materials.** When contractor process control sampling and testing are used as part of the acceptance decision, the sampling and testing shall be performed in laboratories, and by personnel, that are qualified by the Iowa DOT Office of Materials. This will be accomplished by a certified technician training program, an independent assurance (IA) program, and by a satisfactory correlation program with regional and/or Central Materials laboratories.

A Non-compliance Notice (Form #830245) will be immediately delivered to the acting representative of the contractor for the area of construction involved whenever project or laboratory test results indicate noncompliance with the specifications and/or plans. Appropriate action in accordance with specifications and instructional memorandums shall be taken.

### **VERIFICATION AND ASSURANCE SAMPLING AND TESTING**

Independent verification sampling and testing will be performed to validate the quality of a material (e.g. freeze-thaw durability, abrasion, specific gravity, etc.) or a product (e.g. AC content, voids, density, smoothness, etc.). Those verification tests will be performed on the individual materials and/or the products considered to be the most critical and are identified in the attached guides. Independent assurance inspection will be performed as a check on the reliability of a material and the process control and acceptance sampling and testing. It is the responsibility of the **District Materials Engineer** to provide the verification and assurance inspection as outlined herein and designated in the sampling and testing guides. Personnel assigned to either of these activities shall be certified by the Iowa Department of Transportation, Office of Materials and not have any direct responsibility for project process control or acceptance sampling and testing.

Assurance samples of materials are required in some cases for testing to secure supplemental data for acceptance of source inspected or certified materials. The majority of the assurance samples are for validating process control and acceptance sampling and testing.

Verification and assurance sampling and testing shall be performed using test equipment other than that assigned to the project. Occasionally, for expedient situations, the project test equipment may be used. When specified in the appendices or when small quantities of materials are involved, the assurance sampling and testing may be accomplished by observation of the acceptance sampling and testing performed by contract authority personnel. When similar material is being incorporated into the work and processed through the same plant for more than one project, one verification or one assurance sample may be taken to represent those projects. Test results on the sample are to be reported to all projects represented by the sample.

Assurance Sampling and Testing for Incidental Concrete, as described in I.M. 528, is not required.

Assurance samples of materials for which project personnel are performing acceptance sampling and testing will normally be taken at approximately the same time and location as the project acceptance samples. Verification samples will be taken at random and will not be part of a split sample.



Samples of other materials, which require laboratory testing, are to be taken in accordance with the sampling and testing guides and appropriate instructions.

A report of the assurance tests, and the companion project acceptance tests will be made by the individual performing the assurance tests. If there are any significant discrepancies between the test results, the report shall document the procedures used to evaluate and reconcile the differences and be signed by the District Materials Engineer. Generally, the report of the verification testing will be signed by the Central Laboratory Testing Engineer. The documentation to evaluate and reconcile any significant differences between process control and verification test results will be signed by the District Materials Engineer.

The frequency of assurance sampling should be increased when it appears that the average values of the test results are approaching either an upper or lower specification limit. If the test results on assurance samples, or verification samples, do not reflect the indicated quality of the material or if they are outside specification requirements, the District Materials Engineer should be consulted promptly concerning the cause, degree, and necessity for correction. Additional samples may be necessary to determine the cause of the deviations. Should there be any dispute over a discrepancy between contractor process control test results and verification or acceptance test results, the central office Materials Laboratory's test results will be considered as being the correct value.

The location, frequency, and responsibility for assurance and verification samples are designated in the attached sampling and testing guides.

It is not always possible to coordinate the assurance sampling from projects where small quantities of materials are incorporated in a short period of time. In such cases, assurance samples may be waived by the District Materials Engineer. However, assurance sampling is encouraged when possible. Quantities below which assurance samples are not required are shown in the appropriate appendixes.

The District Materials Engineer may opt to use a system basis for conducting the independent assurance responsibility. The frequency of sampling and testing will be based on quantity of production, a unit of time, or a combination of the two rather than a project basis. When a system basis is used, an annual report will be made to document the performance of the program.

### **SAMPLING AND TESTING GUIDE SCHEDULES**

The following guides prescribe the minimum frequency for sampling and testing, the indicated inspection locations and the size for each sample type. The guide frequencies are considered to be the minimum required for proper project documentation under normal construction conditions and procedures. More frequent sampling may be required by special conditions such as low or intermittent production, or widely varying test results, and must be initiated at the discretion of and by contractor process control and project inspection personnel. Test results reported via computer terminal may not be identified by a report form number.



---

**NOTE:** Currently only asphaltic concrete projects follow the Quality Control/Quality Assurance (QC/QA) guidelines. The sampling and testing frequencies are described, in detail, in the specifications for these Quality Management-Asphalt (QM-A) projects and are not included in the attached guides.

In order to maintain as much clarity as possible in the Guide Schedules, the changes from the last issue are not marked. The Schedules should be checked carefully for changes.



---

**I.M. 204 Appendixes**

Appendix A	Roadway and Borrow Excavation and Embankments
Appendix B	Deleted
Appendix C	Modified Subbase
Appendix D	Granular Subbase
Appendix E	Portland Cement Conc. Pavement, Pavement Widening, Base Widening, Curb and Gutter & Class 1 Shoulders
Appendix F	Type A Asphaltic Concrete
Appendix G	Type B Asphalt Concrete, Type B Asphaltic Concrete Base Subbase and Base Widening
Appendix H	Structure Concrete, Reinforcement, Foundations & Substructures, Conc. Struct., Conc. Floors, & Conc. Box, Arch & Circular Culverts
Appendix I	Soil Aggregate Subbase
Appendix J	<del>Deleted</del>
Appendix K	Cold-In-Place Asphalt Cement Concrete Recycling
Appendix L	Granular Surfacing/Driveway Surfacing
Appendix M	Concrete Bridge Floor Repair & Overlay & Surfacing
Appendix P	Bituminous Seal Coat
Appendix Q	Deleted
Appendix R	Deleted
Appendix T	Base Repair 2212, Concrete Pavement Repair 2529 & 2530
Appendix U	Granular Shoulders
Appendix V	Subdrains







October 2, 2001  
Supersedes October 3, 2000

---

## I.M. 204 SUPPLEMENTAL GUIDE BASIS OF ACCEPTANCE

### TEST REPORT

The Office of Materials has the responsibility to sample and/or inspect the material for compliance. They will issue a test report after the necessary testing and/or inspection. The inspector must have this report before the material is incorporated into the project. The report number and amount approved must be recorded in accordance with the Office of Construction documentation procedures.

### CERTIFICATION OF COMPLIANCE

Material to be incorporated into the project must be tested and approved. Testing and approval may include test report, certification, or visual approval. The certification comes in a variety of forms, stamped or preprinted on truck tickets as with aggregates; stamped or preprinted on invoices as with Portland Cement and asphalt cement; stamped or printed on the mill analysis as with reinforcing steel, structural steel, and other metals; furnished as a separate document with each shipment as with zinc-silicate paint, engineering fabrics, epoxy coatings, and dowel baskets; stamped or printed on a list of materials for each shipment as with CMP, concrete pipe, clay tile, and corrugated plastic subdrain; in the form of a guaranteed analysis as with seed labels. The inspector shall verify that the certification has been received by documenting it in the project materials book. Certifications shall be Type A, Type B, Type C, Type D or other type as required by the engineer for specific products. A copy of the test report or certification verifying compliance with the applicable specifications will accompany all materials supplied to a project by a jobber unless acceptance is by brand name or approved source. Examples of typical certifications are attached.

These types of certification shall be used by project personnel for acceptance and incorporation of materials into the projects. However, other types of certification from approved manufacturers or producers, as required by appropriate Instructional Memorandums, may also be furnished to the District Materials or Central Materials Offices to ensure compliance with Quality Control testing required for an approved source.

### TYPE A

The manufacturer or producer shall prepare a Type A certification. It shall consist of a certified copy of a laboratory report, which lists results of specified tests and shall certify that the materials furnished comply with the specifications. The tests may be conducted in the laboratory of the manufacturer or in another qualified laboratory. Such tests shall have been conducted on samples obtained from the lot or lots of material identifiable in the shipment.

**Examples:** Steel H-piles  
Structural steel materials  
Reinforcing steel  
ASTM A36, anchor bolts  
Seven-wire strand for prestressed concrete  
Seeds



---

### **TYPE B**

The manufacturer or producer shall prepare a Type B certification. It shall include the maximum and minimum results for the specified tests and shall certify that the lot of materials furnished complies with the specifications. The applicable specification shall be referred to in the certification. The tests may be conducted in the laboratory of the manufacturer or in another qualified laboratory.

**Examples:** Aluminum pipes and sheets  
Aluminum grating

### **TYPE C**

A Type C certification shall be prepared by the manufacturer or producer and shall certify that the materials furnished are in accordance with the specifications. The applicable specification or Materials I.M. shall be referred to in the certification.

**Examples:** Structural plate pipe  
Latex emulsion  
Packaged PC premix  
Clay tile

### **TYPE D**

A Type D certification shall be in the form of a letter or statement of compliance from the approved manufacturer. The letter or statement of compliance shall state that the materials furnished comply with the applicable specifications of Iowa Department of Transportation.

**Examples:** PE tubing  
Cement  
Fly Ash  
Paint  
CMP  
Asphalt Cement  
Aggregate  
Plastic pipe (PVC, PE, ABS)

### **APPROVED BRAND**

The material must be listed in the appropriate Office of Materials I.M. in order to be used on a project. The project inspector shall document information about this material such as product name, source, date, producer, lot number, in the project materials book.

Certification of compliance is not needed when material is accepted by approved brand.

### **APPROVED SHOP DRAWING & APPROVED CATALOG CUT**

This information must be submitted to, and reviewed by the Iowa DOT Central Design Offices before the material can be incorporated in the project.



---

### **TEST REPORT BY AN APPROVED INSPECTION AGENCY**

All treated and untreated timber products, including posts, piling, and lumber, must be tested by an approved inspection agency. A certified report will show the results of the tests. If the supplier is furnishing material from stored stock, a certification statement shall be included with each shipment stating that the material has been inspected by an approved agency.

### **AS PER PLAN & ENGINEER, VISUAL APPROVAL BY PROJECT ENGINEER, APPROVED BY RCE, & MANUFACTURER RECOMMENDATIONS**

The inspector must document information about this material such as product name, source, producer, lot number, date produced in the project materials book. The inspector shall make sure the material meets the requirements of the plans, the engineer, or the manufacturer before the material is used. Visual approval requires construction personnel to visually inspect the material to determine if it generally complies with the specifications. Visual approval is appropriate for non-critical items such as mulch or sod stakes, where general compliance can be readily determined by visual means. If there are questions on specification compliance, samples will be taken for testing.

### **APPROVED SOURCE**

Material furnished must be from a manufacturer or distributor listed in the appropriate I.M. to be used on a project. The project inspector shall document pertinent information such as product name, source, date of production, distributor, etc, in the project materials book.

### **LOT ACCEPTANCE**

Material furnished on a lot accepted basis must be from an approved brand and lot on a list maintained and provided by Central Materials. Materials on the list have been sampled, tested, and determined to comply with applicable specifications and I.M.'s. If a product from a lot is not listed, it must be sampled and tested prior to incorporation in the project. If the sample complies with specifications, it will be added to the list of accepted lots and may be used on the project.

### **FABRICATION REPORT**

The project inspector must have a copy of the final fabrication report prior to incorporating the component into the project. Contents of the report will vary depending on the requirements of the appropriate Materials I.M. for the component being fabrication. Final acceptance is by construction personnel at the project site, and is based on proper documentation and the condition of the component.







Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Abrasives for Blast Cleaning	<a href="#">482.03</a>			Approved Brand	
Admixture - Air Entraining	<a href="#">403</a>	<a href="#">4103</a>	0.5 L/Lot	Approved Brand/Lot Accept	
Admixture - Latex Emulsion		<a href="#">2413.02b</a>		Certification	C
Admixture - Retarder	<a href="#">403</a>		0.5 L/Lot	Approved Brand/Lot Accept	
Admixture - Water Reducer	<a href="#">403</a>		0.5 L/Lot	Approved Brand/Lot Accept	
Aggregates - General	<a href="#">209</a> <a href="#">409</a> <a href="#">T-203</a> <a href="#">T-204</a>	<a href="#">4110</a> to <a href="#">4133</a>		Approved Source	
Aggregates - Gradation	<a href="#">301</a> to <a href="#">306</a> , <a href="#">209</a>	<a href="#">4109</a>	<a href="#">I.M. 301</a>	Certification	D
Aluminum, Structural		<a href="#">4190.01</a>		Approved Shop Drawing and Fabrication Report	
Anchor Bolts			1 Bolt, Nut & Washer	Approved Shop Drawing & Test Report ( Steel Mill Certifications)	A
Anchors, Concrete	<a href="#">453.09</a>			Approved Brand	
Anti-Strip Agent	<a href="#">491.16</a>			Approved Brand	
Arrow Panels, Solar Assisted	<a href="#">486.12</a>	<a href="#">2528.06</a>		Approved Brand	
Asphalt Cement	<a href="#">437</a>	<a href="#">4137</a>	1 L	Approved Source/Cert./Test Report	D
Asphalt, Cutback	<a href="#">437</a>	<a href="#">4138</a>	1 L	Approved Source/Cert./Test Report	D
Asphalt, Emulsified	<a href="#">437</a>	<a href="#">4140</a>	1 L	Approved Source/Cert./Test Report	D
Asphalt, Polymer Modified	<a href="#">437</a>		1 L	Test Report (Approved Batch)	
Backer Rod for Cold Pour Joint Seal	<a href="#">436.04</a>	<a href="#">4136.02c</a>		Approved Brand	
Backer Rod for Hot Pour Joint Seal	<a href="#">436.04</a>	<a href="#">4136.02c</a>		Approved Brand	
Barrier Rail, Precast Concrete	<a href="#">571</a>			Source Approval/DOT Stamp/Fabrication Report	
Beads, Glass		<a href="#">4184</a>	1 L/Lot	Cert./ Lot Accept	D
Bearing, Bronze		<a href="#">4190.03</a>	1/Project	Test Report	
Bearing, Lead		<a href="#">4195.01</a>		Certification	D
Bearing, Neoprene	<a href="#">495.03</a>	<a href="#">4195.02</a>	1 Pad	Source Approval/Fab Report	A



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Bolts, Nuts & Washers, Structural	<a href="#">453.06b</a>	<a href="#">4153.06</a>	Per I.M.	Test Report by Central Lab	
Calcium Chloride Solution	<a href="#">373</a>	<a href="#">4194.01</a>	2 kg or 1 L	Test By RCE	
Caulking Compound		<a href="#">4192</a>		As per Plan & Engineer	
Concrete & Special Sections	<a href="#">445</a>	<a href="#">4145</a> <a href="#">4149.02b</a>		Certification	D
Concrete, Pre-Stressed, Precast Units	<a href="#">570</a>	<a href="#">2407</a>		Iowa DOT Stamp/Fabrication Report	
Concrete Sealer	<a href="#">491.12a</a> <a href="#">491.12b</a>	<a href="#">4139</a>		Approved Brand	
Conduit - See Lighting Material					
Curing Materials - Burlap		<a href="#">4104</a>		Test Report When New	
Curing Materials - Clear	<a href="#">405.07</a>	<a href="#">4105.07</a>		Approved Brand	
Curing Materials - Dark Colored		<a href="#">4105.06</a>	1 L/Lot	Test Report	
Curing Materials - Plastic Film		<a href="#">4106.02</a>		Visual approval	
Curing Materials - White Pigmented		<a href="#">4105.05</a>	1 L/Lot	Approved brand/lot accept	
Delineators - See Signing Materials.					
Dowel - See Steel Reinforcement.					
Drains, Floor		<a href="#">2406.05</a>		Approved Shop Drawing and Fabrication Report	
Drums, Channelizing	<a href="#">488.02</a>	<a href="#">4188.02</a>		Approved Brand	
Epoxy-Coated Steel - See Steel Reinforcement.					
Epoxy Injection Resin	<a href="#">491.19a</a> <a href="#">491.19b</a>			Approved Brand	
Erosion Control, Fertilizer	<a href="#">469.03</a>	<a href="#">4169.03</a>	2 kg or 1 L	Approved Source	
Erosion Control, Fungicide		<a href="#">4169.05</a>		Seed Manufacturing Recommendation	
Erosion Control, Inoculant		<a href="#">4169.04</a>		Seed Manufact. recommendation	
Erosion Control, Jute Mesh		<a href="#">4169.10a</a>	Visual	Visual Approval by Project Engineer	
Erosion Control, Mulch		<a href="#">4169.07</a>	Visual	Visual Approval by Project Engineer	
Erosion Control, Silt Fence Fabric	<a href="#">496.01</a>	<a href="#">4196.01</a>		Approved Brand	
Erosion Control, Silt Fence Wire and		Std. Road		Visual Approval by Project	



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Posts		Plan RC-16 Series	Visual	Engineer	
Erosion Control, Sod		<a href="#">4169.07</a>	Visual	Visual Approval by Project Engineer	
Erosion Control, Sod Stakes		<a href="#">4169.09</a>	Visual	Visual Approval by Project Engineer	
Erosion Control, Sticking Agent		<a href="#">4169.06</a>		Seed Manufacturing Recommendation	
Erosion Control, Wire Staples		<a href="#">4169.10b</a>	Visual	Visual Approval by Project Engineer	
Erosion Control, Wood Excelsior Mat	<a href="#">469.10</a>	<a href="#">4169.10c</a>		Approved Brand	
Expansion Device, Steel		<a href="#">4152.02</a>	Visual	Approved Shop Drawing and Fabrication Report	
Expansion Tube		<a href="#">4191.01b</a>		Visual Approval by Project Engineer	
Fabric, Engineering	<a href="#">496.01</a>	<a href="#">4196.01</a>		Approved Brand	
Fasteners, Aluminum	<a href="#">486</a>	<a href="#">4190.02</a>		Fabrication Report	
Fence, Barbed Wire		<a href="#">4154.04</a>	Visual	Visual Approval By Project Engineer	
Fence, Brace for Field Fence		<a href="#">4154.08</a>	Visual	Visual Approval By Project Engineer	
Fence, Brace, Tie and Tension Wire		<a href="#">4154.05</a>	Visual	Visual Approval By Project Engineer	
Fence, Chain Link Fabric	<a href="#">454.1</a>	<a href="#">4154.03</a>	1 m	Test Report	
Fence, Chain Link Fittings		<a href="#">4154.11</a>	Visual	Visual Approval By Project Engineer	
Fence, Chain Link Posts, Braces, and Rails	<a href="#">454.10a</a> <a href="#">454.10b</a> <a href="#">454.10c</a>	<a href="#">4154.10</a>	150 mm	Test Report	
Fence, Field Fence Fabric		<a href="#">4154.02</a>	Visual	Visual Approval By Project Engineer	
Fence, Gate		<a href="#">4154.12</a>	Visual	Visual Approval By Project Engineer	
Fence, Miscellaneous Hardware			Visual	Visual Approval By Project Engineer	
Fence, Orange Mesh Safety	<a href="#">488.03</a>	<a href="#">4188.03</a>		Approved Brand	
Fence, Silt - See Erosion Control					
Fence, Staples		<a href="#">4154.06</a>	Visual	Visual Approval By Project Engineer	



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Fence, Steel Line Posts		<a href="#">4154.09</a>	1 Post	Test Report	
Fence, Wood Fence Post	<a href="#">462</a>	<a href="#">4154.07</a>		Special Test by Approved Inspection Agency or Certification	D
Fertilizer - See Erosion Control					
Fly Ash	<a href="#">491.17</a>	<a href="#">4108</a>		Certification	D
Galvanized Items		<a href="#">4100.07</a>		Test Report by District Materials	
Grating (Aluminum)		<a href="#">4187.01a5</a>		Approved Shop Drawing and Fab Report	
Grout, Hydraulic Cement	<a href="#">491.13a</a> <a href="#">491.13b</a>			Approved Brand	
Grout, Polymer	<a href="#">491.11a</a> <a href="#">491.11b</a> <a href="#">491.11c</a>			Approved Brand	
Guardrail, Attenuators				As per Plan	
Guardrail, Box-beam Median Barrier		<a href="#">4155.06</a>		Approved Shop Drawing and Fabrication Report	
Guardrail, Cable		<a href="#">4155.03</a>	2 m	Test Report by Central Lab	
Guardrail, Formed Steel Beam	<a href="#">455.02</a>	<a href="#">4155.02</a>		Approved Brand	
Guardrail, Steel Posts		<a href="#">4155.05</a>		Mill Test Report	A
Guardrail, Wood Posts	<a href="#">462</a>	<a href="#">4155.04</a>		Test Report by Approved Inspection Agency or Cert	D
Iron Castings, Manhole Covers, etc		<a href="#">4153.04</a>		Approved Shop Drawing & Test Report by District Materials	
Bridge Rockers		<a href="#">4153.04</a>		Approved Shop Drawing & Fabrication Report	
Joint Filler, Flexible Foam - Type CF and EF Joints	<a href="#">436.05a</a> <a href="#">436.05b</a>	<a href="#">4136.03b</a> <a href="#">4136.03d</a>		Approved Brand	
Joint Filler, Type E Joint	<a href="#">436.03</a>	<a href="#">4136.03a</a>		Approved Brand	
Joint Filler, Bituminous Type	<a href="#">436.03</a>	<a href="#">4136.03a</a>		Approved Brand	
Joint Sealer for Concrete Sewer Pipes	<a href="#">491.09</a>	<a href="#">4149.08</a>		Approved Brand	
Joint Sealer, Elastomeric Neoprene)	<a href="#">436.02</a>	<a href="#">4136.0</a>		Approved Brand	
Joint Sealer, Poured	<a href="#">436.01</a>	<a href="#">4136.02a</a>	5 kg/Lot	Cert./Test Report/Approved Lot	D



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Keyway		<a href="#">4191.01a</a>		Visual by PE	
Lighting Material, Aluminum Poles		<a href="#">4185.02d</a>		Approved Shop Drawing and Fabrication Report	
Lighting Material, Circuit Test		<a href="#">2523.21</a>		Test Report (Contractor)	
Lighting Material, Connectors		<a href="#">4185.11</a>		Approved Catalog Cut	
Lighting Material, Contractors		<a href="#">4185.05</a>		Approved Catalog Cut	
Lighting Material, Control Cabinet		<a href="#">4185.07</a>		Approved Shop Drawing and Catalog Cut	
Lighting Material, Conduit and Fittings		<a href="#">4185.10</a>	1 m-Steel 2 m-Plastic	Test Report	
Lighting Material, Ground Rods and Clamps		<a href="#">4185.04</a>	1 piece	Test Report	
Lighting Material, Handholes	<a href="#">445</a>	<a href="#">4185.08</a>		Certification	D
Lighting Material, Junction Boxes		<a href="#">4185.09</a>		Approved Catalog Cut	
Lighting Material, Lighting Tower		<a href="#">2522.04</a>		Approved Shop Drawing and Fabrication Report	
Lighting Material, Lowering Device		<a href="#">2522.06</a>		Approved Shop Drawing and Fabrication Report	
Lighting Material, Luminaries		<a href="#">4185.03</a>		Approved Catalog Cut	
Lighting Material, Photoelectric Control		<a href="#">4185.06</a>		Approved Catalog Cut	
Lighting Material, Sealant for Traffic Loop Detectors	<a href="#">491.18</a>			Approved Brand	
Lighting Material, Steel Poles		<a href="#">4185.02d</a>		Approved Shop Drawing and Fabrication Report	
Lighting Material, Underground Warning Tape		<a href="#">2523.13</a>		Visual/approval	
Lighting Material, Wire and Cable		<a href="#">4185.12</a>	1 m	Test Report and Approved Catalog Cut	
Lighting Material, Wood Poles	<a href="#">462</a>	<a href="#">4185.02f</a>		Test Report by Approved Inspection Agency or Certification	D
Lighting Materials, Fasteners for Poles		<a href="#">4185.02a</a>	1 Each Type	Test Report and Approved Shop Drawing	



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Lighting Materials, Mastarms		<a href="#">4185.02b</a>		Approved Shop Drawing and Fabrication Report	
Lighting Materials, Slip Base		<a href="#">4185.02</a>		Approved Shop Drawing and Fabrication Report	
Lighting Materials, Transformer Base		<a href="#">4185.02c</a>		Approved Shop Drawing and Fabrication Report	
Markers (reflective) for Guard Rail and Concrete Barrier Rail	<a href="#">486.08</a>	<a href="#">4186.08</a>		Approved Brand	
Markers, Raised Pavement	<a href="#">483.07</a>	<a href="#">2527.02e</a>		Approved Brand	
Mastarms - See Lighting Materials					
Paint, Epoxy Aluminum	<a href="#">482.04</a>			Approved Brand	
Paint, Traffic - VOC Compliant Solvent Borne	<a href="#">483.03</a>	<a href="#">4183.03</a>		Approved Brand/Lot Number in Field Book	
Paint, Traffic - Waterborne	<a href="#">483.03</a>	<a href="#">4183.04</a>		Approved Brand/Lot Number in Field Book	
Paint, Waterborne Acrylic Finish (Bridge Paint)	<a href="#">482.03</a>	<a href="#">4182.03</a>		Approved Source/Cert.	
Paint, Zinc-Rich Epoxy	<a href="#">482.02</a>	<a href="#">4182.02</a>		Approved Brand	
Paint, Zinc-silicate Solvent Borne	<a href="#">482.02</a>	<a href="#">4182.02</a>		Approved Brand	
Paint, Zinc-Silicate Waterborne	<a href="#">482.02</a>	<a href="#">4182.02</a>		Approved Brand	
Patch Material, Rapid-Set Concrete	<a href="#">491.20</a>			Approved Brand	
Piling, Concrete		<a href="#">4166</a>		DOT Stamp/Fabrication Report	
Piling, Steel	<a href="#">467</a>	<a href="#">4167</a>	2'	Mill Certification/District Materials Monitor	A
Pipe, ABS Sewer/PVC	<a href="#">443</a> <a href="#">446</a>	<a href="#">4146.04</a> <a href="#">4146.05</a>		Approved Source/Certification	D
Pipe, Clay Sewer		<a href="#">4149.02a</a>	2 Each	Test Report	
Pipe, Concrete	<a href="#">445</a>	<a href="#">4145</a>		Certification	D
Pipe, Corrugated Aluminum		<a href="#">4142</a>	0.3 m	Test Report	
Pipe, Corrugated Polyethylene 3-10 in.	<a href="#">443</a>	<a href="#">4146.02</a> <a href="#">4143.02</a>	3 pieces 1.5 m each	Approved Source/ Certification/Test Report	D
Pipe, Corrugated Polyethylene 12-36 in.	<a href="#">446</a>	<a href="#">4146.02</a>		Approved Source/Certification	D



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Pipe, Corrugated Steel	<a href="#">441</a>	<a href="#">4141</a>		Certification	D
Pipe, Ductile Iron Sewer		<a href="#">4149.02c</a>		Certification	A
Pipe, Polyethylene Sewer	<a href="#">443</a> <a href="#">446</a>	<a href="#">4146.03</a>		Approved Source/Certification	D
Pipe, Rodent Guard for PE pipe	<a href="#">443.01A</a>	<a href="#">4143.01B</a>		Approved Brand	
Pipe, Rodent Guard for CMP Pipe	<a href="#">443.01B</a>	<a href="#">4143.01B</a>		Approved Brand	
Plant Material, Fertilizer	<a href="#">469.03</a>	<a href="#">4170.09b</a>	2 kg or 1 L	Approved Source	
Plant Material, Mulch	<a href="#">470</a>	<a href="#">4170.09d</a>	Visual	Field Review Report	
Plant Material, Plants	<a href="#">470</a>	<a href="#">4170.01 - 4170.08</a>		Field Review Report	
Portland Cement Concrete Premix Pack	<a href="#">447</a>			Approved Source/Certification	C
Portland Cement Type II	<a href="#">401</a>	<a href="#">4101</a>		Certification	D
Portland Cement Type III	<a href="#">401</a>	<a href="#">4101</a>		Certification	D
Railing, Bridge				Approved Shop Drawing and Fabrication Report	
Reflective Sheeting - See Signing Material.					
Release Agent	<a href="#">491.15</a>			Approved Brand	
Sealant, Traffic Loop - See Lighting Material.					
Seed		<a href="#">4169.02</a>		Certification	A
Signing Material, Delineator Posts		<a href="#">4186.10c</a>	1 Each	Test Report	
Signing Material, Delineators	<a href="#">486.07</a>	<a href="#">4186.07</a>		Approved Brand	
Signing Material, Finished Sign	<a href="#">486</a>	<a href="#">4186</a>		Fabrication Report/ Approved Source/Certification	D
Signing Material, Fasteners		<a href="#">4186.06</a>		Fabrication Report	
Signing Material, Reflective Sheeting	<a href="#">486.03</a>	<a href="#">4186.03</a>		Approved Brand	
Signing Material, Sign Panels		<a href="#">4186.02</a>		Approved Shop Drawing and Fabrication Report	
Signing Material, Sign Support Structures		<a href="#">4187</a>		Approved Shop Drawing and Fabrication Report	



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Signing Material, Steel Posts		<a href="#">4186.10</a>		Approved Shop Drawing and Fabrication Report	
Signing Material, Wood Posts	<a href="#">462</a>	<a href="#">4186.10</a>		Test Report by Inspection Agency or Certification	D
Signing Materials, Galvanized Items		<a href="#">4100.07</a>		Test Report by District Matls.	
Sod - See Erosion Control					
Steel Castings		<a href="#">4153.03</a>		Approved Shop Drawing & Fabrication Report	
Steel Masonry Plates		<a href="#">4152.02</a>		Mill Certification	A
Steel Pile, Welded		<a href="#">4153.05</a>		Approved Shop Drawing & Fabrication Report	
Steel, Pins/Rollers, Cold Finished		<a href="#">4153.02</a>		Approved Shop Drawing & Fabrication Report	
Steel, Pins/Rollers, Forged		<a href="#">4153.01</a>		Approved Shop Drawing & Fabrication Report	
Steel Reinforcement, Basket Assemblies	<a href="#">451</a>	<a href="#">4151.02</a>		Approved Source/Certification	D
Steel Reinforcement, Epoxy-Coated	<a href="#">451.03B</a>	<a href="#">4151.03b</a>	1.5 m of Largest Size in Each Shipment	Mill Certifications & Epoxy Certification/Test Report	A
Steel Reinforcement, Epoxy-Coated Tie Bars	<a href="#">451.03B</a>	<a href="#">4151.02a</a>		Certification	D
Steel Reinforcement, Epoxy-Coated Dowels	<a href="#">451.03b</a>	<a href="#">4151.02</a>		Certification	D
Steel Reinforcement, Galvanized	<a href="#">451</a>	<a href="#">4151.03A</a>	1 m	Mill Certifications & Test Report for Galvanizing	A
Steel Reinforcement, Uncoated	<a href="#">451</a>	<a href="#">4151</a>		Mill Certification	A
Steel Reinforcement, Wire Mesh	<a href="#">451</a>	<a href="#">4151.04</a>	1 m X 1 m	Test Report or Certification	A
Steel Mechanical Splicers for Reinforcement	<a href="#">451</a>			Approved Brand	
Steel, Structural	<a href="#">561 to 565</a>	<a href="#">2408 4152</a>		Appr. Shop Drawing/Fabrication Report/Mill Certifications	A
Step Irons for Utility Access		<a href="#">4149.06</a>		Fabrication Report	
Structural Items, Other				Approved Shop Drawing and Fabrication Report	



Material	I.M.	Spec.	Sample Size	Basis of Acceptance	Cert. Type
Structural Plate (Arches)	<a href="#">444</a>	<a href="#">4144</a>		Certification	C
Studs, Shear	<a href="#">453.10</a>			Approved Source/Cert.	A
Subdrain, Concrete Drain Tile	<a href="#">448</a>	<a href="#">4148</a>	6 Tile	Certification	C
Subdrain, Corrugated Metal Pipe Outlet	<a href="#">441</a>	<a href="#">4141</a>		Approved Source/Cert	D
Subdrain, Corrugated Polyethylene	<a href="#">443</a>	<a href="#">4143.01b</a>		Source Approval/Certification/ Test Report	D
Subdrain, Horizontal		<a href="#">4143.01a</a>	2 m	Test Report	
Surface Finish, Special	<a href="#">491.10</a>	<a href="#">2403.21c</a>		Approved Brand	
Tape, Pavement Marking	<a href="#">483.06</a>	<a href="#">2527.02a</a>		Approved Brand	
Torque Calibration Machine (skidmore)		<a href="#">2408.38c</a>	Calibrate Every 6 Months	Test Report	
Torque Wrench		<a href="#">2408.38c</a>	Calibrate Every 6 Months	Test Report	
Water		<a href="#">4102</a>	1 L/Source	Test Report or City Water Supply	
Wire and Cable - See Lighting Material.					
Wood, Hardware for Timber Structure		<a href="#">4153.07</a>	1 Each Type	Test Report	
Wood, Timber Piles	<a href="#">462</a>	<a href="#">4165</a>		Test Report by Approved Inspection Agency or Certification	D
Wood, Treated Posts	<a href="#">462</a>	<a href="#">4164</a>		Test Report by Approved Inspection Agency or Certification	D
Wood, Treated Timber and Lumber	<a href="#">462</a>	<a href="#">4162</a>		Test Report by Approved Inspection Agency or Certification	D
Wood, Untreated Timber and Lumber	<a href="#">462</a>	<a href="#">4162</a>		Test Report by Approved Inspection Agency or Certification	D



---

GUIDE FOR THE ACCEPTANCE OF SMALL QUANTITIES OF MATERIALS

Material	Maximum Quantity	Specifications	Alternate Acceptance Method
Beads, Glass	0.5 km application	<a href="#">4184</a>	Visual
Dowel Baskets, Epoxy-Coated	25		Visual & Field Check
Fly Ash	5 metric ton		Approved Source & Type
Hardware for Timber	50 kg	<a href="#">4153.07</a>	Visual
Joint Filler, Preformed	15 m	<a href="#">4136.03</a>	Visual & Dimension
Lighting Material - Conduit & Fittings	30 m	<a href="#">4185.10</a>	Visual & Brand Name
Paint, Bridge	20 L	<a href="#">4182</a>	Visual & Brand Name
Pipe, Welded Steel	30 m	<a href="#">4153.05</a>	Letter of Compliance





ION OF USX CORPORATION

01.030.0772 (REV. 4/87)

metallurgical  
Test Report



Q. OF CONTRACT NO.

P.O. DATE

PURCHASE ORDER NO.

11/03/90

640350

SHIPPER NO.

01 04 91

MILL ORDER NO.

INVOICE NO.

B89864

VM12235

187-097245

WHOLE IDENTITY

1A

60296

SOUTH WORKS  
CHICAGO, ILL. 60617

SKYLINE STEEL CORP  
17 W 705-C BUTTERFIELD RD  
OAK BROOK IL 60181

SKYLINE STEEL CORP  
17 W 705-C BUTTERFIELD RD  
OAK BROOK IL 60181

BEING DULY SWORN ACCORDING  
LAW, DEPOSES AND SAYS PRODUCED  
DESCRIBED HEREIN WAS MFGD  
SAMPLED, TESTED AND/OR INSPECTION  
IN ACCORDANCE WITH THE SPECIFICATION  
AND FULFILLS REQUIREMENTS IN SUCH RESPECTS

PREPARED BY THE OFFICE OF:  
J. J. HARRINGTON Q A MGE

BY:

DATE

SRC.  
&  
INSP.

H-PILES CARBON ASTM A36-87

BRF-13-2 (23) -- 38-26

Delaware County

Contract No 32280

Guertka Construction, Ltd

STATE OF INDIANA

COUNTY OF LAKE

SUBSCRIBED AND SWORN TO BEFORE ME  
THIS 04TH DAY OF JANUARY A. D. 1991

NOTARY PUBLIC

MY COMMISSION EXPIRES 11-15-1993

INSP 01 MILL SWORN T/R

ITEM NO.	MATERIAL DESCRIPTION			QUANTITY	WEIGHT	HEAT NO.	TEST OR PIECE IDENTITY	YIELD ST. KSI	TENSILE ST. KSI	ELONGATION%		% RED. OF AREA	BEN.
	THICKNESS OR SECTION	WIDTH, DIA. OR PT. WT.	LENGTH							IN 8"	IN 2"		
05	.4150	HP10X042	42'	07	12348	1R7508	294	49.7 49.3	72.0 72.5	21.0 27.0	40.0 48.0		
05	.4150	HP10X042	42'	06	10584	1R7509	252	33.5 31.5	71.5 73.0	27.0 26.0	48.0 48.0		
06	.4150	HP10X042	48'	08	16128	2R0055	384 930 L.F.	61.5 50.0	74.5 69.5	25.0 27.0	46.0 48.0		
"USS, A DIVISION OF USX, HEREBY CERTIFIES THAT ALL MANUFACTURING PROCESSES, INCLUDING MELTING, INVOLVED IN THE PRODUCTION OF USS STEEL MILL PRODUCTS OCCUR ENTIRELY IN THE UNITED STATES." RESEND OF DATANNN													

HEAT NO.	TYPE	C	MN	P	S	SI	CU	NI	CR	MO	SH	AL	N	V	B	TI	CO	OT
1R7508	HEAT	21	078	009	030	035												
1R7509	HEAT	22	075	009	031	040												
2R0055	HEAT	18	057	008	028	039												
RESEND OF DATANNN																		



October 2, 2001  
Supersedes October 3, 2000

Mats. I.M. 204 Supplemental

CERTIFIED INSPECTION REPORT

A. M. CASTLE AND COMPANY  
P. O. BOX 419809  
KANSAS CITY, MO 64141

A M CASTLE AND COMPANY  
6100 STILWELL  
KANSAS CITY, MO 64120

24-095



ALUMINUM COMPANY OF AMERICA

PITTSBURGH, PA.

SHIPPED FROM: DAVENPORT, IOWA

ALCOA

CUSTOMER P.O. NO./GOVT. CONTRACT NO.

U7-88937

PAGE 003

We hereby certify that the material covered by this report has been inspected in accordance with, and has been found to meet, the applicable requirements described herein, including any conditions forming a part of the description and that samples representative of the material and the composition limits and that the mechanical properties shown on the face of this sheet, for

INVOICE NO. 22544982	INVOICE DATE 91/01/29	CODE 120 170J02	QUALITY ASSURANCE MANAGER <i>J.L. Sely</i>				
ALCOA NO. US 52849	SHIP DATE 91/01/29	VIA HARSON DIXON					
PRODUCT DESCRIPTION PLATE			<table border="1"> <tr> <td>S/L NO. 76702</td> <td>GROSS WEIGHT 4140</td> </tr> <tr> <td colspan="2">ALLOY-TEMPER 6061 T651</td> </tr> </table>	S/L NO. 76702	GROSS WEIGHT 4140	ALLOY-TEMPER 6061 T651	
S/L NO. 76702	GROSS WEIGHT 4140						
ALLOY-TEMPER 6061 T651							

ITEM DESCRIPTION	QUANTITY SHIPPED		NO. OF TESTS & DIR Q			TEST	TEST	TEST	TEST	TEST	TEST	TEST
	PCS, FT. ETC.	POUNDS										
& EXCEPT MARKING ASME-SB-209 REV 83 ((MARKED)) INTERLEAVED SKID WGT: 4500 LB QUAN TOL +/-10 % COR 0124403 REV 09 ORR 000881 ***	LOT-397996 2PC	1651	3 L.T	MAX MIN	UTS1 44.6 44.4	TYS1 39.6 39.2	EL40 14.0 14.0					
	LOT-397982 4PC	1651	3 L.T	MAX MIN	47.4 47.2	42.4 42.2	19.0 13.0					
PACKAGE LOT NO					CASTLE METALS-KC							
440159 398027					DATE REC'D 1-31-91							
440159 398074					REC'D FROM							
444406 397986					APPROVED BY							
444406 397982												
ITEM 4												
1.5000 IN TK X 48.500 IN W X 144.500 IN LN CAT D 124410 (N) A/T 6061-T651 TYPE 200 WROUGHT TOOLING PLATE MILL FINISH, SAWED IAC 8631 PER QQ-A-250/11 REV F & EXCEPT MARKING AMS4027 REV K & EXCEPT MARKING ASTM B209 REV 89 & EXCEPT MARKING ASME-SB-209 REV 83 ((MARKED)) INTERLEAVED SKID WGT: 4500 LB	LOT-230747 3PC	1651	3 L.T	MAX MIN	47.0 46.4	42.5 42.1	15.0 12.0					
	LOT-230744 1PC	1651	3 L.T	MAX MIN	45.7 44.8	40.7 40.1	17.5 13.5					
	LOT-230741 3PC	1651	3 L.T	MAX MIN	47.7 46.8	43.3 42.9	14.5 13.5					
Chemical Composition												
	SI	FE	CU	MN	MG	CR	ZN	TI	OTHER OTHER ALUMINUM			
Max 6061 T651	0.08	0.7	0.40	0.15	1.2	0.35	0.25	0.15	0.05 0.15 REMAINDER			
Min 6061 T651	0.04	0.15	0.15	0.08	0.04	EACH TOTAL						
Chemical Composition												

Max.  
Min.

ALL TESTS PER LOT ARE MADE, THE HIGHEST AND LOWEST VALUES ARE REPORTED FOR EACH TYPE OF EXPLANATION ON THE BACK OF THIS SHEET.

IF DETERMINED.





SHIP TO: PETIT CONSTRUCTION CO.  
BOX 428  
BATTLE CREEK, IA 51006

DATE: 4/19/91  
PROJECT: IDA COUNTY L-901 (1)  
CONTRACTOR: \_\_\_\_\_

CERTIFICATE OF COMPLIANCE

The material covered by this certification was manufactured to comply in full with the specifications of AASHTO M-167.

Based on mill test results, it is certified that the listed materials have been tested and that the test results conform to the requirements of this specification.

SHIPMENT IDENTIFICATION: ORDER NUMBER: 17-9160  
SALES NUMBER: 26-0770-00

ITEM NO.	QUANTITY	MATERIAL DESCRIPTION
001	1 PIPE	GALVANIZED MULTI-PLATE ROUND PIPE: 10 ga., 102 PL, 96'0"  MANUFACTURED FROM THE FOLLOWING HEAT NUMBERS: 101A91A 149P90A 475A90A 2A91A 108A91A
EXAMPLE: TYPE "C" CERT		
AVERAGE WEIGHT OF COATING: 3 OZ. MIN.		

PREPARED BY: Judy A. Gault  
WINCHESTER PLANT







COPY

**MARTIN MARIETTA**

4626448

**AGGREGATES COMPANY**

SOLD TO:

MANATTS INC  
SN-3478(2) — 51-08  
BOONE COUNTY

SOLD FROM:

121  
AMES MINE  
RR2, AMES, IOWA  
(515) 232-3363

DATE: 06/28/91 TIME: 03:08 PM TRX NO. MA63P HAULER NO. 0174 TICKET NO. 4626448

PROD NO. 0816 DESCRIPTION: 1/2 TYPE A CUST NO. 524584 P.O. NO. SCN 507

TONS GROSS: 39.64  
TONS TARE: 16.41  
TONS NET: 23.23

CASH SALE			
MATERIAL	\$	PER	TON
TAX	\$		
HAUL	\$	PER	TON
TOTAL	\$	PAYMENT REC BY.	

LOADS TODAY: 82  
QUANTITY TODAY: 1755.98  
QUANTITY TO DATE: 3448.96

WOMPERSON: SHORT D

STATE SECRETARY OF AGRICULTURE CERTIFIED. EFFECTIVE  
CaCO<sub>3</sub> EQUIVALENT PER TON OF AGGREGATE. \_\_\_\_\_ LBS

DRIVER

CUSTOMER

CERTIFICATION BELOW VALID ONLY  
WITH AUTHORIZED SIGNATURE.  
THIS IS TO CERTIFY THAT THE  
MATERIAL HEREIN DESCRIBED  
MEETS THE APP. CONTRACT  
SPECIFICATIONS & REQUIREMENTS

EXAMPLE:

TYPE "D" CERT



<p>RECEIVED, subject to the classification and terms in effect on the date of the issue of this Bill of Lading</p> <p>DATE: 10/13/91 15H-0724</p> <p>CARRIER/ROUTE: VAN W/ TRUCKING</p> <p>CAR/VEHICLE NO: 136</p> <p>DEST. CODE: 136</p>		<p>CONSTRUCTION PRODUCTS INC.</p> <p>ARMED ARMED PLANT</p> <p>DATE: 10/13/91 15H-0724</p> <p>CARRIER/ROUTE: VAN W/ TRUCKING</p> <p>CAR/VEHICLE NO: 136</p> <p>DEST. CODE: 136</p>		<p>SHIPMENT MUST SHOW THIS NUMBER ON FREIGHT BILLS</p> <p>72-454 F/N</p> <p>ORDER NUMBERS</p> <p>PLANT: 72-0050-10</p> <p>SALES 26-3876-10</p> <p>BUYER:</p>	
<p>CONSIGNEE TO: (MAIL OR STREET ADDRESS OF CONSIGNEE - FOR PURPOSES OF NOTIFICATION ONLY)</p> <p>HCC, INC. 1001, CONST. CO.</p>		<p>IF CHARGES ARE TO BE PREPAID WRITE OR STAMP HERE, "PPD"</p> <p>ORIGIN, FRGT PREPAID</p>		<p>TO EXPEDITE PAYMENT, MAIL A COPY OF THIS BILL OF LADING WITH FREIGHT BILL. FREIGHT BILLS RECEIVED WITHOUT THIS COPY WILL BE RETURNED. MAIL TO COMPUTREX, INC. P.O. BOX 13020, LEXINGTON, KY. 40583.</p>	
<p>EXAMPLE: TYPE "D" CERT.</p>		<p>Subject to Section 1 of conditions of contracts set of being, it is intended to be delivered to the consignee without liability on the carrier, the consignor and the shipping agent.</p>		<p>* N/M This is to certify that the named materials are properly classified, described, packaged, marked and labeled, and are in proper condition for transportation according to the applicable regulations of the Department of Transportation</p>	
<p>1. STATE CERTIFICATION REQUIRED</p> <p>PROJ # 1-10-2</p> <p>2. STA 112224</p> <p>3. BRIDGE BACK 1 - 112224</p> <p>4 - 112224 &amp; 1 - 112224</p>		<p>The material covered by this fabricator's certification statement was manufactured in compliance with the Iowa Department of Transportation's specifications based upon mill certificates and quality control tests. It is certified that representative samples of the listed materials have been tested and that the test results conform to the requirements of those specifications. Material description and project identification are as shown.</p>		<p>PER</p> <p>CONTRACTOR CONSTRUCTION PRODUCTS INC. SHIPPER</p>	
<p>101 H/C PIPE 2 2/3x1/2 GALV WS 16GA 24" 8.00FT 129</p> <p>ROLL ONE END</p>		<p>102 H/C PIPE 2 2/3x1/2 GALV WS 16GA 24" 14.00FT 226</p>		<p>103 CSP BAND 10"HUGGER GALV 16GA 24" 1PC 39</p> <p>W/DRS BOLT &amp; 3" NUT.</p>	
<p>104 H/C PIPE 2 2/3x1/2 GALV WS 16GA 18" 20.00FT 243</p>		<p>105 CSP BAND 10"HUGGER GALV 16GA 18" 1PC 16</p> <p>W/DRS BOLT &amp; 3" NUT.</p>		<p>106 BAND ACC FASTENER STEEL BOLT 1/2"x6" 3</p>	
<p>107 BAND ACC FASTENER STEEL NUT 3</p>		<p>Authorized Signature: [Signature]</p> <p>Date: 7-15-91 6:57 LRG</p> <p>Item # 1-7</p>		<p>Permanent post-office address of shipper:</p> <p>1081 Centre Pl., Lexington, Ohio 45004</p>	



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix A (U.S.) Units

### ROADWAY AND BORROW EXCAVATION AND EMBANKMENTS Section 2102 and 2107

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Special Backfill														
Crushed Stone (4132.02)		AS 209												
Crushed Concrete (4132.02)		209												
RAP(2303.02)														
Gravel (4132.03)		AS 209												
Granular Backfill		AS 209												
Engineering Fabric (4196)	Quality	AB 496.01												
GRADE INSPECTION														
Special & Select Backfill	Moisture	309, 310	RCE	1/lift/ 1500 ft.	1 lb	RCE	Field Book							
Compaction Control														
Moisture & Density Compaction Control	Density (Proctor) Moisture	309, 310	RCE	1/soil class 1/lift/1500 ft.	25 lb 1lb	RCE	Field Book							
Compacted Materials	Density	311,312, 326, 334	RCE	1/lift/mile or 1/1500 cy ➡➡		RCE	Field Book							Unless otherwise specified or directed
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix A (Metric) Units

### ROADWAY AND BORROW EXCAVATION AND EMBANKMENTS Section 2102 and 2107

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT
SOURCE INSPECTION													
Special Backfill													
Crushed Stone (4132.02)		AS 209											
Crushed Concrete (4132.02)		209											
RAP(2303.02)													
Gravel (4132.03)		AS 209											
Granular Backfill		AS 209											
Engineering Fabric (4196)	Quality	AB 496.01											
GRADE INSPECTION													
Special & Select Backfill	Moisture	309, 310	RCE	1/lift/ 450 m	0.5 kg	RCE	Field Book						
Compaction Control													
Moisture & Density Compaction Control	Density (Proctor) Moisture	309, 310	RCE	1/soil class 1/lift/450 m	12 kg 0.5 kg	RCE	Field Book						
Compacted Materials	Density	311,312, 326, 334	RCE	1/lift/1.5 km or 1/1150 m³ ➡➡		RCE	Field Book						Unless otherwise specified or directed
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				



## Sampling and Testing Guide-Minimum Frequency

Mtls. I.M. 204  
Appendix C (US) Units

### MODIFIED SUBBASE Section 2115

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Natural Aggregate	Quality Gradation	AS 209												
Recycled Products														
Composite	Gradation	* As Per Spec.												
PCC Pavement	Gradation	* As Per Spec.												
Rap		* As Per Spec.												
GRADE INSPECTION														
Compacted Subbase	Density	* As Per Spec.	RCE			RCE	Field Book							
Dimensions	Thickness Width	337	RCE	3/2 lane mi.		RCE	Field Book							
	Cross Section (Primary)	Stringline	RCE	10/mi.		RCE	Field Book							
	Cross Section (Other)	Template	RCE	3/mi.		RCE	Field Book							
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

\* Use Current Specification for Modified Subbase



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix C (Metric) Units

### MODIFIED SUBBASE Section 2115

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT
SOURCE INSPECTION													
Natural Aggregate	Quality Gradation	AS 209											
Recycled Products													
	Gradation	* As Per Spec.											
Composite													
PCC Pavement	Gradation	* As Per Spec.											
Rap		* As Per Spec.											
GRADE INSPECTION													
Compacted Subbase	Density	*As Per Spec.	RCE			RCE	Field Book						
Dimensions	Thickness Width	337	RCE	2/2 lane km		RCE	Field Book						
	Cross Section (Primary)	Stringline	RCE	6/km		RCE	Field Book						
	Cross Section (Other)	Template	RCE	2/km		RCE	Field Book						
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

\* Use Current Specification for Modified Subbase



## Sampling and Testing Guide-Minimum Frequency

Mats. I.M. 204  
Appendix D (U.S.) Units

### GRANULAR SUBBASE Section 2111

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
<b>SOURCE INSPECTION</b>														
Natural Aggregate (4121)	Quality Gradation	AS 209												
PCC Pavement	Gradation	209												
<b>GRADE INSPECTION</b>														
Compacted Subbase (2111)	Density	By Specification	RCE				RCE	Field Book						
Dimensions	Thickness	337	RCE	3 / 2			RCE	Field Book						
	Width			lane										
				mi.										
	Cross Section (Primary)	stringline	RCE	10/ mi.			RCE	Field Book						
	Cross Section (Others)	template	RCE	3/mi			RCE	Field Book						
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification					RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor			



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix D (Metric) Units

### GRANULAR SUBBASE Section 2111

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
<b>SOURCE INSPECTION</b>													
Natural Aggregate (4121)	Quality Gradation	AS 209											
PCC Pavement	Gradation	209											
<b>GRADE INSPECTION</b>													
Compacted Subbase (2111)	Density	By Specification	RCE			RCE	Field Book						
Dimensions	Thickness	337	RCE	2/2		RCE	Field Book						
	Width		RCE	lane km									
	Cross Section (Primary)	stringline	RCE	6/km		RCE	Field Book						
	Cross Section (Others)	template	RCE	2/km		RCE	Field Book						
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification		RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

### PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING CURB & GUTTER, AND PAVED SHOULDERS Section 2122, 2201, 2213, 2301, and 2302

Matls. I.M. 204

Appendix E (U.S.) Units

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregates-Fine (4110)		AS 209					Refer to IM 527 for report number							
Aggregate-Coarse (4115)		AS 209												
Portland Cement (4101)	Quality	AS 401												
Fly Ash (4108)	Quality	AS 491.17												
GGBFS (Ground Granulated Blast Furnace Slag)	Quality	AS 491.14												
Curing Compounds (4105)	Lab-Tested													
Clear Curing Compounds (4105)		AB 405.07												
Air Entraining Admixture (4103)	Quality	AB 403												
Water Reducing Admixture (4103)	Quality	AB 403												
Retarding Admixture (4103)	Quality	AB 403												
Joint Sealer (4136.02)	Lab Tested	436.01, 436.02,436.03												
Backer Rod (4136.02)	Lab Tested	AB 436.04												
Mixing Water (4102)	Lab Tested		RCE	➡ 1/source	1 qt	CTRL							Not required for potable water from municipal supply	
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



# Sampling and Testing Guide-Minimum Frequency

## PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING CURB & GUTTER, AND PAVED SHOULDERS

Matls. I.M. 204

Appendix E (U.S.) Units

Section 2122, 2201, 2213, 2301, and 2302

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Steel Reinforcement (4151)							Refer to IM 527 for report number							
Dowels	Quality	AS 451												
Tie Bars	Quality	AS 451												
Continuous Reinforcement	Quality	AS 451												
General Use	Quality	AS 451												
PLANT INSPECTION														
Aggregates-Fine (4110/4111)	Grad *	302,306 336	CONTR	3/lot	IM 301	CONTR	Refer to IM 527 for report number	ASSUR CORR V	DME CONTR DME	1/100,000 sy 1 <sup>st</sup> day + 10% 1/QM-C project	IM 301 IM 301 IM 301	DME RCE CTRL		See Notes See I.M. 214
	Moist ➡	308,527	CONTR	1 / half day	1000 gm	CONTR								Not applicable with probe
	Sp. Gr.	307	CONTR	I.M. 527	1000 gm	CONTR								
	Quality	AS 209												
AS-Approved Source		Cert A-Type A Certification			RCE-Resident Construction Engineer/Project Engineer			ASSUR-Independent Assurance						
AB-Approved Brand		Cert B-Type B Certification			DME-District Materials Engineer			VERIF-Verification						
ASD-Approved Shop Drawing		Cert C-Type C Certification			CTRL-Central Materials Office			CORR-Correlation						
S&T-Sampling & Testing		Cert D-Type D Certification			CONTR-Contractor			MON-Monitor						

\* A system approach may be applied, at the discretion of the DME

Note 1: When Certified Plant Inspection is not provided, the Engineer is responsible for performing sampling and testing.

Note 2: When the project engineer does the acceptance gradation testing, the assurance sample is to be split with the project engineer. This split sample is for correlation purposes, and if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.

Note 3: If a third aggregate is used on a QM-C project, individual verification samples of the third aggregate must be obtained by the DME at a rate of 1/QM-C project for gradation and quality testing by CTRL.



## Sampling and Testing Guide-Minimum Frequency

### PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING

#### CURB & GUTTER, AND PAVED SHOULDERS

#### Section 2122, 2201, 2213, 2301, and 2302

Matis. I.M. 204

Appendix E (U.S.) Units

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Aggregates- Coarse (4115)	Grad *	302, 306 336	CONTR	3/lot	I.M. 301	CONTR	Refer to IM 527 for report number	ASSUR CORR V	DME CONTR DME	1/100,000 sy 1 <sup>st</sup> day + 10% 1/QM-C project	IM 301 IM 301 IM 301	DME RCE CTRL		See Notes
	Moist	308	CONTR	1 / half day	2000 gm	CONTR								1000gm may be used (IM 301)
	Sp. Gr.	307	CONTR	I.M. 527	2000 gm	CONTR								1000gm may be used (IM 301)
	Quality	AS 209						V	DME	1/ 100,000 sy	50 lb	CTRL		
Portland Cement (4101)	Quality	AS Cert D		Each Load				V	DME	1/100,000 sy	15 lb	CTRL		
	Cement Yield		CONTR	1/10,000 cy		CONTR								
Fly Ash	Quality	AS Cert D		Each Load				V	DME	1/100,000 sy	15 lb	CTRL		
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS Cert		Each Load				V	DME	1/100,000 sy	15 lb	CTRL		
Air Admixture	Quality	AB 403	DME	1/lot	1 pint	CTRL								
Water Reducer	Quality	AB 403	DME	1/lot	1 pint	CTRL								
Retarding Admixture	Quality	AB 403	DME	1/lot	1 pint	CTRL								
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

\* A - System approach may be applied at the discretion of the DME

Note 1: When Certified Plant Inspection is not provided, the Engineer is responsible for performing sampling and testing.

Note 2: When the project engineer does the acceptance gradation testing, the assurance sample is to be split with the project engineer. This split sample is for correlation purposes, and if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.

Note 3: If a third aggregate is used on a QM-C project, individual verification samples of the third aggregate must be obtained by the DME at a rate of 1/QM-C project for gradation and quality testing by CTRL.

Verification/Assurance samples not required when mix quantity is less than 2000 sq. yds.



# Sampling and Testing Guide-Minimum Frequency

## PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING CURB & GUTTER, AND PAVED SHOULDERS

Matls. I.M. 204

Appendix E (U.S.) Units

Section 2122, 2201, 2213, 2301, and 2302

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION														
Chloride Solution	Concentration	373	RCE	1/day			Refer to IM 527 for report number							
Wire Mesh		AS CERT A						V	DME	1/Project/YR	2 ft X 2 ft	CTRL		
Steel Reinforcement: Dowels	Quality	AS 451						V ➡	DME	1/District/YR	2 ft	CTRL		Steel sampling Frequency Minimum of one per District per year
Tie Bars	Quality	AS 451						V ➡	DME	1/District/YR	2 ft	CTRL		
General Use	Quality	AS 451						V ➡	DME	1/District/YR	48 in	CTRL		
Continuous Reinforcement	Quality	AS 451						V ➡	DME	1/District/YR	2 - 2 ft pcs.	CTRL		
Plastic Concrete	Air	318 327	RCE	➡ 1/1000 cy		RCE		ASSUR	DME	1/100,000 sy		DME		1/100 cy for transit mixer min 1 per day
	Grade Yield		RCE	1/1000 cy		RCE								
		Beams**	316, 327, 328	RCE	2/day			RCE						
Hardened Concrete	Thickness*➡	346, 347	CONTR	1/2000 sy	I.M. 346	RCE		ASSUR	CONTR		10%	DME		Monitor Sampling
	Smoothness	341 Cert. Test Report	CONTR		100%	CONTR		CORR	DME		10%	DME		
AS-Approved Source		Cert A-Type A Certification			RCE-Resident Construction Engineer/Project Engineer				ASSUR-Independent Assurance					
AB-Approved Brand		Cert B-Type B Certification			DME-District Materials Engineer				VERIF-Verification					
ASD-Approved Shop Drawing		Cert C-Type C Certification			CTRL-Central Materials Office				CORR-Correlation					
S&T-Sampling & Testing		Cert D-Type D Certification			CONTR-Contractor				MON-Monitor					

\* Thickness cores sent to Central lab for additional project information testing

\*\*None required when maturity is used

Verification/Assurance samples not required when mix quantity is less than 2000 sq. yds.



## Sampling and Testing Guide-Minimum Frequency

### PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING

#### CURB & GUTTER, AND PAVED SHOULDERS

#### Section 2122, 2201, 2213, 2301, and 2302

Matls. I.M. 204

Appendix E (Metric) Units

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregates-Fine (4110)		AS 209					Refer to IM 527 for report form							
Aggregate-Coarse (4115)		AS 209												
Portland Cement (4101)	Quality	AS 401												
Fly Ash (4108)	Quality	AS 491.17												
GGBFS (Ground Granulated Blast Furnace Slag)	Quality	AS 491.14												
Curing Compounds (4105)	Lab-Tested													
Clear Curing Compounds (4105)		AB 405.07												
Air Entraining Admixture (4103)	Quality	AB 403												
Water Reducing Admixture (4103)	Quality	AB 403												
Retarding Admixture (4103)	Quality	AB 403												
Joint Sealer (4136.02)	Lab Tested	436.01, 436.02,436.03												
Backer Rod (4136.02)	Lab Tested	AB 436.04												
Mixing Water (4102)	Lab Tested		RCE	1/source	1 L	CTRL							Not required for potable water from municipal supply	
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor						



## Sampling and Testing Guide-Minimum Frequency

### PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING

#### CURB & GUTTER, AND PAVED SHOULDERS

Mats. I.M. 204

Appendix E (Metric) Units

Section 2122, 2201, 2213, 2301, and 2302

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Steel Reinforcement (4151)							Refer to IM 527 for report form							
Dowels	Quality	AS 451												
Tie Bars	Quality	AS 451												
Continuous Reinforcement	Quality	AS 451												
General Use	Quality	AS 451												
PLANT INSPECTION														
Aggregates-Fine (4110/4111)	Grad *	302, 306 208	CONTR	3/lot	IM 301	CONTR	Refer to IM 527 for report form	ASSUR CORR V	DME CONTR DME	1/100,000 m² 1 <sup>st</sup> day + 10% 1/017-01000	IM 301 IM 301 IM 301	DME RCE DME		See Notes See I.M. 214
	Moist ➡	308, 527	CONTR	1 / half day	1000 gm	CONTR								Not applicable w probe
	Sp. Gr.	307	CONTR	I.M. 527	1000 gm	CONTR								
	Quality	AS 209												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor						

\* A system approach may be applied, at the discretion of the DME

Note 1: When Certified Plant Inspection is not provided, the Engineer is responsible for performing sampling and testing.

Note 2: When the project engineer does the acceptance gradation testing, the assurance sample is to be split with the project engineer. This split sample is for correlation purposes, and if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.

Note 3: If a third aggregate is used on a QM/C project, individual verification samples of the third aggregate must be obtained by the DME and are of 1/017-01000 project for gradation and quality testing by CTRL.



## Sampling and Testing Guide-Minimum Frequency

### PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING CURB & GUTTER, AND PAVED SHOULDERS Section 2122, 2201, 2213, 2301, and 2302

Matls. I.M. 204

Appendix E (Metric) Units

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS →
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Aggregates- Coarse (4115)	Grad *	302, 306 <del>336</del>	CONTR	3/lot	I.M. 301	CONTR	Refer to IM 527 for report form	ASSUR CORR <del>V</del>	DME CONTR <del>DME</del>	1/100,000 m <sup>2</sup> 1 <sup>st</sup> day + 10% <del>1/100,000 m<sup>2</sup></del>	IM 301 IM 301 <del>IM 301</del>	DME RCE <del>DME</del>		See Notes
	Moist	308	CONTR	1 / half day	1000 gm	CONTR								
	Sp. Gr.	307	CONTR	I.M. 527	1000 gm	CONTR								
	Quality	AS 209						V	DME	1/ 100,000 m <sup>2</sup>	22 kg	CTRL		
Portland Cement (4101)	Quality	AS Cert D		Each Load				V	DME	1/100,000 m <sup>2</sup>	7 kg	CTRL		
	Cement Yield		CONTR	1/7500 m <sup>3</sup>		CONTR								
Fly Ash	Quality	AS Cert D		Each Load				V	DME	1/100,000 m <sup>2</sup>	7 kg	CTRL		
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS Cert		Each Load				<del>V</del>	<del>DME</del>	<del>1/100,000 m<sup>2</sup></del>	<del>7 kg</del>	<del>CTRL</del>		
Air Admixture	Quality	AB 403	DME	1/lot	0.5 L	CTRL								
Water Reducer	Quality	AB 403	DME	1/lot	0.5 L	CTRL								
Retarding Admixture	Quality	AB 403	DME	1/lot	0.5 L	CTRL								
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

\* A - System approach may be applied at the discretion of the DME

Note 1: When Certified Plant Inspection is not provided, the Engineer is responsible for performing sampling and testing.

Note 2: When the project engineer does the acceptance gradation testing, the assurance sample is to be split with the project engineer. This split sample is for correlation purposes, and if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.

Note 3: If third aggregate is used on a QM/C project, individual verification samples of the third aggregate must be obtained by the DME at a rate of 1 QM/C project for gradation and quality testing by CTRL. Verification/Assurance samples not required when mix quantity is less than 2000 m<sup>2</sup>.



# Sampling and Testing Guide-Minimum Frequency

## PORTLAND CEMENT CONCRETE PAVEMENT, PAVEMENT WIDENING, BASE WIDENING

### CURB & GUTTER, AND PAVED SHOULDERS

**Section 2122, 2201, 2213, 2301, and 2302**

Matls. I.M. 204

Appendix E (Metric) Units

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T				ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ⇒	
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
GRADE INSPECTION															
Chloride Solution	Concentration		373	RCE	1/day			Refer to IM 527 for report form							
Wire Mesh		AS	CERT A						V	DME	1/Project/YR	0.5 m X 0.5 m	CTRL		
Steel Reinforcement: Dowels	Quality	AS	451						V ⇒	DME	1/District/YR	0.5 m	CTRL		Steel sampling Frequency Minimum of one per District per year
Tie Bars	Quality	AS	451						V ⇒	DME	1/District/YR	0.5 m	CTRL		
General Use	Quality	AS	451						V ⇒	DME	1/District/YR	1 m	CTRL		
Continuous Reinforcement	Quality	AS	451						V ⇒	DME	1/District/YR	2 - 0.5 m pcs.	CTRL		
Plastic Concrete	Air	318	327	RCE	⇒ 1/750 m³		RCE		ASSUR	DME	1/100,000 m²		DME		1/75 m³ for transit mixer minim 1 per day
	Grade Yield			RCE	1/750 m³		RCE								
	Beams**	316, 327, 328		RCE	2/day		RCE								
Hardened Concrete	Thickness*⇒	346, 347		CONTR	1/2000 m²	I.M. 346	RCE		ASSUR	CONTR		10%	DME		Monitor Sampling
	Smoothness	341 Cert. Test Report		CONTR		100%	CONTR		CORR	DME		10%	DME		
AS-Approved Source		Cert A-Type A Certification				RCE-Resident Construction Engineer/Project Engineer				ASSUR-Independent Assurance					
AB-Approved Brand		Cert B-Type B Certification				DME-District Materials Engineer				VERIF-Verification					
ASD-Approved Shop Drawing		Cert C-Type C Certification				CTRL-Central Materials Office				CORR-Correlation					
S&T-Sampling & Testing		Cert D-Type D Certification				CONTR-Contractor				MON-Monitor					

\* Thickness cores sent to Central lab for additional project information testing      \*\*None required when maturity is used  
Verification/Assurance samples not required when mix quantity is less than 2000 m².



## Sampling and Testing Guide-Minimum Frequency

Mats. I.M. 204  
Appendix F (U.S.) Units

### TYPE A & B ASPHALT CONCRETE (QMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Note 1	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregates-Coarse (4127)		AS 209												
Aggregates-Fine (4127)		AS 209												
Hydrated Lime (4126/4127)		AS 491.04												
Asphalt Cement		AS 437												
Emulsions & Cutbacks		AS 437												
Release Agent		AB 491.15												
PLANT INSPECTION														
Aggregates (2303)	Quality							V	DME	1/20,000 Ton	50 lb.	CTRL		
Combined Aggregate (4126, 4127)	Gradation		CONTR	3/lot	I.M. 301	CONTR		CORR. ASSUR	CONTR DME	1 <sup>st</sup> day + 10% 1/20,000 T.	I.M. 301	DME/RCE DME	I.M. 216 I.M. 216	
	Moisture ➡➡		CONTR	1 / half day	1000 gm	CONTR								Dryer Drum Plants Only
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

Note: Sample Frequencies based on Tons of Mix



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix F (U.S.) Units

### TYPE A & B ASPHALT CONCRETE (QMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ↔
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Notes	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Mineral Filler			DME	1/proj.	50 gm	DME	821278							
Asphalt Cement	DSR Quality	AS Cert D	CONTR	1/40 T	3 oz. Tin	DME↔		V	DME	1/20,000 T of Mix	1 qt	CTRL		log all shipments Test 1 <sup>st</sup> 3days then 1/week
Cutback	Quality Viscosity	AS 329	RCE	1/proj	1 qt	DME								log all shipments
Emulsion	Residue	AS 360	RCE	1/proj	1 qt	DME								Plastic bottle required
GRADE INSPECTION														
Uncompacted Mixture:	Lab Density	321, 325	CONTR	As per 2303	50 lb	CONTR		CORR	CONTR	1/day ↔	50 lb	DME		May be adjusted by DME as per 2303
	Lab Voids	350, 510	CONTR	As per 2303	50 lb	CONTR		CORR V	CONTR DME	1/day ↔ 1/20,000 T of Mix	50 lb 40 lb	DME CTRL		May be adjusted by DME as per 2303
Compacted Mixture	Density Thickness Voids	320, 321 337 321	CONTR↔ CONTR↔ CONTR↔	lot lot lot	7/lot 7/lot 7/lot	CONTR CONTR CONTR		CORR CORR CORR	CONTR CONTR	1 <sup>st</sup> day+10% 1 <sup>st</sup> day+10% 1 <sup>st</sup> day+10%		DME DME DME		Witness by RCE Witness by RCE Witness by RCE
	Smoothness	341	CONTR	100%	100%	CONTR		CORR	DME	10%		DME		
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Note: Verif/Assur/Corr not required under 2000 Tons of Mix.

Note: Sample Frequency based on Tons of Mix.



## Sampling and Testing Guide-Minimum Frequency

Matis. I.M. 204  
Appendix F (Metric) Units

### TYPE A & B ASPHALT CONCRETE (QMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Note 1	SAMPLE SIZE	TEST BY	REPORT	
<b>SOURCE INSPECTION</b>														
Aggregates-Coarse (4127)		AS 209												
Aggregates-Fine (4127)		AS 209												
Hydrated Lime (4126/4127)		AS 491.04												
Asphalt Cement		AS 437												
Emulsions & Cutbacks		AS 437												
Release Agent		AB 491.15												
<b>PLANT INSPECTION</b>														
Aggregates (2303)	Quality							V	DME	1/20,000 Mg	22 kg	CTRL		
Combined Aggregate (4126, 4127)	Gradation		CONTR	3/lot	I.M. 301	CONTR		CORR. ASSUR	CONTR DME	1 <sup>st</sup> day + 10% 1/20,000 Mg	I.M. 301	DME/RCE DME	I.M. 216 I.M. 216	
	Moisture ➡		CONTR	1 / half day	1000 gm	CONTR								Dryer Drum Plants Only
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification		RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor						

Note: Sample Frequencies based on Mg of Mix



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix F (Metric) Units

## TYPE A & B ASPHALT CONCRETE (QMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ⇒⇒
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Notes	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Mineral Filler			DME	1/proj.	50 gm	DME	821278							
Asphalt Cement	DSR Quality	AS Cert D	CONTR	1/40 Mg	85 gm Tin	DME⇒⇒		V	DME	1/20,000 Mg of Mix	1 L	CTRL		log all shipments Test 1 <sup>st</sup> 3days then 1/week
Cutback	Quality Viscosity	AS 329	RCE	1/proj	1 L	DME								log all shipments
Emulsion	Residue	AS 360	RCE	1/proj	1 L	DME								Plastic bottle required
GRADE INSPECTION														
Uncompacted Mixture:	Lab Density	321, 325	CONTR	As per 2303	22 kg	CONTR		CORR	CONTR	1/day ⇒⇒	22 kg	DME		May be adjusted by DME as per 2303
	Lab Voids	350, 510	CONTR	As per 2303	22 kg	CONTR		CORR V	CONTR DME	1/day ⇒⇒ 1/20,000 Mg of Mix	22 kg 18 kg	DME CTRL		May be adjusted by DME as per 2303
Compacted Mixture	Density Thickness Voids	320, 321 337 321	CONTR⇒⇒ CONTR⇒⇒ CONTR⇒⇒	lot lot lot	7/lot 7/lot 7/lot	CONTR CONTR CONTR		CORR CORR CORR	CONTR CONTR	1 <sup>st</sup> day+10% 1 <sup>st</sup> day+10% 1 <sup>st</sup> day+10%		DME DME DME		Witness by RCE Witness by RCE Witness by RCE
	Smoothness	341	CONTR	100%	100%	CONTR		CORR	DME	10%		DME		
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Note: Verif/Assur/Corr not required under 2000 Mg of Mix.

Note: Sample Frequency based on Mg of Mix.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix G (U.S.) Units

### TYPE A & B ASPHALT CONCRETE (Non QMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Note 1	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregates-Coarse (4127)		AS 209												
Aggregates-Fine (4127)		AS 209												
Hydrated Lime (4126/4127)		AS 491.04												
Asphalt Cement		AS 437												
Emulsions & Cutbacks		AS 437												
Release Agent		AB 491.15												
PLANT INSPECTION *														
Aggregates (2303)	Quality							V	DME	1/20,000 Ton of Mix	50 lb.	CTRL		
Combined Aggregate (4126, 4127)	Gradation		RCE	3/lot	I.M. 301	RCE		ASSUR	DME	1/20,000 Ton of Mix	I.M. 301	DME	I.M. 216	
	Moisture ➡➡		RCE	1/ half day	1000 gm	RCE								Dryer Drum Plants Only
AS-Approved Source		Cert A-Type A Certification				RCE-Resident Construction Engineer/Project Engineer				ASSUR-Independent Assurance				
AB-Approved Brand		Cert B-Type B Certification				DME-District Materials Engineer				VERIF-Verification				
ASD-Approved Shop Drawing		Cert C-Type C Certification				CTRL-Central Materials Office				CORR-Correlation				
S&T-Sampling & Testing		Cert D-Type D Certification				CONTR-Contractor				MON-Monitor				

\* For certified Plant Insp. on non-QMA projects. See QMA table for S & T guide.

Note 1: Sample frequency based on Tons of Mix.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix G (U.S.) Units

### TYPE A & B ASPHALT CONCRETE ( NonQMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Mineral Filler			DME	1/proj.	50 gm	DME	821278							
Asphalt Cement	DSR Quality	AS Cert D	RCE	1/40 T	3 oz. Tin	DME➡➡		V	DME	1/20,000 Tons of Mix	1 qt	CTRL		log all shipments Test 1 <sup>st</sup> 3days/ then 1/week
Cutback	Quality Viscosity	AS 329	RCE➡➡	1/proj	1 qt	DME								log all shipments
Emulsion	Residue	AS 360	RCE	1/proj	1 qt ➡➡	DME								Plastic bottle required
GRADE INSPECTION														
Uncompacted Mixture	Lab Density	321, 325	RCE	3/Lot ➡➡	50 lb	DME								Tests 1/Lot
	Lab Voids	350, 510	RCE	As per 2303	50 lb	DME		V	DME	1/20,000 Ton of Mix	40 lb	CTRL		
Compacted Mixture	Density Thickness	320, 321 337	CONTR* CONTR*	Lot Lot	7/Lot 7/Lot	RCE RCE		ASSUR ASSUR	CONTR CONTR	1 <sup>st</sup> day + 10% 1 <sup>st</sup> day + 10%		DME		
	Voids	321	CONTR*	Lot	7/Lot	RCE								
	Smoothness	341	CONTR	100%	100%	CONTR		CORR	DME	10%		DME		
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

\* Witness by RCE

Note: Verif/Assur/Corr not required under 2000 Tons of Mix.



## Sampling and Testing Guide-Minimum Frequency

Matis. I.M. 204  
Appendix G (Metric) Units

### TYPE A & B ASPHALT CONCRETE (Non QMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ. Note 1	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregates-Coarse (4127)		AS 209												
Aggregates-Fine (4127)		AS 209												
Hydrated Lime (4126/4127)		AS 491.04												
Asphalt Cement		AS 437												
Emulsions & Cutbacks		AS 437												
Release Agent		AB 491.15												
PLANT INSPECTION *														
Aggregates (2303)	Quality							V	DME	1/20,000 Mg of Mix	22 kg	CTRL		
Combined Aggregate (4126, 4127)	Gradation		RCE	3/lot	I.M. 301	RCE		ASSUR	DME	1/20,000 Mg of Mix	I.M. 301	DME	I.M. 216	
	Moisture ➡➡		RCE	1/ half day	1000 gm	RCE								Dryer Drum Plants Only
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

\* For certified Plant Insp. on non-QMA projects. See QMA table for S & T guide.

Note 1: Sample frequency based on Mg of Mix.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix G (Metric) Units

### TYPE A & B ASPHALT CONCRETE ( NonQMA) Section 2303, 2213, and 2114

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Mineral Filler			DME	1/proj.	50 gm	DME	821278							
Asphalt Cement	DSR Quality	AS Cert D	RCE	1/40 Mg	85 gm Tin	DME➡➡		V	DME	1/20,000 Mg of Mix	1 L	CTRL		log all shipments Test 1 <sup>st</sup> 3days then 1/week
Cutback	Quality Viscosity	AS 329	RCE➡➡	1/proj	1 L	DME								log all shipments
Emulsion	Residue	AS 360	RCE	1/proj	1 L ➡➡	DME								Plastic bottle required
GRADE INSPECTION														
Uncompacted Mixture	Lab Density	321, 325	RCE	3/Lot ➡➡	22 kg	DME								Tests 1/Lot
	Lab Voids	350, 510	RCE	As per 2303	22 kg	DME		V	DME	1/20,000 Mg of Mix	18 kg	CTRL		
Compacted Mixture	Density Thickness	320, 321 337	CONTR* CONTR*	Lot Lot	7/Lot 7/Lot	RCE RCE		ASSUR ASSUR	CONTR CONTR	1 <sup>st</sup> day + 10% 1 <sup>st</sup> day + 10%		DME		
	Voids	321	CONTR*	Lot	7/Lot	RCE								
	Smoothness	341	CONTR	100%	100%	CONTR		CORR	DME	10%		DME		
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

\*Witness by RCE

Note: Verif/Assur/Corr not required under 2000 Mg of Mix.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
SOURCE INSPECTION													
Aggregate-Fine (4110)		AS 209											
Aggregate-Coarse (4115)		AS 209											
Granular Backfill (4133)		AS 209											
Portland Cement (4101)	Quality	AS 401											
Fly Ash (4108)	Quality	AS 491.17											
Mixing Water (4102)	Quality		RCE	➡➡ 1/project	1 L	CTRL	731						Not required for potable water from Municipal Supply
GGBFS (Ground Granulated Blast Furnace Slag)	Quality	AS 491.14											
Air Entraining Admixture	Quality	AB 403											
Retarding Admixture	Quality	AB 403											
Water reducing Admixture	Quality	AB 403											
Curing Compound (4105)	Lab Tested	AB 405 ➡➡	DME	1/lot	1 L	CTRL							Bridge Barrier Rails AASHTO, M148, Cert. by Manufacturer
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance samples is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Pre-formed Joint Sealer (4136)	Lab-Tested	AB <u>436</u>												
Reinforcing Steel Bars (4151)	Quality	AS <u>451</u>												
Steel Pile (4167)	Quality	<u>467</u>												
Concrete Pile (4166)	Quality	AS <u>570</u>												
Timber Pile (4165)	Quality	➡➡ <u>462</u>		Each Shipment										Rpt. or Cert by Independent Insp. Agency
Timber & (4162) Lumber (4163)		➡➡ <u>462</u>		Each Shipment										Rpt. or Cert by Independent Insp. Agency
Concrete Anchors	Quality	AB <u>453.09</u>												
Epoxy Grout	Quality	AB <u>491.11</u>												
Concrete Sealer	Quality	AB <u>491.12</u>												
Subdrain Pipe (4143)	Quality	AS <u>443</u> , 448												
Neoprene Bearing Pads (4195)		AS <u>495.03</u>												
Bronze Bearing Plates (4190.03)		ASD/Cert A												
AS-Approved Source		Cert A-Type A Certification			RCE-Resident Construction Engineer/Project Engineer				ASSUR-Independent Assurance					
AB-Approved Brand		Cert B-Type B Certification			DME-District Materials Engineer				VERIF-Verification					
ASD-Approved Shop Drawing		Cert C-Type C Certification			CTRL-Central Materials Office				CORR-Correlation					
S&T-Sampling & Testing		Cert D-Type D Certification			CONTR-Contractor				MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance samples is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
SOURCE INSPECTION													
Steel Masonry Plate (4152)		ASDrawing/Cert A											
Precast Units (2407)	Quality	AS 570											
Anchor Bolts (lighting, signing, handrail) (4153)	Lab Tested	ASD											
Structural Steel (4152)	Quality	➡➡ Cert A											Monitor Sample According to plans or other instructions
Aluminum Bridge Rail & Anchor Assembly		ASD Cert B											
Conduit (Electrical) (4185.1)	Lab Tested		DME	1/ size	2' with coupling	CTRL							
Bentonite		AS Cert D											
Flowable Mortar	Lab Tested ➡➡	Approved Trial Mix 525, 375											Tested by DME
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor			

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and, if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPL E SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPL E SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Aggregate- Fine (4110)	Gradation	302, 306 <del>336</del>	CONTR	3/lot	IM 301	CONTR	830211	ASSUR CORR	DME CONTR	1/1000 cy➡ 1 <sup>st</sup> day +10%	IM 301 IM 301	DME RCE		System Approach Applicable
	Moisture	➡ 308, 528	CONTR	1/lot	1000 gm	CONTR	830211							See IM 528 if Moisture Probe is used
	Sp. Gr.	307	CONTR	IM 528	1000 gm	CONTR	830211							
	Quality	AS 209												
Aggregate- Coarse (4115)	Gradation	302, 306 <del>336</del>	CONTR	3/lot	IM 301	CONTR	830211	ASSUR CORR	DME CONTR	➡ 1/1000 CY 1 <sup>st</sup> day+10%	IM 301 IM 301	DME RCE		System Approach Applicable
	Moisture	308, 528	CONTR	1/lot	2000g m	CONTR	830211							
	Sp. Gr.	307	CONTR	IM 528	2000g m	CONTR	830211							
	Quality	AS 209						V	DME	1/1000 cy	50 lb	CTRL		
Portland Cement	w/c ratio	528	CONTR	1/pour		CONTR	830211							
	Quality	AS Cert D					830211	V	DME	1/1000 cy	15 lb	CTRL		
AS-Approved Source		Cert A-Type A Certification			RCE-Resident Construction Engineer/Project Engineer					ASSUR-Independent Assurance				
AB-Approved Brand		Cert B-Type B Certification			DME-District Materials Engineer					VERIF-Verification				
ASD-Approved Shop Drawing		Cert C-Type C Certification			CTRL-Central Materials Office					CORR-Correlation				
S&T-Sampling & Testing		Cert D-Type D Certification			CONTR-Contractor					MON-Monitor				

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Mats. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS	
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
PLANT INSPECTION															
Fly Ash	Quality	AS	Cert		Ea Load			830211							
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS	Cert		Ea Load			830211							
Air Entraing Admixture (4103)		AB	403	RCE	1/lot↔	0.5 L	CTRL								Sample lots not previously reported or as required by DME
Retarding Admixture		AB	403	RCE	1/lot↔	0.5 L	CTRL								
Water Reducing Admixture (4103)		AB	403	RCE	1/lot↔	0.5 L	CTRL								
GRADE INSPECTION															
Plastic Concrete	Air Content		316, 327	RCE	1/30 cy↔		RCE	830211	ASSUR	DME	1/1000 cy		DME		DME may adjust
	Slump		317, 327	RCE	1/30 cy↔		RCE	830211	ASSUR	DME	1/1000 cy		Witness Only		DME may adjust
	Beams		316, 327, 328	RCE	2/placement↔		RCE	830211							As per 2403.18 & 2403.18
	Cylinders									DME	↔ 3/project		DME		Primary Projects Only (Information only)
AS-Approved Source		Cert A-Type A Certification				RCE-Resident Construction Engineer				ASSUR-Independent Assurance					
AB-Approved Brand		Cert B-Type B Certification				DME-District Materials Engineer				VERIF-Verification					
ASD-Approved Shop Drawing		Cert C-Type C Certification				CTRL-Central Materials Office				CORR-Correlation					
S&T-Sampling & Testing		Cert D-Type D Certification				CONTR-Contractor				MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Mtls. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION															
Reinforcing Steel (4151)	Quality	AS	Cert A		Each Shipment			Field Book	V	DME	IM 451	6 ft	CTRL		
Reinforcing Steel Epoxy Coated (4151)	Quality	AS	Cert A		Each Shipment			Field Book	V	DME	1 of largest bar in deck	6 ft	CTRL	Will be acceptance tested for coating	
Steel Pile (4167)	Quality	AS	Cert A		Each Heat			Field Book		DME	IM 467		CTRL	Monitor by CTRL Materials	
Timber Pile (4165)	Quality	Cert D	462						MON					Test report by Independent Lab	
Anchor Bolts (lighting, signing, handrail)	Lab Tested	ASD		DME	1/project	1 bolt w/nut & washer	CTRL							Sample only if not source inspected	
Steel Masonry Plates (4152)		ASD	Cert A		Each Shipment			Field Book						Approved by Materials Department	
Bronze Bearing Plates (4190.03)	Lab Tested			DME	1/project	1 only	CTRL							Sample only if not source inspected	
Neoprene Bearing Pads (4199)		AS	495.03		Each Shipment			820905							
Alum. Bridge Rail & Anchor Assembly		ASD			Each Shipment			Field Book						Approved By Materials Dept.	
Drains (Std Steel Pipe)(as per plan)	Dimensions Galvanized	ASD	Visual 332	DME	1/project		DME	Test Report							
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance samples is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (U.S.) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION														
Timber (4162) & Lumber (4163)	Quality	Cert D 4162		Each Shipment										
Subdrain Pipe (4143)	Quality	AS Cert D 443, 448		Each Shipment										
Flowable Mortar (2506) ➡➡	Flow Test	375	RCE	As needed for Project Control		RCE	830211							Mix Design approval by DME
Bentonite	Flow Test	Visual 375				RCE								
Smoothness (2317)	Profilometer	Cert. Test Report 341	CONTR	Each Project	Each Wheelpath	CONTR	821301	CORR	DME	10%				
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 50 cu. yd.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregate-Fine (4110)		AS 209												
Aggregate-Coarse (4115)		AS 209												
Granular Backfill (4133)		AS 209												
Portland Cement (4101)	Quality	AS 401												
Fly Ash (4108)	Quality	AS 491.17												
Mixing Water (4102)	Quality		RCE	➡ 1/project	1 L	CTRL	731							Not required for potable water from Municipal Supply
GGBFS (Ground Granulated Blast Furnace Slag)	Quality	AS 491.14												
Air Entraining Admixture	Quality	AB 403												
Retarding Admixture	Quality	AB 403												
Water reducing Admixture	Quality	AB 403												
Curing Compound (4105)	Lab Tested	AB 405 ➡	DME	1/lot	1 L	CTRL								Bridge Barrier Rails AASHTO, M148, Cert. by Manufacturer
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 40 m<sup>3</sup>

Note: When the Project Engineer does the acceptance gradation testing, the assurance samples is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
SOURCE INSPECTION														
Pre-formed Joint Sealer (4136)	Lab- Tested	AB <u>436</u>												
Reinforcing Steel Bars (4151)	Quality	AS <u>451</u>												
Steel Pile (4167)	Quality	<u>467</u>												
Concrete Pile (4166)	Quality	AS <u>570</u>												
Timber Pile (4165)	Quality	➡➡ <u>462</u>		Each Shipment										Rpt. or Cert by Independent Insp. Agency
Timber & (4162) Lumber (4163)		➡➡ <u>462</u>		Each Shipment										Rpt. or Cert by Independent Insp. Agency
Concrete Anchors	Quality	AB <u>453.09</u>												
Epoxy Grout	Quality	AB <u>491.11</u>												
Concrete Sealer	Quality	AB <u>491.12</u>												
Subdrain Pipe (4143)	Quality	AS <u>443</u> , <u>448</u>												
Neoprene Bearing Pads (4195)		AS <u>495.03</u>												
Bronze Bearing Plates (4190.03)		ASD/Cert A												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 40 m<sup>3</sup>.

Note: When the Project Engineer does the acceptance gradation testing, the assurance samples is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Steel Masonry Plate (4152)		ASDrawing/Cert A												
Precast Units (2407)	Quality	AS 570												
Anchor Bolts (lighting, signing, handrail) (4153)	Lab Tested	ASD												
Structural Steel (4152)	Quality	➡➡ Cert A												Monitor Sample According to plans or other instructions
Aluminum Bridge Rail & Anchor Assembly		ASD Cert B												
Conduit (Electrical) (4185.1)	Lab Tested		DME	1/ size	0.5 m with coupling	CTRL								
Bentonite		AS Cert D												
Flowable Mortar	Lab Tested ➡➡	Approved Trial Mix 525, 375												Tested by DME
AS-Approved Source		Cert A-Type A Certification				RCE-Resident Construction Engineer/Project Engineer				ASSUR-Independent Assurance				
AB-Approved Brand		Cert B-Type B Certification				DME-District Materials Engineer				VERIF-Verification				
ASD-Approved Shop Drawing		Cert C-Type C Certification				CTRL-Central Materials Office				CORR-Correlation				
S&T-Sampling & Testing		Cert D-Type D Certification				CONTR-Contractor				MON-Monitor				

Verification/Assurance samples not required when mix quantity is less than 40 m³.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and, if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Mtls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPL E SIZE	TEST BY		REPORT
PLANT INSPECTION														
Aggregate- Fine (4110)	Gradation	302, 306 <del>306</del>	CONTR	3/lot	IM 301	CONTR	830211	ASSUR CORR	DME CONTR	1/750 m³➡➡ 1 <sup>st</sup> day +10%	IM 301	DME RCE		System Approach Applicable
	Moisture	➡➡ 308, 528	CONTR	1/lot	1000 gm	CONTR	830211							See IM 528 if Moisture Probe is used
	Sp. Gr.	307	CONTR	IM 528	1000 gm	CONTR	830211							
	Quality	AS 209												
Aggregate- Coarse (4115)	Gradation	302, 306 <del>306</del>	CONTR	3/lot	IM 301	CONTR	830211	ASSUR CORR	DME CONTR	➡➡ 1/750 m³ 1 <sup>st</sup> day+10%	IM 301	DME RCE		System Approach Applicable
	Moisture	308, 528	CONTR	1/lot	2000gm	CONTR	830211							
	Sp. Gr.	307	CONTR	IM 528	2000gm	CONTR	830211							
	Quality	AS 209						V	DME	1/750 m³	22 kg	CTRL		
Portland Cement	w/c ratio	528	CONTR	1/pour		CONTR	830211							
	Quality	AS Cert D					830211	V	DME	1/750 m³	7 kg	CTRL		
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 40 m³.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION															
Fly Ash	Quality	AS	Cert		Ea Load			830211							
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS	Cert		Ea Load			830211							
Air Entraing Admixture (4103)		AB	<u>403</u>	RCE	1/lot➡➡	0.5 L	CTRL							Sample lots not previously reported or as required by DME	
Retarding Admixture		AB	<u>403</u>	RCE	1/lot➡➡	0.5 L	CTRL								
Water Reducing Admixture (4103)		AB	<u>403</u>	RCE	1/lot➡➡	0.5 L	CTRL								
GRADE INSPECTION															
Plastic Concrete	Air Content		<u>316, 327</u>	RCE	1/25 m³➡➡		RCE	830211	ASSUR	DME	1/750 m³		DME		DME may adjust
	Slump		<u>317, 327</u>	RCE	1/25 m³ ➡➡		RCE	830211	ASSUR	DME	1/750m³		Witness Only		DME may adjust
	Beams		<u>316, 327, 328</u>	RCE	2/placement ➡➡		RCE	830211							As per <u>2403.18</u> & <u>2403.19</u>
	Cylinders									DME	➡➡ 3/project		<del>DME</del>		Primary Projects Only (Information only)
AS-Approved Source		Cert A-Type A Certification				RCE-Resident Construction Engineer				ASSUR-Independent Assurance					
AB-Approved Brand		Cert B-Type B Certification				DME-District Materials Engineer				VERIF-Verification					
ASD-Approved Shop Drawing		Cert C-Type C Certification				CTRL-Central Materials Office				CORR-Correlation					
S&T-Sampling & Testing		Cert D-Type D Certification				CONTR-Contractor				MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 40 m³.

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Mtls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION															
Reinforcing Steel (4151)	Quality	AS	Cert A		Each Shipment			Field Book	V	DME	IM 451	2 m	CTRL		
Reinforcing Steel Epoxy Coated (4151)	Quality	AS	Cert A		Each Shipment			Field Book	V ➡➡	DME	1 of largest bar in deck	2 m	CTRL	Will be acceptance tested for coating	
Steel Pile (4167)	Quality	AS	Cert A		Each Heat			Field Book		DME	IM 467		CTRL	Monitor by CTRL Materials	
Timber Pile (4165)	Quality		Cert D 462						MON					Test report by Independent Lab	
Anchor Bolts (lighting, signing, handrail)	Lab Tested	ASD		DME	➡➡ 1/project	1 bolt w/nut & washer	CTRL							Sample only if not source inspected	
Steel Masonry Plates (4152)		ASD	Cert A		Each Shipment			Field Book						Approved by Materials Department	
Bronze Bearing Plates (4190.03)	Lab Tested			DME	➡➡ 1/project	1 only	CTRL							Sample only if not source inspected	
Neoprene Bearing Pads (4199)		AS	495.03		Each Shipment			820905							
Alum. Bridge Rail & Anchor Assembly		ASD			Each Shipment			Field Book						Approved By Materials Dept.	
Drains (Std Steel Pipe)(as per plan)	Dimensions Galvanized	ASD	Visual 332	DME	1/project		DME	Test Report							
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Verification/Assurance samples not required when mix quantity is less than 40 m<sup>3</sup>

Note: When the Project Engineer does the acceptance gradation testing, the assurance samples is to be split with the Project Engineer. This split sample is for correlation purposes and , if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Mtls. I.M. 204  
Appendix H (Metric) Units

### STRUCTURAL CONCRETE, REINFORCEMENT, FOUNDATIONS & SUBSTRUCTURES, CONCRETE STRUCTURES, CONCRETE FLOORS, AND CONCRETE BOX, ARCH AND CIRCULAR CULVERTS Sections 2403, 2404, 2405, 2406, 2412, & 2415

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION														
Timber (4162) & Lumber (4163)	Quality	Cert D 4162		Each Shipment										
Subdrain Pipe (4143)	Quality	AS Cert D 443, 448		Each Shipment										
Flowable Mortar (2506) ➡➡	Flow Test	375	RCE	As needed for Project Control		RCE	830211							Mix Design approval by DME
Bentonite	Flow Test	Visual 375				RCE								
Smoothness (2317)	Profilometer	Cert. Test Report 341	CONTR	Each Project	Each Wheelpath	CONTR	821301	CORR	DME	10%				
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

Verification/Assurance samples not required when mix quantity is less than 40 m<sup>3</sup>

Note: When the Project Engineer does the acceptance gradation testing, the assurance sample is to be split with the Project Engineer. This split sample is for correlation purposes and, if it is not a routine lot sample, should not be used for determining specification compliance of a lot. However, any non-compliant test result is to be resolved.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix I (U.S.) Units

### SOIL AGGREGATE SUBBASE Section 2110

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Granular Surfacing Material (4120)		AS 209												
GRADE INSPECTION														
Mixed Materials (2110)	Density➡➡ (Proctor)	I.M. 309	RCE	2/ mile (min 2/project)	5000 gm	RCE	Field Book							Change of Soil type requires additional Proctors
Uncompacted Mixture	Pulverization Moisture	2" Sieve Visual	RCE	2/2 lane mile		RCE	Field Book							
Compacted Mixture (2110)	Density Thickness Width	311, 312, 334 337	RCE	2/2 lane mile		RCE	Field Book							
Finished Subbase	Cross Section	Stringline ➡➡	RCE	10/ mi		RCE	Field Book							Template for secondary park and institutional roads
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix I (Metric) Units

### SOIL AGGREGATE SUBBASE Section 2110

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
<b>SOURCE INSPECTION</b>														
Granular Surfacing Material (4120)		AS 209												
<b>GRADE INSPECTION</b>														
Mixed Materials (2110)	Density➡➡ (Proctor)	I.M. 309	RCE	2/ km (min 2/project)	5000 gm	RCE	Field Book							Change of Soil type requires additional Proctors
Uncompacted Mixture	Pulverization Moisture	50.8 mm Sieve Visual	RCE	2/2 lane km		RCE	Field Book							
Compacted Mixture (2110)	Density Thickness Width	311, 312, 334 337	RCE	2/2 lane km		RCE	Field Book							
Finished Subbase	Cross Section	Stringline ➡➡	RCE	6/km		RCE	Field Book							Template for secondary park and institutional roads
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix K (U.S.) Units

### COLD-IN-PLACE ASPHALT CEMENT CONCRETE RECYCLING(NEW) Section 2318

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Emulsion (Rej. Agent) (2318.02)	Quality	AS 437												
GRADE INSPECTION														
RAP (2318.02)	Max Size		RCE	1 <sup>st</sup> day + 1/ week	10 lb	RCE								
Emulsion (Rej. Agent)	Quality Residue	Cert D 360	RCE	1/10,000 gal.	1 qt ➡➡	DME								Must use plastic bottle
Uncompacted Mixture (2318.04)	Moisture Density	504 504	RCE RCE	1/lot 1/lot	30 lb ➡➡ 30 lb	DME DME								Sealed Container
Compacted Mixture (2318.04)	Moisture * Density	504 504	CONTR CONTR	7/day 7/day		CONTR CONTR➡➡								Witnessed by RCE
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

\* See I.M. 504 for Day 1 moisture correction factor.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix K (Metric) Units

### COLD-IN-PLACE ASPHALT CEMENT CONCRETE RECYCLING(NEW) Section 2318

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT
SOURCE INSPECTION													
Emulsion (Rej. Agent) (2318.02)	Quality	AS 437											
GRADE INSPECTION													
RAP (2318.02)	Max Size		RCE	1 <sup>st</sup> day + 1/ week	5 kg	RCE							
Emulsion (Rej. Agent)	Quality Residue	Cert D 360	RCE	1/38,000 L	1 L ➡➡	DME							Must use plastic bottle
Uncompacted Mixture (2318.04)	Moisture Density	504 504	RCE RCE	1/lot 1/lot	14 kg ➡➡ 14 kg	DME DME							Sealed Container
Compacted Mixture (2318.04)	Moisture Density *	504 504	CONTR CONTR	7/day 7/day		CONTR CONTR➡➡							Witnessed by RCE
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

\* See I.M. 504 for Day 1 moisture correction factor.



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix L (U.S.) Units

## GRANULAR SURFACING/DRIVEWAY SURFACING Section 2312 & 2315

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
<b>SOURCE INSPECTION</b>														
Class C Gravel (4120.03)	Gradation Quality	AS 209												
Class A Crushed Stone (4120.04)	Gradation Quality	AS 209												
Class B Crushed Stone (4120.05)	Gradation Quality	AS 209												
Class D Crushed Stone (4120.06)	Gradation Quality	AS 209												
Aggregate for Type B, AC or cold laid Bituminous Concrete (for driveways only)	Gradation Quality	AS 209												
Crushed Stone Base (for driveways only) (4122)	Gradation Quality	AS 209												
<b>GRADE INSPECTION</b>														
Dimensions	Thickness Width Cross Slope		RCE	3/ mi.			Field Book							
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification		RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor						



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix L (Metric) Units

## GRANULAR SURFACING/DRIVEWAY SURFACING Section 2312 & 2315

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
<b>SOURCE INSPECTION</b>														
Class C Gravel (4120.03)	Gradation Quality	AS 209												
Class A Crushed Stone (4120.04)	Gradation Quality	AS 209												
Class B Crushed Stone (4120.05)	Gradation Quality	AS 209												
Class D Crushed Stone (4120.06)	Gradation Quality	AS 209												
Aggregate for Type B, AC or cold laid Bituminous Concrete (for driveways only)	Gradation Quality	AS 209												
Crushed Stone Base (for driveways only) (4122)	Gradation Quality	AS 209												
<b>GRADE INSPECTION</b>														
Dimensions	Thickness Width Cross Slope		RCE	2/km			Field Book							
AS-Approved Source		Cert A-Type A Certification	RCE-Resident Construction Engineer/Project Engineer					ASSUR-Independent Assurance						
AB-Approved Brand		Cert B-Type B Certification	DME-District Materials Engineer					VERIF-Verification						
ASD-Approved Shop Drawing		Cert C-Type C Certification	CTRL-Central Materials Office					CORR-Correlation						
S&T-Sampling & Testing		Cert D-Type D Certification	CONTR-Contractor					MON-Monitor						



## Sampling and Testing Guide-Minimum Frequency

Matts. I.M. 204

Appendix M (U.S.) Units

### CONCRETE BRIDGE FLOOR REPAIR & OVERLAY AND SURFACING

#### Section 2413

April 25, 2001

Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
SOURCE INSPECTION													
Aggregates-Fine (4110)		AS 209											
Aggregates-Coarse (4115)		AS 209											
Portland Cement (4101)	Quality	AS 401											
Mixing Water (4102)	Quality	Lab Tested	RCE	➡➡ 1/source	1 qt.	CTRL							Not needed for potable Municipal Water
Air Entraining Admixture (4103)	Quality	AB 403											
Water Reducing Admixture (4103)	Quality	AB 403											
Retarding Admixture (4103)		AS 403											
Curing Compound (4105)	Lab Tested	405	DME 1/lot	1/lot ➡➡	1 pt	CTRL							Sample lots not previously reported
PLANT INSPECTION													
Aggregate-Fine (4110)		AS CERT											
Aggregate-Coarse (4115)	Quality	AS CERT						✓	DME	1/project ➡➡	50 lb	CTRL	DME may adjust frequency
Portland Cement (4101)	Quality	AS CERT						✓	DME	1/project	15 lb	CTRL	
Air Entraining Admixture (4103)		AB 403	RCE	Each ➡➡ Lot	1 pt	CTRL							Sample if not previously reported
Water Reducing Admixture (4103)		AB 403	RCE	Each ➡➡ Lot	1 pt	CTRL							Sample if not previously reported
Retarding Admixture (4103)		AB 403	RCE	Each ➡➡ Lot	1 pt	CTRL							Sample if not previously reported
Latex Emulsion		Certification		Each Lot									
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204

Appendix M (U.S.) Units

## CONCRETE BRIDGE FLOOR REPAIR & OVERLAY AND SURFACING

### Section 2413

April 25, 2001

Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION														
Plastic Concrete (2413)	Air	318, 327	RCE	1/100 sy		RCE	830211	ASSUR	DME	1/project		DME		
	Slump	317, 327	RCE	1/100 sy		RCE	830211	ASSUR	DME	1/project		Witness Only		
	Density	358	RCE	6/bridge		RCE	1297							Minimum of 1 per placement and witness by DME
	Thickness		RCE	3/50 sy		RCE	Field Book							
	Cylinders								DME	3/project		DME		Primary Projects only (Information Only)
Concrete Sealer (2413.09)	Quality	AB 491.12												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				



## Sampling and Testing Guide-Minimum Frequency

Matis. I.M. 204

### CONCRETE BRIDGE FLOOR REPAIR & OVERLAY AND SURFACING

April 25, 2001

Appendix M (Metric) Units

#### Section 2413

Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
SOURCE INSPECTION													
Aggregates-Fine (4110)		AS 209											
Aggregates-Coarse (4115)		AS 209											
Portland Cement (4101)	Quality	AS 401											
Mixing Water (4102)	Quality	Lab Tested	RCE	➡➡ 1/source	1 L	CTRL							Not needed for potable Municipal Water
Air Entraining Admixture (4103)	Quality	AB 403											
Water Reducing Admixture (4103)	Quality	AB 403											
Retarding Admixture (4103)		AS 403											
Curing Compound (4105)	Lab Tested	405	DME 1/lot	1/lot ➡➡	0.5 L	CTRL							Sample lots not previously reported
PLANT INSPECTION													
Aggregate-Fine (4110)		AS CERT											
Aggregate-Coarse (4115)	Quality	AS CERT						DME	1/project ➡➡	22 kg	CTRL		DME may adjust frequency
Portland Cement (4101)	Quality	AS CERT						DME	1/project ➡➡	22 kg	CTRL		
Air Entraining Admixture (4103)		AB 403	RCE	Each ➡➡ Lot	0.5 L	CTRL							Sample if not previously reported
Water Reducing Admixture (4103)		AB 403	RCE	Each ➡➡ Lot	0.5 L	CTRL							Sample if not previously reported
Retarding Admixture (4103)		AB 403	RCE	Each ➡➡ Lot	0.5 L	CTRL							Sample if not previously reported
Latex Emulsion		Certification		Each Lot									
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				



# Sampling and Testing Guide-Minimum Frequency

Matis. I.M. 204

## CONCRETE BRIDGE FLOOR REPAIR & OVERLAY AND SURFACING

April 25, 2001

Appendix M (Metric) Units

### Section 2413

Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IIMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
GRADE INSPECTION														
Plastic Concrete (2413)	Air	318, 327	RCE	1/100 m <sup>2</sup>		RCE	830211	ASSUR	DME	1/project		DME		
	Slump	317, 327	RCE	1/100 m <sup>2</sup>		RCE	830211	ASSUR	DME	1/project		Witness Only		
	Density	358	RCE	➡➡ 6/bridge		RCE	1297							Minimum of 1 per placement and witness by RCE
	Thickness		RCE	3/50 m <sup>2</sup>		RCE	Field Book							
	Cylinders								DME	3/project		DME		Primary Projects only (Information Only)
Concrete Sealer (2413.09)	Quality	AB 491.12												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix P (U.S.) Units

## BITUMINOUS SEAL COAT Section 2307

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
SOURCE INSPECTION													
Aggregates (4125)	Quality	AS 209											
Emulsions/Cutbacks	Quality	AS											
Emulsion & Aggregate	Compatibility	349	DME	1/ source	1 qt & 10lb	DME/ CTRL							
GRADE INSPECTION													
Aggregate	Quality Gradation	Cert D 301						V	DME	1/proj.	50 lb	CTRL	
Emulsion (1)	Quality Residue Compatibility	Cert D 323, 360 349	RCE ➡➡ RCE	1/20,000 gal 1 <sup>st</sup> Day + 1/ week	1 qt 1 qt & 10 lb	DME DME		V	DME	1/proj.	1 gal.	CTRL	Log all shipments Plastic bottle only
Cutback	Quality Viscosity Anit-Strip	Cert D 323, 329 AB 323, 374	RCE	1/20,000 gal	1 qt	DME		V	DME	1/proj	1 qt	CTRL	
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				

Note: (1) Poymer-modified emulsions are not normally accepted on the basis of certification; prior approval must be obtained from the DME before beginning shipments to a project.



## Sampling and Testing Guide-Minimum Frequency

Mats. I.M. 204  
Appendix P (Metric) Units

### BITUMINOUS SEAL COAT Section 2307

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
SOURCE INSPECTION														
Aggregates (4125)	Quality	AS 209												
Emulsions/Cutbacks	Quality	AS												
Emulsion & Aggregate	Compatibility	349	DME	1/ source	1 L & 5 kg	DME/ CTRL								
GRADE INSPECTION														
Aggregate	Quality Gradation	301 Cert D						V	DME	1/proj.	22 kg	CTRL		
Emulsion (1)	Quality Residue Compatibility	323, 360 349 Cert D	RCE ➡➡ RCE	1/75000 L 1 <sup>st</sup> Day + 1/ week	1 L 1 L & 5 kg	DME DME		V	DME	1/proj.	4 L	CTRL		Log all shipments Plastic bottle only
Cutback	Quality Viscosity Anit-Strip	323, 329 323, 374 Cert D AB	RCE	1/75000 L	1 L	DME		V	DME	1/proj	1 L	CTRL		
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					

Note: (1) Polymer-modified emulsions are not normally accepted on the basis of certification; prior approval must be obtained from the DME before beginning shipments to a project.



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix T (U.S.) Units

### BASE REPAIR (2212) PAVEMENT REPAIR (Patches) Sections 2529 and 2530

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
SOURCE INSPECTION													
Aggregates Fine (4110)		AS 209											
Aggregates Coarse (4115)		AS 209											
Portland Cement (4101)	Quality	AS 401											
Fly Ash (4108)	Quality	AS 491.17											
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS 491.14											
Curing Compound (4105)	Lab Tested	405											
Air Entraining Admixture (4103)	Quality	AB 403											
Granular Backfill	Gradation Quality	AS CERT AS CERT											
Drain Tubing	Quality	AS 443											
Epoxy Grout		AB 491.11											
Joint Seal (4136.02)	Lab Tested	436.01 AB 436.02											
Backer Rod (4136.02)		AB 436.04											
Steel Reinforcing	Quality	AS 451											
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor				



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix T (U.S.) Units

### BASE REPAIR (2212) PAVEMENT REPAIR (Patches) Sections 2529 and 2530

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ➡➡
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
PLANT INSPECTION														
Aggregates-Coarse (4115)	Grad	302    306 <del>306</del>	CONTR	3/lot	I.M. 301	CONTR		CORR	CONTR	1 <sup>st</sup> day +10%	IM 301	RC E		
	Moist	308	CONTR	1 / half day	1000 gm	CONTR								
	Sp. Gr.	307	CONTR	I.M. 527	1000 gm	CONTR								
	Quality	AS    209												
Aggregate- Fine (4110)	Gradation	302, 306 <del>306</del>	CONTR	3/lot	IM 301	CONTR	830211	CORR	CONTR	1 <sup>st</sup> day+10%	IM 301 IM 301	RC E		
	Moisture	➡➡    308, 528	CONTR	1/lot	1000 gm	CONTR	830211							See IM 528 if Moisture Probe is used
	Sp. Gr.	307	CONTR	IM 528	1000 gm	CONTR	830211							
	Quality	AS    209												
Portland Cement (4101)	Quality	AS    CERT D		Each Load										
Fly Ash	Quality	AS    CERT D		Each Load										
Air Entraining Admixture		AB    403	➡➡ DME	1/lot	1 pt	CTRL								Sample lots not previously reported or as directed by DME
Water Reducing Admixture		AB    403	➡➡ DME	1/lot	1 pt	CTRL								
Retarding Admixture		AB    403	➡➡ DME	1/lot	1 pt	CTRL								
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

Matis. I.M. 204  
Appendix T (U.S.) Units

### BASE REPAIR (2212) PAVEMENT REPAIR (Patches) Sections 2529 and 2530

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T						REMARKS ↔
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	
GRADE INSPECTION														
Plastic Concrete	Air Slump	318 327 318 327	RCE RCE	2/half day 2/half day		RCE RCE	830224 830224							
Reinforcing Steel Epoxy-Coated Steel	Quality Quality	AS 451 AS 451		Each Shipment										
Calcium Chloride	Concentr.	373	RCE	1/lot		RCE								
Asphalt Mixes Hardened Conc. Smoothness	↔ ↔												↔	Approval by DME See Plans/Specs for exclusions
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

Mtls. I.M. 204

Appendix T (Metric) Units

### BASE REPAIR (2212) PAVEMENT REPAIR (Patches) Sections 2529 and 2530

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
SOURCE INSPECTION														
Aggregates Fine (4110)		AS 209												
Aggregates Coarse (4115)		AS 209												
Portland Cement (4101)	Quality	AS 401												
Fly Ash (4108)	Quality	AS 491.17												
GGBFS(Ground Granulated Blast Furnace Slag)	Quality	AS 491.14												
Curing Compound (4105)	Lab Tested	405												
Air Entraining Admixture (4103)	Quality	AB 403												
Granular Backfill	Gradation Quality	AS CERT AS CERT												
Drain Tubing	Quality	AS 443												
Epoxy Grout		AB 491.11												
Joint Seal (4136.02)	Lab Tested	436.01 AB 436.02												
Backer Rod (4136.02)		AB 436.04												
Steel Reinforcing	Quality	AS 451												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204

Appendix T (Metric) Units

## BASE REPAIR (2212) PAVEMENT REPAIR (Patches) Sections 2529 and 2530

October 2, 2001

Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
PLANT INSPECTION														
Aggregates-Coarse (4115)	Grad	302 <u>306</u> <del>308</del>	CONTR	3/lot	<u>I.M. 301</u>	CONTR		CORR	CONTR	1 <sup>st</sup> day +10%	<u>IM 301</u>	RCE		
	Moist	<u>308</u>	CONTR	1 / half day	1000 gm	CONTR								
	Sp. Gr.	<u>307</u>	CONTR	<u>I.M. 527</u>	1000 gm	CONTR								
	Quality	AS <u>209</u>												
Aggregate- Fine (4110)	Gradation	<u>302, 306</u> <del>308</del>	CONTR	3/lot	<u>IM 301</u>	CONTR	830211	CORR	CONTR	1 <sup>st</sup> day+10%	<u>IM 301</u> <u>IM 301</u>	RCE		
	Moisture	➡➡ <u>308, 528</u>	CONTR	1/lot	1000 gm	CONTR	830211							See <u>IM 528</u> if Moisture Probe is used
	Sp. Gr.	<u>307</u>	CONTR	<u>IM 528</u>	1000 gm	CONTR	830211							
	Quality	AS <u>209</u>												
Portland Cement (4101)	Quality	AS CERT D		Each Load										
Fly Ash	Quality	AS CERT D		Each Load										
Air Entraining Admixture		AB <u>403</u>	➡➡ DME	1/lot	0.5 L	CTRL								Sample lots not previously reported or as directed by DME
Water Reducing Admixture		AB <u>403</u>	➡➡ DME	1/lot	0.5 L	CTRL								
Retarding Admixture		AB <u>403</u>	➡➡ DME	1/lot	0.5 L	CTRL								
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix T (Metric) Units

### BASE REPAIR (2212) PAVEMENT REPAIR (Patches) Sections 2529 and 2530

October 2, 2001  
Supersedes April 3, 2001

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS		QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡
				SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
GRADE INSPECTION														
Plastic Concrete	Air Slump	318	327	RCE	2/half day		RCE	830224						
		318	327	RCE	2/half day		RCE	830224						
Reinforcing Steel	Quality	AS	451		Each									
Epoxy-Coated Steel	Quality	AS	451		Shipment									
Calcium Chloride	Concentr.		373	RCE	1/lot		RCE							
Asphalt Mixes	➡➡												➡➡	Approval by DME See Plans/Specs for exclusions
Hardened Conc.	➡➡													
Smoothness														
AS-Approved Source		Cert A-Type A Certification				RCE-Resident Construction Engineer/Project Engineer				ASSUR-Independent Assurance				
AB-Approved Brand		Cert B-Type B Certification				DME-District Materials Engineer				VERIF-Verification				
ASD-Approved Shop Drawing		Cert C-Type C Certification				CTRL-Central Materials Office				CORR-Correlation				
S&T-Sampling & Testing		Cert D-Type D Certification				CONTR-Contractor				MON-Monitor				



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix U (U.S.) Units

### GRANULAR SHOULDERS Section 2121

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
<b>SOURCE INSPECTION</b>														
Aggregate (4120.02)	Gradation Quality	AS 209												
Aggregate (Paved Shoulder Fillets) (4120.07)	Gradation Quality	AS 209												
<b>GRADE INSPECTION</b>														
Dimensions	Thickness Width Cross Section	Template	RCE	3/mile 3/mile 3/mile		RCE	Field Book							
Aggregate (Paved Shoulder Fillets)	Gradation	Certification												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification		RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor						



## Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204  
Appendix U (Metric) Units

### GRANULAR SHOULDERS Section 2121

October 3, 2000  
Supersedes April 25, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS →	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
<b>SOURCE INSPECTION</b>														
Aggregate (4120.02)	Gradation Quality	AS 209												
Aggregate (Paved Shoulder Fillets) (4120.07)	Gradation Quality	AS 209												
<b>GRADE INSPECTION</b>														
Dimensions	Thickness Width Cross Section	Template	RCE	2/km 2/km 2/km		RCE	Field Book							
Aggregate (Paved Shoulder Fillets)	Gradation	Certification												
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification		RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor						



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204

Appendix V (U.S.) Units

## SUBDRAINS

### Section 2502

April 25, 2001

Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMs	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
SOURCE INSPECTION														
Drain Tubing (4143)	Quality	AS 443												
Rodent Guard (4143.01)		AB 443.01												
Subdrain Outlet (4143)		AS												
Porous Backfill (4131)	Quality Gradation	AS 209												
Granular Backfill (4133)	Quality Gradation	AS 209												
Class A (Outlets) (4120.04)	Quality Gradation	AS 209												
GRADE INSPECTION														
Drain Tubing (4143)	Quality	AS Cert		Each Shipment			Field Book	MON ➡	RCE	1/project	3-5-foot pcs.	CTRL		Sample for projects over 25,000 ft. only
Engineering Fabric (4196)		AS 496.01												
Subdrain Outlet	Quality	AS Cert												
Porous Backfill (4131)	Gradation	AS Cert		Each Shipment										
Granular Backfill (4133)	Gradation	AS Cert		Each Shipment										
Class A (Outlets) (4120.04)	Gradation	AS Cert		Each Shipment										
Metal Posts (4154.09)		Visual	RCE											
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



# Sampling and Testing Guide-Minimum Frequency

Matls. I.M. 204

Appendix V (Metric) Units

## SUBDRAINS Section 2502

April 25, 2001

Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION AND VERIFICATION S&T					REMARKS ➡➡	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
SOURCE INSPECTION														
Drain Tubing (4143)	Quality	AS 443												
Rodent Guard (4143.01)		AB 443.01												
Subdrain Outlet (4143)		AS												
Porous Backfill (4131)	Quality Gradation	AS 209												
Granular Backfill (4133)	Quality Gradation	AS 209												
Class A (Outlets) (4120.04)	Quality Gradation	AS 209												
GRADE INSPECTION														
Drain Tubing (4143)	Quality	AS Cert		Each Shipment			Field Book	MON ➡➡	RCE	1/project	3-2m pcs.	CTRL		Sample for projects over 25000 ft. only
Engineering Fabric (4196)		AS 496.01												
Subdrain Outlet	Quality	AS Cert												
Porous Backfill (4131)	Gradation	AS Cert		Each Shipment										
Granular Backfill (4133)	Gradation	AS Cert		Each Shipment										
Class A (Outlets) (4120.04)	Gradation	AS Cert		Each Shipment										
Metal Posts (4154.09)		Visual	RCE											
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing			Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor			ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



Sampling and Testing Guide-Minimum Frequency  
**WATER POLLUTION CONTROL**  
 EROSION CONTROL (New)  
**Section 2525, 2601**

Matls. I.M. 204  
 Appendix W (U.S.) Units

April 25, 2001  
 Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION) AND VERIFICATION S&T					REMARKS	
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY		REPORT
GRADE INSPECTION														
Seeds 4169.02		Cert A												
Fertilizer 4169.03		AS 469.03												
Inoculant 4169.04		Seed Manufacturer Recommendation												
Sticking Agent		Manufacturer Recommendation												
Sod 4169.07		Visual				RCE	Field Book							
Mulch 4169.07		Visual				RCE	Field Book							
Stakes for Sod		Visual				RCE	Field Book							
1/2" mesh 4169.10a		Visual				RCE	Field Book							
Wire Staples 4169.10b		Visual				RCE	Field Book							
Excelsior Mat 4169.10c		Visual				RCE	Field Book							
Engineering Fabrics		Cert D I.M. 496.01					Field Book							
Silt Fence Wire and Posts (Std. Rd. Plan RC-16)		Visual				RCE	Field Book							
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification			RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor					



# Sampling and Testing Guide-Minimum Frequency

## WATER POLLUTION CONTROL

EROSION CONTROL (New)

Section 2525, 2601

Matls. I.M. 204

Appendix W (Metric) Units

April 25, 2001


Supersedes October 3, 2000

MATERIAL OR CONSTRUCTION ITEM	TESTS	METHOD OF ACCEPTANCE AND RELATED IMS	QC/ACCEPTANCE S&T					ASSURANCE, CORRELATION) AND VERIFICATION S&T					REMARKS
			SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	REPORT	S&T TYPE	SAMPLE BY	FREQ.	SAMPLE SIZE	TEST BY	
GRADE INSPECTION													
Seeds <u>4169.02</u>		Cert A											
Fertilizer <u>4169.03</u>		AS <u>469.03</u>											
Inoculant <u>4169.04</u>		Seed Manufacturer Recommendation											
Sticking Agent		Manufacturer Recommendation											
Sod <u>4169.07</u>		Visual				RCE	Field Book						
Mulch <u>4169.07</u>		Visual				RCE	Field Book						
Stakes for Sod		Visual				RCE	Field Book						
<del>4169</del> mesh <u>4169.10a</u>		Visual				RCE	Field Book						
Wire Staples <u>4169.10b</u>		Visual				RCE	Field Book						
<del>Wood</del> Excelsior Mat <u>4169.10c</u>		Visual				RCE	Field Book						
Engineering Fabrics		Cert D <u>I.M. 496.01</u>					Field Book						
Silt Fence Wire and Posts (Std. Rd. Plan RC-16)		Visual				RCE	Field Book						
AS-Approved Source AB-Approved Brand ASD-Approved Shop Drawing S&T-Sampling & Testing		Cert A-Type A Certification Cert B-Type B Certification Cert C-Type C Certification Cert D-Type D Certification				RCE-Resident Construction Engineer/Project Engineer DME-District Materials Engineer CTRL-Central Materials Office CONTR-Contractor				ASSUR-Independent Assurance VERIF-Verification CORR-Correlation MON-Monitor			



# NOTES







---

## AGGREGATE SAMPLING METHODS AND DETERMINATION OF MINIMUM SIZE OF SAMPLES FOR SIEVE ANALYSIS

### SCOPE

This I.M. sets forth approved sampling methods and the minimum amount of dry materials necessary for the determination of particle size distribution.

### LOCATION FOR SAMPLING

To help ensure representative samples are taken, one of the following methods will be used for obtaining aggregate samples:

1. Conveyor Belt/Template Method

To obtain an off-the-belt sample: stop the belt, insert a template (as illustrated in the pictures below) at three or more separate locations along the belt, remove all material within the template, and combine it into the sample. In belt sampling, the ends of the template should be spaced just far enough apart to get an increment approximately one-third the minimum mass (weight) of the sample. If the template does not yield the minimum size of sample in three locations, additional locations will be necessary. No less than three separate locations should be used in obtaining one sample.





2. Stream Flow Method

When obtaining a sample by interception of the aggregate stream flow, care must be exercised, so the sampling device (See picture below.) passes quickly through the entire stream flow and does not overflow. At least three separate passes shall be made with the sampling device when obtaining a sample. Each pass is an increment of the sample. This is normally considered to be the best method to obtain a representative sample of coarse aggregate.



3. Stockpile Method (for fine aggregate only, or as directed by the Transportation Center Materials Engineer)

Stockpile sampling of fine aggregate may be accomplished by either using a shovel or a sand probe. When obtaining a field sample by the stockpile method, a minimum of three increments shall be taken at different locations around the stockpile. Avoid sampling in areas prone to segregation, such as along the bottom of cone stockpiles.

**Note:** Stockpile sampling of coarse aggregate should be avoided. If it becomes absolutely necessary to obtain a sample from a stockpile, consult the Transportation Center Materials Engineer to help devise an adequate and proper sampling plan.





### **SHIPPING SAMPLES**

Transport aggregate samples in bags or other containers constructed to preclude loss or contamination of the sample, or damage to the contents from mishandling during shipment.

Shipping containers for aggregate samples shall each have suitable identification attached and enclosed so that field reporting, laboratory logging and testing may be facilitated.

### **SAMPLE SIZES**

Minimum sample sizes for sieve analysis of aggregates are based on the maximum size of the product and the intended use. The following table lists the required minimum field sample and test sample sizes based on the **smallest sieve through which at least 95% of the sample will pass.**

<u>SIEVE SIZE</u>	<u>FIELD SAMPLE (kg/lbs.)</u>	<u>TEST SAMPLE (kg/gms)</u>
37.5 mm (1½ in.)	23.0/50	5.0/5,000<2>
25.0 mm (1 in.)	13.5/30	3.5/3,500
19.0 mm (¾ in.)	9.0/20	2.0/2,000
12.5 mm (½ in.)	9.0/20	1.5/1,500
9.5 mm (⅜ in.)	4.5/10	1.0/1,000<1>
4.75mm (#4 sieve)	4.5/10	.5/500
2.36mm (#8 sieve)	4.5/10	.2/200

(Products with maximum sizes over 37.5 mm (1½ in.) are normally visually inspected. Contact the appropriate Transportation Center Materials Engineer.)

- (1) When testing fine aggregate for PC Concrete, the minimum test sample is 500 grams.
- (2) When testing 1 1/2" aggregate for Special Backfill or Granular Subbase, the minimum test sample is 2500 grams.



THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU

THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU

THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU

THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU

THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU


THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU

THE UNIVERSITY OF CHICAGO  
DEPARTMENT OF THE HISTORY OF ARTS  
1100 EAST 58TH STREET, CHICAGO, ILL. 60637  
TEL: 773-936-5000 FAX: 773-936-5001  
WWW.HA.UCHICAGO.EDU



# NOTES







### SECTION III

## AGGREGATE PROPERTIES AND CHARACTERISTICS

Ideally, construction aggregates should be composed of durable, abrasion-resistant particles free of any deleterious or objectionable materials such as clay, shale, coal, organic matter, etc. Their specific gravities and absorptions are important when they are incorporated into Portland cement or asphaltic concrete mixes.

#### Aggregate Production Problems

Three common problems occur during the production phase and also at the time of use. These are SEGREGATION, DEGRADATION, and CONTAMINATION. When any of these conditions occur, it will affect the performance of the aggregate for its intended use and may lessen the design life of the project.

Segregation will occur anytime an aggregate is handled, and is especially predominate during construction of the stockpile. When a stacker conveyor is used, the finer (smaller) material will normally congregate in the center of the pile. The larger particles will tend to roll to the outside of the pile. As material is fed out of the stockpile, gradation variation is likely to occur.

When using a stacker conveyor, a helpful technique is using a movable stacker capable of building the stockpile in lifts. If the stacker is set too high, segregation will still occur. Some materials, such as "recycled asphalt paving" (RAP), have specifications controlling the height of individual lifts during stockpile construction.

Truck dumping is another common method of stockpile construction. With some less critical aggregates, this is usually

Stockpile segregation





accomplished with trucks running on the stockpile to make additional lifts. This method can result in degradation (breakdown) of the material as the trucks drive across the stockpile. Also, as the height of the stockpile increases, aggregate dumped close to the edge will segregate, with the coarser material rolling down the outside of the stockpile. Multiple lift truck stockpile construction of more critical aggregates, such as aggregate intended for use in paving, should be avoided.

Using a dozer to construct a stockpile is not recommended, especially with an aggregate prone to degradation. When a dozer is used, it normally forms ramp areas that are used over and over, tending to grind the aggregate under the tracks.

When loading material from a stockpile using an end loader, it is best to work along the entire vertical face of the pile. Done properly, this tends to equalize the coarse and fine areas of the stockpile, minimizing the segregation.

Contamination can easily happen during stockpiling. Material of one type may mistakenly be dumped into the wrong stockpile, contaminating both products. Different materials stockpiled too close to each other tends to lead to contamination where the stockpiles adjoin. Stockpiles should be constructed on sound bases to help eliminate contamination during the load-out process. Sometimes loader operators get too low when loading-out, or the bases may soften during the spring thaw or wet periods, increasing the danger of contamination from mud or dirt.

A good inspector should be alert to segregation, degradation and contamination and take steps to correct the problem before



the effected material can be incorporated into the project.

### **Deleterious Material**

It is very important that the aggregate be kept clean and free from deleterious substances. For this reason, the specifications limit the amount of deleterious substances that can be present. Shale, coal, chert, and other lightweight particles tend to float in a PC concrete mix.

Im 344

### **Resistance to Abrasion**


Abrasion is the mechanical wearing away of aggregate particles by friction and impact. Aggregates with low resistance to abrasion will readily wear away when used as surfacing materials or when exposed in pavement surfaces. They also degrade with handling. Excessive handling of aggregates with low resistance to abrasion can result in their containing relatively high percentages of fine material, often above the maximum level specified for the 75 $\mu$ m (#200) sieve for the particle aggregate involved.

### **Los Angeles Abrasion Test**

Resistance to abrasion is determined by the use of the Los Angeles Abrasion Machine, a cylindrical drum mounted on a horizontal shaft. A specified weight of coarse aggregate is placed in the machine along with a specified number of standard steel balls, the abrasive charge. After rotation at 30-33 rpm for 500 revolutions, the percentage of the aggregate sample that has been abraded to pass 1.70 mm (#12) sieve is reported as the loss due to abrasion, the percentage of wear.

Natural gravels will generally develop wear losses of 20% to 35% when tested for abrasion resistance. Crushed limestone aggregates will generally develop wear losses of 30% to 45%. Losses of 45% or more are commonly accepted to be indicative of aggregates with poor resistance to abrasion.

Abrasion Test using steel balls





### **Durability and Soundness**

These two terms are very similar in meaning and are often used interchangeably. The durability of an aggregate or other material is a measure of its ability to perform satisfactorily over an extended period of time. Soundness of an aggregate is a measure of its ability to resist the detrimental effects of exposure to natural forces.

#### **Durability**

Aggregate related deterioration can lead to the premature failure of our Portland Cement Concrete (PCC) highways. Durability is done only for **coarse aggregate** for use in PCC. The designations of Class 2, Class 3, and Class 3i durability are used. The best method to determine durability class is to observe the performance of a concrete pavement that was constructed with the coarse aggregate in question. If the pavement has performed satisfactorily for 20 years, it is a **Class 3 durability**. **Class 3i durability aggregates** must perform satisfactorily for up to 30 years in interstate class highways.

When a pavement performance history is not available, we have relied on ASTM Designation C666, Method B to make laboratory determination of the durability class. This consists of a series of 300 freeze and thaw test cycles on a concrete specimen and takes approximately 6 months to complete.

Much of an aggregate's ability to perform in PCC is a function of the pore spaces between the mineral grains. These voids can be thought of as both large pores connected to a smaller, or capillary, pore system. It has been determined that aggregates with extensive capillary pore systems are subject to durability problems due to failure after repeated freeze and thaw cycles.

#### **Durability**

Class 2  
Class 3  
Class 3i



**Durability Test**-Sound wave machine with prepared samples (concrete cubes with brass plugs on each end). Sound wave is transmitted through each cube before subjecting the sample to 300 F&T cycles and that reading is compared to first reading. If the coarse aggregate used in the sample tends to be susceptible it will crack during the process and the second sound wave will indicate how much aggregate was affected.



A unique apparatus was designed and constructed by the Iowa DOT Materials Laboratory personnel which measures the pore system of an aggregate particle in a relatively simple, quick and environmentally safe test. the test is referred to as the "Iowa Pore Index Test". This test, in conjunction with chemical analysis, has largely taken the place of the ASTM C666 test method in Iowa.

Chemical testing is a rapid way to evaluate the salt-susceptibility of carbonate aggregates by directly measuring aggregate properties that were being determined by indirect physical test. X-ray fluorescence (XRF), X-ray diffraction (XRD), and Thermogravimetric analysis (TGA), along with the Iowa pore index test, is used to generate an overall quality number.

- X-ray fluorescence (XRF) provides an elemental analysis used to calculate oxide percents.

- X-ray diffraction (XRD) determines mineralogy and is used primarily to determine purity of dolomite crystals.

- Thermogravimetric analysis (TGA) determines grain and crystallite size and some mineralogy.

The ASTM test takes approximately 6 months to complete. Chemical testing can normally be completed in one week, and through years of in-house research, has proven to be a more reliable method to predict the aggregate's durability.

### Soundness

Through the chemical testing research, an alternative method of predicting a coarse, carbonate aggregate's resistance to freeze and thaw cycles has been developed. It is suspected that the principle cause of aggregate failure is due to the clay content of the stone. Because clays are aluminosilicate minerals, the amount of alumina in the

### X-ray fluorescence





aggregate will be a measure of the clay content in the stone.

We use this test as a screening method for carbonate aggregates. If an aggregate sample fails the alumina content specification ( $\text{Al}_2\text{O}_3$ ), the 'A' freeze and thaw test will be performed to determine compliance. The alumina test does not indicate other characteristics such as the presence of soft oolites, which could cause 'A' F & T non-compliance.

**Method of Test for Determining the Soundness of Aggregates by Freezing and Thawing**

Test samples of coarse aggregate are alternately frozen and thawed for a prescribed number of cycles-16 in Method "A" for higher quality requirements, and 25 cycles in Method "C" for lower quality requirements. In both methods, the percentage passing the 2.36 mm (#8) sieve, computed to a clean dry weight basis, is reported as the soundness loss.

Method "A": 0.5% methyl alcohol is added to water in which the sample is immersed for thawing. This test is particularly severe on limestone aggregates that contain 5% or more of insoluble material in the clay or silt-size particle range. Generally, this is also the limestone that fails to perform well when the use of sound stone is required.

Method "C": Test samples are thawed in water only. Freezing and thawing in water is not particularly severe, hence 25 cycles are required on this test while only 16 cycles are required when the water-alcohol solution is used. Any reasonably clean, coarse aggregate will perform well in this test and it is used for all materials, which do not require high quality aggregates.

Freezer for Freeze-Thaw Test



Freeze-Thaw Test





### Specific Gravity

Specific Gravity is a property that can be determined for all materials and is important for the aggregate inspector to understand. Simply defined, specific gravity is the relative density of a material to water, or the number of times heavier a material is than water.

The specific gravity of aggregate to be used in a Portland cement concrete (PCC) mix is determined, at time of use, by the Pycnometer Method in Iowa. This method is described in I.M. 307, included in this manual, and personnel performing this test must possess a Level II Aggregate Certification.

PCC mix designs are based on volumetrics, which, for the aggregate portion of the mix, requires that the amount of each of the aggregates to be incorporated, per cubic yard of mix, be based on the "saturated surface-dry" (SSD) weight of the individual material.

SSD is defined as neither absorbing water from, nor contributing water to the concrete mix. The aggregate particles have all the moisture they can absorb with no "free" moisture on the particle surfaces.

The bulk SSD specific gravity of each aggregate must be known to determine the correct amount of each aggregate needed in the PCC mix. The specific gravity of the aggregate is normally determined from a series of tests performed on samples obtained during the production phase of each aggregate. Most aggregate sources have a uniform specific gravity as long as production practices stay consistent. Sources, which may have variable specific gravities, will usually be designated with a "DWU" (determined when used) in the T-203 source instructional memorandum.

Specific Gravity Jars





The specific gravity test performed at time of use (the plant site) is for verification purposes and to figure moisture percentages. The specific gravity to be used in determining batch weights is the one listed in the T-203. When the source indicates it is a "DWU", the plant technician is to call the appropriate District Materials office for the current specific gravity.

The test results by the plant inspector at time of use should be within 0.020 of the intended specific gravity. If the result is not within this tolerance, the plant inspector should rerun the test. If the result is still not in conformance, the plant inspector is to notify the District Materials office for investigation.

### **Aggregate Moisture**

The amount of individual aggregates used in a Portland cement concrete mix is determined in the design process based on the **Saturated-Surface-Dry** weight of the material. Terms used to describe the moisture content of aggregate are as follows:

- **Oven-dry (or constant-dry weight)** – containing no surface or internal moisture.
- **Air-dry** – dry at the particle surface but containing some internal moisture – this is somewhat absorbent.
- **Saturated-Surface-Dry** – an ideal condition in which the aggregate can neither absorb nor contribute water. In this condition, the interior has absorbed all the moisture it can hold, but the surface is dry.
- **Damp or Wet** – containing moisture on the particle surface.

**Oven-Dry**



**Air-Dry**



**SSD**



**Wet**



The free moisture present in aggregates must be accounted for when used in a Portland Cement Concrete mix. Aggregates containing free moisture carry that moisture into the mix during the batching process. If corrections are not made, the weight of the



individual aggregates containing this moisture will result in aggregate under yielding, that is, less aggregate in the mix than is required in the mix design. This “extra” water will also affect the water/cement ratio.

An aggregate particle’s internal structure is made up of solid matter and voids that may or may not contain water. Sometimes the aggregates to be used may be in an “absorbent” condition, which means that during the batching process, the aggregates will actually absorb some of the mix water, resulting in a mix drier than intended, with more aggregate by weight than designed. Iowa specifies that a stockpile of coarse aggregate having absorption of 0.5% or more shall be wetted and allowed to drain for at least 1 hour before use in the PCC mix. Fine aggregate, which is normally washed during the production phase, must be allowed to drain at least 24 hours before use in the mix. Also, at the time of use, aggregates must be handled in a manner that will prevent variations of more than 0.5 percent in moisture content of successive batches. The plant operator is responsible to devise remedial measures. The moisture content is normally determined in Iowa by the pycnometer method when tested at the time of use (I.M. 308, included in this manual). Personnel performing this test must have a valid Iowa Level II Aggregate certification. If water can be observed draining or dripping from any individual aggregate moisture sample, the moisture content cannot be measured successfully with the pycnometer, nor can it be uniformly controlled in the proportioning process. The moisture content must be allowed to stabilize (drain) before using the affected aggregate.




### Unit Weight

Unit weight is a ratio of weight to volume, such as kilograms per cubic meter square. Unit weight is not a measure of quality, but it is useful in converting weights of material to volumes. See ASTM Designation C29.

### Shape and Surface Texture

Particle shape of either coarse or fine aggregate may be angular, sub-angular, sub-rounded, or rounded.



Aggregate particles should ideally be equal dimensionally and free of excessive amounts of flat and elongated pieces. Long, slender aggregate pieces should be avoided. The shape of aggregate particles many times depends on the type of crusher used in the processing operation.

Particle shape and surface texture have a definite bearing on the quality of the finished product. Base courses composed of angular particles will compact and key together to form a dense, tight base, while elongated and rounded particles will slide and roll without compacting.

On the other hand, rounded particles tend to make plastic concrete. The texture of aggregate particles is normally defined in the following sequence: lithographic, sub-lithographic, fine-grained, medium grained, and coarse grained. Lithographic and fine-grained particles are polished quite easily by normal traffic wear and in time become a maintenance problem.



### **Gradation**

Gradation is the particle size distribution of aggregates determined by using sieves with square openings. As an aggregate is moved or handled, there is tendency for the particle sizes to separate. This separation is known as segregation. Limits are usually specified for the percentage of material passing each sieve. There are several reasons for specifying grading limits and maximum aggregate size. Deviations from the grading limits seriously affect the uniformity of finished work.

#### **Dense Graded Aggregate:**

Dense graded aggregates contain a proportion of material in each particle size present so as to minimize the void spaces between particles.

#### **Gap Graded Aggregate:**

Gap or open-graded aggregates contain too great an amount of particles of nearly the same size. This produces an open-type mixture with large void spaces. There are not enough of the smaller sizes to fill the voids between the larger sizes.

#### **Plasticity Index:**

The plasticity index of an aggregate is determined in order to determine the presence and relative activity of contained clay minerals. In Iowa, the Atterberg test (Iowa Test Method 109-A) is used to determine the Plasticity Index (P.I.) of a soil. The P.I. is directly related to the amount of clay in a material and is determined by subtracting the plastic limit from the liquid limit.

The Liquid Limit (L.L.) is that water content, expressed in percent dry weight, at which the material passes from a plastic to a liquid state. In general, it is determined by adding water to a portion of the minus 425 mm (#40) sieve size material until a certain consistency is reached.

*Gradation-Describes the various sizes of aggregate particles in terms of percentage passing or a percentage retained on a set of standardized square sieves.*



After at least 15 minutes of aging in a humidity chamber, a small amount is transferred to a special pan on top of an L.L. machine. A groove is made through the middle of the sample on the pan, separating the two halves by a fraction of an inch. The number of "drops" needed to bring a portion of the two halves back together is used to determine if the proper amount of water was initially added. If the initial amount of water was wrong, the sample is re-mixed and re-ran. The final sample is then weighed, dried, and again added, as well as the weight of the original grooved samples.

The Plastic Limit (P.L.) is that water content expressed in percent dry weight, at which the material passes from a semi-solid state to a plastic state. Generally, it is determined by adding water to a portion of the minus 425 mm (#40) sieve size material and then rolling it between the palm of the hand and a clean dry table. If the "threads" reach 3.175 mm (1/8 in.) diameter without breaking, they are remade into balls and rolled again. When the balls cannot be made to reach the 3.175 mm (1/8 in.) diameter thread size without breaking, they are placed in a pan for weighing, drying, and re-weighing to determine the weight of the threads.

### Summary-Aggregates


For the most purposes, aggregates must conform to certain requirements and should consist of clean, hard, strong, and durable particles free of chemicals, coatings of clay, or other fine materials that may affect construction.

Weak, friable, or freeze-thaw susceptible aggregate particles are undesirable for normal open highway construction. Aggregate containing natural shale or shale particles, soft and porous particles, and certain types of chert should be especially avoided since they have poor resistance to weathering. Visual inspection may often disclose weaknesses in coarse aggregates.



# NOTES







## Section IV

### *Sieve Analysis*

#### General Requirements

Aggregate sieve analysis procedures are governed by the Standard Specifications of the Iowa Department of Transportation and the Materials Office Instructional Memorandum Manual. The applicable test methods in the Materials Manual are included primarily in the 300 series under the subsection "Aggregate."

Sieve analysis is nothing more than the separation of a material based on particle size. For example, material that passes a 38.1 mm (1 ½ in.) sieve and is retained on a 25.4 mm (1 in.) sieve would not contain any particle larger than 38.1 mm (1 ½ in.) nor smaller than 25.4 mm (1 in.). Sieves are normally arranged in a "nest" with the largest wire opening at the top of the nest and the smallest at the bottom.

Iowa Department of Transportation Standard Specifications normally set limits on the percent passing a given sieve. The percent of the total weight retained on each sieve must be found first.

#### Coarse Aggregate Sieves

<u>SI Units</u>	<u>US Units</u>
37.5 mm	1 ½ inch
25.0 mm	1 inch
19.0 mm	¾ inch
12.5 mm	½ inch
9.50 mm	3/8 inch
4.75 mm	No. 4 (0.187 inch)

#### Fine Aggregate Sieves

<u>SI Units</u>	<u>US Units</u>
4.75 mm	No. 4 (0.187 in.)
2.36 mm	No. 8 (0.0937 in.)
1.18 mm	No. 16 (0.0469 in.)
0.600 mm	No. 30 (0.0234 in.)
0.300 mm	No. 50 (0.0117 in.)
0.150 mm	No. 100 (0.0059 in.)



Aggregate placed in  
coarsest sieve

Coarsest Sieve

Intermediate Sieves

Finest Sieve

Pan



To calculate percent retained on any sieve, merely divide the weight retained by the original dry weight of the sample and multiply by 100. The percent passing each sieve is then determined from the percent-retained column.

$$\text{Percent retained} = \frac{\text{Weight retained}}{\text{Original Dry Weight}} \times 100$$



# NOTES









April 27, 1999  
Supersedes October 27, 1998

Matls. I.M. 336

---

## METHODS OF REDUCING AGGREGATE FIELD SAMPLES TO TEST SAMPLES

### SCOPE

This method outlines the proper procedure for reducing an aggregate sample to the proper test sample size.

### PROCEDURE

The sample for testing should be approximately of the mass (weight) desired, conforming to the sample size for the material as indicated by Materials I.M. 301. The test sample must be the end result of the sample reduction method. Do not attempt to select a sample to an exact predetermined mass (weight).

#### I. SPLITTING METHOD

##### A. Apparatus

1. Sample splitter (conforming to equipment requirements of AASHTO T248-95).
2. Three catch pans
3. Wide, flat-edged scoop

##### B. Sample Preparation

1. The sample shall be dry enough to allow free flow of the aggregate through the chutes.

##### C. Test Procedure



1. Place the field sample on a hard, clean surface, such as a counter-top, concrete floor, or in a large, flat pan.
2. Thoroughly mix the field sample until it appears homogenous.
3. Place a catch pan under the chutes on each side of the splitter.
4. Place increments of the field sample on the wide, flat-edged scoop and uniformly distribute it from edge to edge, so when it is introduced into the chutes, approximately equal amounts will flow through each chute.



5. Repeat the above step until the entire field sample has been introduced into the chutes. It may be necessary to use a brush to collect the fine material of the sample for splitting.
6. The rate at which the sample is introduced shall be such as to allow a free flow of material from the scoop and through the chutes into the catch pans below.
7. Use the material contained in one of the catch pans and repeat the previous steps until the sample is reduced to the desired size. Be sure to split entire increments during this procedure.

D. General Comments

1. If the catch pans are equal to, or slightly less, than the total combined width of the riffle chutes, they may be used to place the material through the splitter in lieu of using the scoop. Do not use containers longer than the combined width of the riffle chutes to avoid overloading the end chutes.
2. Use the size of sample splitter best suited for the maximum particle size of the aggregate to be tested. Generally use the splitters with 25 mm (1 in.) riffle openings for aggregates with a 19 mm ( $\frac{3}{4}$  in.) maximum particle size, and the splitters with 50 mm (2 in.) openings for samples containing larger particle sizes 45 mm ( $1\frac{1}{4}$  in.). Samples of material with particles larger than 45 mm ( $1\frac{1}{4}$  in.) shall be quartered. (See IV. Below.)



## II. MECHANICAL SPLITTER METHOD

### A. Apparatus

1. Mechanical Sample Splitter



2. Ten Catch Pans
3. Buckets
4. Shovel

B. Sample Preparation

1. The sample shall be dry enough to allow free flow of the aggregate through the chutes.

C. Test Procedure

1. Place the ten small pans of the splitter in the appropriate area of the splitter.
2. Place the entire field sample in buckets. Turn on the splitter and pour material slowly into the top of the hopper.
3. Complete the pouring of the entire field sample into the hopper (catch pans will hold one bag without overflowing). If more than one bag is used, you will have to pour each catch pan into separate, larger containers and then resume splitting. It may be necessary to use a brush to collect the fine material of the sample.
4. Use all of the material contained in one or more of the catch pans to obtain the desired size.





---

### III. MINIATURE STOCKPILE METHOD (Fine Aggregate Only)

#### A. Apparatus


1. Shovel
2. Small scoop

#### B. Sample Preparation

1. This sample reduction method is only for fine aggregate samples in moist condition. Fine aggregates, which are in a substantially surface-dry condition or drier, should be reduced with a sample splitter.

#### C. Test Procedure

1. Place the moist field sample on a hard, clean, level and non-absorbent surface. Thoroughly mix the sample with the shovel and form a "miniature stockpile."
2. Obtain the test sample by selecting at least five increments of material at random locations from the miniature stockpile using the scoop.



### IV. QUARTERING METHOD

#### A. Apparatus



1. Shovel (square-nosed)
2. Brush
3. Quartering Device (optional)

B. Test Procedure

1. Place the sample on a hard, clean, smooth surface where there will be neither loss of material from the sample, nor the accidental addition of foreign material.
2. Mix the sample thoroughly by turning the entire lot over three times with a shovel. With the last turning, shovel the entire sample into a conical pile by depositing each shovelfull on top of the preceding one.
3. Carefully flatten the conical pile to a uniform thickness and diameter by pressing down the apex with the shovel, so each quarter will contain the amount of material originally in it.
4. Mark the flattened mass (weight) into quarters (or use the quartering device) by two lines that intersect at right angles at the center of the pile.
5. Remove two diagonally-opposite quarters and brush the cleared spaces clean, placing the brushed, fine aggregates into the removed quarters.
6. Successively mix and quarter the remaining materials as above, until the sample is reduced to the desired size, with the two remaining quarters giving the sample for the test.

C. General Comments

1. The quartering method is not recommended for sample reduction of coarse aggregate due to potential problems with segregation. This method should only be used when use of a sample splitter is not possible.





1947-1948

1949-1950

1951-1952

1953-1954

1955-1956

1957-1958

1959-1960

1961-1962

1963-1964


1965-1966

1967-1968



# NOTES









October 2, 2001  
Supersedes October 3, 2000

Matls. I.M. 302

## METHOD OF TEST SIEVE ANALYSIS OF AGGREGATES

### SCOPE

This method of test covers the procedure for determination of the particle size distribution of aggregates.

### PROCEDURE

#### A. Apparatus


1. Balance accurate to within 0.1 percent of mass (weight) of the sample to be tested. **NOTE:** The balance shall be reset to zero before each weighing.
2. Sieves with square openings mounted on substantial frames are constructed in such a manner to prevent loss of material during sieving. Use suitable sieve sizes to furnish the information required by the specifications covering the material to be tested. The woven wire cloth shall conform to AASHTO M-92. This will normally consist of a set of each of the following:

**Box Sieves** for testing coarse aggregates consisting of the following sizes:

37.5 mm (1½-in.)  
25 mm (1-in.)

19 mm (¾-in.)  
12.5 mm (½-in.)  
9.5 mm (⅜-in.)

4.75 mm (#4)  
2.36 mm (#8)





**203 mm (8 in.) Diameter Sieves** for testing fine aggregates consisting of the following sizes:

4.75 mm (#4)	1.18 mm (#16)	150 $\mu$ m (#100)
2.36 mm (#8)	600 $\mu$ m (#30)	75 $\mu$ m (#200)
	300 $\mu$ m (#50)	Pan



A set of **305 mm (12 in.) Diameter Sieves** may be used for testing fine aggregate or aggregate containing both coarse and fine material.

3. Mechanical and hand-powered sieve shakers
4. Drying oven or stove
5. Fiber bristle sieve cleaning brush (similar to stencil brush or cropped paintbrush)

**B. Test Sample**

1. Test samples for sieve analysis shall conform to the sample size for the applicable material as indicated by Materials [I.M. 301](#).
2. Obtain the sample for sieve analysis (test sample) from the material to be tested (field sample) by the appropriate method as outlined in Materials [I.M. 336](#). The test sample shall be approximately of the mass (weight) desired when dry and must be the end result of the reduction. Reduction to an exact predetermined mass (weight) shall not be permitted.



---

C. Preparation of Sample

1. When a determination of the amount of material passing the 75  $\mu\text{m}$  (#200) sieve is required, the test sample must first be subjected to Materials [I.M. 306](#), Method of Test for Determining the Amount of Material Finer Than the 75  $\mu\text{m}$  (#200) Sieve. Coarse aggregates may have a *separate* "wash" sample of the appropriate size (per [I.M. 306](#)) *reduced* from the remaining portion of the field sample, per [I.M. 336](#).
2. Coarse aggregates which have changes in moisture for different particle sizes must be dried to a constant mass (weight). When the absorbed moisture stays essentially the same for different particle sizes the sample may be sieved at a surface-dry condition (no free water present).

**NOTE:** Material from crushed composite (AC/PC) pavements shall be sieved at a surface-dry condition using no artificial heat. No gradation determination will be made for material finer than the 2.36 mm (#8) sieve. In some instances, larger particles may be coated to the extent that dry sieving will not accurately reflect the true gradation of the material. In these instances, the air-dried sample must be washed over the 2.36 mm (#8) sieve and allowed to come to a surface-dry condition by air-drying. The total percent passing this sieve is the sum of the washing loss and pan after dry sieving divided by the original (air) dry/mass (weight). Coated particles may also be a problem with some virgin aggregate material (e.g., Class D crushed stone, etc.). When this condition exists, the material shall be dried to a constant mass (weight), washed over the smallest sieve for which there is a specification requirement, and dried again. The total percentage passing this sieve is a combination of the washing loss and the amount passing the sieve obtained by dry sieving the washed sample divided by the original dry mass (weight).

D. Test Procedure

1. Weigh and record the mass (weight) of the test sample as the Original Dry Mass.
2. Sieve the sample over the required sieves. The sieving operation must be accomplished by using a lateral and vertical motion of the sieve(s), accompanied by a jarring action, which keeps the sample moving continuously over the surface of the sieve. Do not attempt to turn or manipulate the aggregate particle through the sieve openings by hand.

When using a mechanical sieve shaker, excessive sieving times may result in degradation of the sample.

The sieving operation may be considered complete when not more than 0.5 percent by mass (weight) of the original sample passes any sieve during an additional one minute of hand-sieving. \*



- a. On the 4.75 mm (#4) and larger sieves, limit the amount of material carried on the sieve to a single layer when determining sieving to completion.
- b. Overloading of the 203 mm (8 in.) and 305 mm (12 in.) diameter sieves, 4.75 mm (#4) and smaller, must be avoided to allow for sieving to completion. The weights retained should not exceed the following:

203 mm (8 in.) diameter sieves		305mm (12 in.) diameter sieves	
4.75 mm (#4) and smaller	200 grams	4.75 mm (#4)	850 grams
		2.36mm (#8) and smaller	450 grams

If sieving to completion (as described above) is not readily accomplished, reduce the amount of material carried on the sieve.

- c. When the aggregate being tested has a mixture of coarse and fine material, the portion of the sample finer than the 4.75 mm (#4) sieve may be distributed among two or more sets of sieves to prevent overloading of individual sieves. Alternately, the portion passing the 4.75 mm (#4) sieve may be reduced to a minimum of 500 grams using a mechanical splitter according to I.M. 336. If this procedure is followed, compute the mass (weight) of each size increment of the original sample as follows:

$$A = \frac{W1}{W2} \times B$$

Where:

- A = calculated mass (weight) of the material retained on each sieve based on the total sample mass (weight).
- W1= mass (weight) of the total amount of material passing the 4.75 mm (#4) sieve.
- W2= mass (weight) of the reduced, minus 4.75 mm (#4) sieve material.
- B = mass (weight) of the reduced sample material retained on each sieve.

**NOTE:** This method is recommended when using 203 mm (8 in.) diameter sieves to test the fine aggregate portion of a sample when overload is anticipated. If using 305 mm (12 in.) sieves and the original test sample is reasonably close to the required mass (weight), overload



should not occur. When sieve overload is anticipated on the 2.36 mm (#8) sieve only, sieve the original sample through the 2.36 mm (#8) box sieve before placing the fine portion in the nest of 203 mm (8 in.) round sieves.

3. Clean the retained material from each sieve for weighing. Remove as much material as practical without damaging the wire cloth. Particles may be removed most readily from a sieve by inverting the sieve over a pan and tapping the sieve by hand and/or pushing (without force) the particles out of the mesh into the pan. Care must be taken while cleaning the sieves, so no damage occurs to the wire mesh by bending or breaking the wires. A fiber-bristle brush should be used for cleaning the 1.18 mm (#16), 600  $\mu$ m (#30), and 300  $\mu$ m (#50) sieves. Do not use a brush or any external force on the wire cloth to attempt cleaning the 150  $\mu$ m (#100), or 75  $\mu$ m (#200) sieves. If clogging of the mesh occurs on these finer sieves, they should be sent to the District Materials Laboratory for cleaning.
4. Weight the fraction of material retained on each sieve and in the pan, to at least the nearest 0.5 gram and record. Total the mass (weight) of the material retained on the sieves and in the pan.
5. An accuracy check must be made comparing the mass (weight) of the material before sieving to the total mass (weight) after sieving. The total of the weights retained on the sieves and in the pan must be within 0.5 percent of the Original Dry Mass by washing.

**When the percent finer than the 75 $\mu$ m (#200) sieve is not determined:**

$$\frac{\text{Total}}{\text{Original Dry Mass}} \times 100 = \text{Tolerance (99.5 to 100.5)}$$

**When the percent finer than the 75  $\mu$ m (#200) sieve is determined by washing (IM 306):**

$$\frac{\text{Total - Washing Loss}}{\text{Dry Mass Washed}} \times 100 = \text{Tolerance (99.5 to 100.5)}$$

If the difference exceeds the 0.5 percent tolerance, check all the calculations, the sieves for retained material and the balance for proper care. If needed, weigh each increment of material retained again. If the error cannot be found, the test is void and a new sample shall be tested.

#### E. Calculations

1. Divide the mass (weight) of the material retained on each sieve, and in the pan, by the Original Dry Mass (Weight) of the sample. When computing the percent retained of a **washed** sample the sum of the washing loss and pan mass



---

(weight) shall be divided by the Original Dry Mass (Weight). Computation shall be carried out to the nearest 0.1 percent when determining percent retained and the consequent percent passing.

2. The percent-retained column should equal 100 percent when totaled. Because the mass (weight) of material retained on the sieves may not equal the Original Dry Mass (Weight), the total of the percentages retained may not equal 100 percent. If this occurs, the percentages retained should be altered by prorating on the larger quantities, so they do equal 100 percent.
3. The percent passing is then determined by subsequent subtraction starting with the sieve which had no material retained (100 percent passing).
4. Sieve analysis results are to be reported in terms of percent passing and recorded to two significant figures, i.e., to the nearest whole percent for percentages above 10.0 and to the nearest tenth of a percent for lower results.



# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

## EXAMPLE #1, COARSE AGGREGATE

Lab. No.:	
Material:	Grad. No.:
Co. & Proj. #:	
Producer:	
Contractor:	
Sampled By:	Date:
Sample Loc.:	

Original Dry Mass:	5793	Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
		Calculated Weight (A) = Conversion Factor x (B)	

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")				100.0	
25mm (1")		577	10.0	90.0	
19mm (3/4")		1088	18.4	71.6	
12.5mm (1/2")		1446	25.0	46.6	
9.5mm (3/8")		1383	23.9	22.7	
4.75mm (No. 4)		1062	18.7	4.0	
2.36mm (No. 60)	(B)	141 (A)	2.4	1.8	
1.18mm (No. 125)	(B)	(A)			
600µm (No. 250)	(B)	(A)			
300µm (No. 600)	(B)	(A)			
150µm (No. 1000)	(B)	(A)			
75µm (No. 200)	(B)	(A)		0.8	
Wash		(A)	1.8		
Pan	(B)	93 (A)			
Total		5790	100.0		
Tolerance		99.9			

Wash Sample	Original Dry Mass:		2571.0	
	Dry Mass Washed:		2555.0	
	Washing Loss:		16.0	
Sieve Size	Mass Retd.	% Retd.	% Passing	Specs.
75µm (200)			0.8	
Wash	16.0	0.8		
Pan	4.0			

Date Reported:	Test. No.:
Tested By:	

Note: For the 4.75mm (No. 4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \_\_\_\_\_

Lab. No.:	
Material:	Grad. No.:
Co. & Proj. #:	
Producer:	
Contractor:	
Sampled By:	Date:
Sample Loc.:	

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
		Calculated Weight (A) = Conversion Factor x (B)	

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")					
19mm (3/4")					
12.5mm (1/2")					
9.5mm (3/8")					
4.75mm (No. 4)					
2.36mm (No. 60)	(B)	(A)			
1.18mm (No. 125)	(B)	(A)			
600µm (No. 250)	(B)	(A)			
300µm (No. 600)	(B)	(A)			
150µm (No. 1000)	(B)	(A)			
75µm (No. 200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Test. No.:
Tested By:	

Note: For the 4.75mm (No. 4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \_\_\_\_\_



IOWA DEPARTMENT OF TRANSPORTATION  
SIEVE ANALYSIS WORKSHEET

EXAMPLE #2, FINE AGGREGATE

Lab. No.:		Grad. No.:	
Material:			
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:		Date:	
Sample Loc.:			

Original Dry Mass:	594.0	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	591.5	Reduced Minus 4.75 mm (W2):	
Washing Loss:	2.5	Conversion Factor: W1/W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")					
19mm (3/4")					
12.5mm (1/2")					
9.5mm (3/8")				100.0	
4.75mm (#4)		29.0	4.9	95.1	
2.36mm (#6)	(B)	84.5 (A)	10.9	84.2	
1.18mm (#16)	(B)	102.0 (A)	17.2	67.0	
600µm (#30)	(B)	181.5 (A)	30.6 (30.7)	38.3	
300µm (#60)	(B)	154.5 (A)	26.0 (26.1)	10.2	
150µm (#100)	(B)	51.0 (A)	8.6	1.6	
75µm (#200)	(B)	6.0 (A)	1.0	0.6	
Wash		2.5	0.6		
Pan	(B)	1.0 (A)			
Total		592.0	99.8 (100.0)		
Tolerance		99.7			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Tested By:	Cert. No.:
----------------	------------	------------

Note: For the 4.75mm (#4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \_\_\_\_\_

Lab. No.:		Grad. No.:	
Material:			
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:		Date:	
Sample Loc.:			

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1/W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")					
19mm (3/4")					
12.5mm (1/2")					
9.5mm (3/8")					
4.75mm (#4)					
2.36mm (#6)	(B)	(A)			
1.18mm (#16)	(B)	(A)			
600µm (#30)	(B)	(A)			
300µm (#60)	(B)	(A)			
150µm (#100)	(B)	(A)			
75µm (#200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Tested By:	Cert. No.:
----------------	------------	------------

Note: For the 4.75mm (#4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \_\_\_\_\_



Fineness Modulus Calculation  
for Concrete Sand (Grad. #1 – 4110)  
AASHTO T27-93

Add the **cumulative** percents retained, starting with the largest sieve retaining any material thru the #100 (150 $\mu$ m) sieve. Divide this total by 100 and report the result to the nearest 0.01.


**Example:**

	<u>Percent Retained</u>	<u>Cumulative Percent Retained</u>
$\frac{3}{8}$ " (9.5mm)	0	0
#4 (4.75mm)	3.6	3.6
#8 (2.36mm)	16.9	20.5
#16 (1.18mm)	19.6	40.1
#30 (600 $\mu$ m)	23.4	63.5
#50 (300 $\mu$ m)	26.1	89.6
#100 (150 $\mu$ m)	9.5	99.1

Total Accumulative Percent Retained = 316.4

$316.4 \div 100 = 3.16$  Fineness Modulus







IOWA DEPARTMENT OF TRANSPORTATION  
SIEVE ANALYSIS WORKSHEET

3.9384

EXAMPLE #3, COMBINED AGGREGATE, 8" AND BOX SIEVES

Lab. No.:	
Material:	Grad. No.:
Co. & Proj. #:	
Producer:	
Contractor:	
Sampled By:	Date:
Sample Loc.:	

4 places

Original Dry Mass:	2457.2	Total Minus 4.75 mm (W1):	2115.7
Dry Mass Washed:	2410.5	Reduced Minus 4.75 mm (W2):	537.2
Washing Loss:	46.7	Conversion Factor: W1 / W2	3.0384
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")				100.0	
19mm (3/4")		14.6	0.6	99.4	
12.5mm (1/2")		45.9	1.9	97.5	
9.5mm (3/8")		81.0	3.3	94.2	
4.75mm (#4)		154.0	6.3	87.9	
2.36mm (#60)	57.6 (B)	226.9 (A)	9.2	78.7	
1.18mm (#125)	93.0 (B)	366.3 (A)	14.9	63.6	
600µm (#30)	176.3 (B)	664.3 (A)	26.3 (26.4)	36.4	
300µm (#60)	172.5 (B)	679.4 (A)	27.6	7.6	
150µm (#100)	32.7 (B)	126.8 (A)	5.2	2.6	
75µm (#200)	3.9 (B)	15.4 (A)	0.6	2.0	
Wash		46.7	2.0		
Pan	0.6 (B)	3.2 (A)			
Total	536.8	2456.5	99.9 (100.0)		
Tolerance	99.9	100.0			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Tested By:	Cart. No.:
----------------	------------	------------

Note: For the 4.75mm (#4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \_\_\_\_\_

Lab. No.:	
Material:	Grad. No.:
Co. & Proj. #:	
Producer:	
Contractor:	
Sampled By:	Date:
Sample Loc.:	

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")					
19mm (3/4")					
12.5mm (1/2")					
9.5mm (3/8")					
4.75mm (#4)					
2.36mm (#60)	(B)	(A)			
1.18mm (#125)	(B)	(A)			
600µm (#30)	(B)	(A)			
300µm (#60)	(B)	(A)			
150µm (#100)	(B)	(A)			
75µm (#200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Tested By:	Cart. No.:
----------------	------------	------------

Note: For the 4.75mm (#4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \_\_\_\_\_



# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

## EXAMPLE #4, COMBINED AGGREGATE, 12" SIEVES

Lab. No.:	
Material:	Grad. No.:
Co. & Proj. #:	
Producer:	
Contractor:	
Sampled By:	Date:
Sample Loc.:	

Original Dry Mass:	2051.2	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	2011.4	Reduced Minus 4.75 mm (W2):	
Washing Loss:	39.8	Conversion Factor: W1 / W2	
Calculated Weight (A) = Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")				100.0	
19mm (3/4")		28.8	1.3	98.7	
12.5mm (1/2")		80.7	3.9	94.8	
9.5mm (3/8")		55.1	2.7	92.1	
4.75mm (#4)		182.7	8.9	83.2	
2.36mm (#6)	(B)	229.7 (A)	11.2	72.0	
1.18mm (#16)	(B)	382.8 (A)	17.7	54.3	
600µm (30)	(B)	610.5* (A)	29.8	24.5	
300µm (50)	(B)	377.1 (A)	18.4	6.1	
150µm (100)	(B)	72.2 (A)	3.5	2.8	
75µm (200)	(B)	10.2 (A)	0.5	2.1	
Wash		39.8	2.1		
Pan	(B)	3.4 (A)			
Total		2051.0	100.0		
Tolerance		100.0			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Spone.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Note: For the 4.75mm (#4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments: \*The 600µm (30) sieve was overloaded. Sieving to completion was verified by hand sieving.

Lab. No.:	
Material:	Grad. No.:
Co. & Proj. #:	
Producer:	
Contractor:	
Sampled By:	Date:
Sample Loc.:	

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A) = Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd.	% Retd.	% Passing	Specs.
37.5mm (1 1/2")					
25mm (1")					
19mm (3/4")					
12.5mm (1/2")					
9.5mm (3/8")					
4.75mm (#4)					
2.36mm (#6)	(B)	(A)			
1.18mm (#16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:			
	Dry Mass Washed:			
	Washing Loss:			
Sieve Size	Mass Retd.	% Retd.	% Passing	Specs.
75µm (200)				
Wash				
Pan				

Date Reported:	Cert. No.:
Tested By:	

Note: For the 4.75mm (#4) sieve and smaller, a 203mm (8") sieve should retain no more than 200 grams, and a 305mm (12") sieve no more than 450 grams

Comments:


October 2, 2001  
Supersedes October 3, 2000

Mats. I.M. 302



# NOTES







---

**METHOD OF TEST  
TO DETERMINE THE AMOUNT OF MATERIAL  
FINER THAN THE 75  $\mu$ m (#200) SIEVE IN AGGREGATE**

**SCOPE**

This test method outlines the procedure for determining the quantity of material finer than a 75  $\mu$ m (#200) sieve by washing and dry sieving.

**PROCEDURE**

**A. Apparatus**

1. A 75  $\mu$ m (#200) sieve (wash sieve)
2. A wash pan large enough to prevent loss of water and material
3. Oven or drying stove
4. Balance accurate to 0.1 percent of the sample mass (weight)
5. A set of 203 mm (8 in.) or 305 mm (12 in.) sieves for dry sieving

**B. Test Sample**

1. Select the test sample from the material to be tested by an appropriate method as outlined in Materials I.M. 336.
2. When determination of specification compliance is needed on each or any of the following sieves: 1.18 mm (#16), 600  $\mu$ m (#30), 300  $\mu$ m (#50), or 150  $\mu$ m (#100), subject the entire sample to this test procedure.
3. When determination of specification compliance is needed for only the amount of material finer than the 75  $\mu$ m (#200) sieve, reduce the remaining portion of the field sample from which the original test sample was selected, by the appropriate method as outlined in I.M. 336. A representative sample, sufficient to yield not less than the appropriate mass of dried material, as shown in the following table shall be selected:



Sieve Analysis Sample Mass (weight) kg (See Materials I.M. 301.)	Appropriate Minimum Mass (Weight) kg of Sample
5.0 kg	2.5 kg
3.5 kg	2.5 kg
2.0 kg	1.0 kg
1.5 kg	*
1.0 kg	*
0.5 kg	*
0.2 kg	*

\*Use entire sample.

### C. Test Procedure

1. Place the sample in the oven at 110°C (230°F) or on the stove and dry to a constant mass (weight). Care must be taken in drying the sample to avoid overheating causing the sample to "pop" or "sputter."
2. Allow the sample to cool, weigh and record as the Original Dry Mass (Weight).
3. Place the sample in the wash pan and add a sufficient amount of water to cover it. A detergent, dispersing agent, or other wetting solution may be added to the water to ensure a thorough separation of fine material from the coarser particles.
4. Agitate the sample vigorously using a rotary motion of the pan for five to ten seconds.
5. Pour off the water through the 75  $\mu$ m (#200) wash sieve. When washing samples with a high silt content, it may be necessary to vibrate or lightly tap the wash sieve in order to keep the mesh open so the water and the minus 75  $\mu$ m (#200) sieve material may pass through freely. Repeat this operation until the wash water appears almost clear.





6. Rinse the material retained on the 75  $\mu\text{m}$  (#200) sieve back into the sample and decant as much water as possible by carefully pouring the water through the 75  $\mu\text{m}$  (#200) sieve.
7. Dry the washed sample, allow to cool, weigh and record as the Dry Mass (Weight) of the washed sample.
8. When determining only the amount passing the 75  $\mu\text{m}$  (#200) sieve, screen the sample over the 2.36 mm (#8) sieve and discard the retained material. Place the portion of material passing the 2.36 mm (#8) sieve on a nest of sieves including the 300  $\mu\text{m}$  (#50), 150  $\mu\text{m}$  (#100), and 75  $\mu\text{m}$  (#200) sieves and the pan. The sieves larger than the 75  $\mu\text{m}$  (#200) sieve is included for protection of the 75  $\mu\text{m}$  (#200) sieve. Place the nest of sieves in the mechanical sieve shaker and sieve to completion (normally five minutes or less). Weigh and record only the material retained in the pan.
9. When a complete sieve analysis is required, test the entire sample using the appropriate method as outlined in I.M. 302.

D. Calculations

$$\% \text{ Passing } 75 \mu\text{m} \text{ (\#200) sieve} = \frac{\text{Washing Loss} + \text{Pan}}{\text{Original Dry Mass (Weight)}} \times 100$$







# NOTES







## GUIDELINES FOR VERIFYING CERTIFIED TESTING RESULTS

### GENERAL

Agency field personnel monitor certified testing by contractor personnel on a regular basis. Tolerances given herein are for use as guides to flag test result variations that indicate a possible discrepancy.

### TOLERANCES

The tolerances shown in the following listing apply to the difference between certified test results and monitoring test results. When the tolerances are exceeded, an immediate investigation must be made to determine possible cause so that any necessary corrections can be made.

<u>TEST NAME</u>	<u>TEST METHOD</u>	<u>TOLERANCE</u>
Slump of PC Concrete	IM 327	6 mm (¼ in.)
Air Content of PC Concrete	IM 318	0.4%
Length of Concrete Cores	IM 347	2 mm (0.10 in.)
Free Moisture in Aggregate, By Pycnometer	IM 308	0.2%
Specific Gravity of Aggregate, by Pycnometer	IM 307	0.02
Moisture in Aggregate or Recycled Asphalt Paving, By Hot Plate		0.3%
Density of AC Concrete, by Displacement	IM 321	0.02
Pavement Profile, by 7.6 m (25 foot) Profilograph, Profile Index, mm/km (in./mi):	IM 341	
Less than 93 mm/km (6 in./mi.)	16 mm/km (1 in./mi.)	
93 to 311 mm/km (6 to 20 in./mi.)	31 mm/km (2 in./mi.)	
311 to 622 mm/km (20 to 40 in./mi.)	47 mm/km (3 in./mi.)	
More than 622 mm/km (40 in./mi.)	78 mm/km	(5 in./mi.)

### TOLERANCES FOR AGGREGATE GRADATIONS

Determining the precision of an aggregate sieve analysis presents a special problem because the result obtained with a sieve is effected by the quantity of material retained on the sieve and by results obtained on sieves coarser than the sieve in question. Tolerances are, therefore, given for different ranges of percentage of aggregate passing one sieve and retained on the next finer sieve used.

Comparisons of test results are made on each fraction of the sample, expressed in percent that occurs between consecutive sieves.



**Note:** Comparisons of aggregate gradations are only valid if the two tests were made on a split sample.

Table 1 gives tolerances for the coarse portion (#4 sieve size material and larger) and the fine portion (material smaller than the #4 sieve) of aggregates. For analysis of combined aggregate for HMA, table 2 will be used for all sieve sizes.

**Table 1 Tolerances for all aggregates except HMA combined aggregate**

	Size Fraction Between Consecutive Sieves, %*	Tolerance, %
<b>Coarse Portion #4 Sieve and larger</b>	0.0 to 3.0	2
	3.1 to 10.0	3
	10.1 to 20.0	5
	20.1 to 30.0	6
	30.1 to 40.0	7
	40.1 to 50.0	9
<b>Fine portion: #8 Sieve and smaller</b>	0.0 to 3.0	1
	3.1 to 10.0	2
	10.1 to 20.0	3
	20.1 to 30.0	4
	30.1 to 40.0	4

**Table 2 Tolerances for all HMA combined aggregate**

Size Fraction Between Consecutive Sieves, %*	Tolerances
0.0 to 3.0	2
3.1 to 10.0	3
10.1 to 20.0	5
20.1 to 30.0	6
30.1 to 40.0	7
40.1 to 50.0	9

\*The monitoring analysis fraction is used to find the proper tolerance. Use of these tolerances is explained in the following examples. Gradation results are reported in two significant figures. Fraction differences between two sieves, one of which is reported to one decimal place, should be calculated to one decimal place.



EXAMPLE #1 - 57 CONCRETE STONE

Sieve Size	Gradation Percent PSG		Percent Retained		Fraction Diff.	Applicable Tolerance	Disposition
	Monitor	Certified	Monitor Fraction	Certified Fraction			
37.5 mm (1.5 in.)	100	100					
25 mm (1.0 in.)	97	99	3	1	2	2	OK
19 mm (3/4 in.)	72	65	25	34	9	(+4) 6	Suspect
12.5 mm (0.5 in.)	38	35	34	30	4	7	OK
9.5 mm (3/8 in.)	12	8.8	26	26.2	0.2	6	OK
4.75 mm (#4)	0.6	0.2	11.4	8.6	2.8	5	OK
2.36 mm (#8)	0.5	0.2	0.1	0.0	0.1	1	OK
75 µm (#200)	0.5	0.2	0.0	0.0	0.0	(-4) 1	OK
Pan	0	0	0.5	0.2	0.3	1	OK

The size fraction between consecutive sieves is found by calculating the difference between the % PSG reported for the two sieves. For example, the fraction between the 37.5 mm (1.5 in.) and 25 mm (1 in.) sieves for the above monitor test is 100 minus 97 equaling 3%. Between the 12.5 mm (½ in.) and 9.5mm (¾ in.) sieves it is 38 minus 12 equaling 26%. Since nothing passes the pan, the size fraction between the 75 µm (#200) sieve and the pan is equal to the percent passing the 75 µm (#200).

The example shows the fraction between each pair of consecutive sieve sizes for both tests and the difference between these fractions for both tests. The difference is compared with the applicable tolerance to determine a disposition. In this example, a suspect result is found in the fraction between the 25 mm (1 in.) and 19 mm (¾ in.) sieves. Since the suspect difference is due primarily to the % PSG results on the 19 mm (¾ in.) sieves, it is these results that should at least be investigated first. Only further investigation can determine which 19 mm (¾ in.) sieve, if any is faulty.

**Note:** The applicable tolerance changes between +4.75-mm/#4 and -4.75-mm/#4 size fractions. Note in the following example the applicable tolerance change as it applies to a Fine Aggregate gradation.

EXAMPLE #2 - CONCRETE SAND

Sieve Size	Gradation Percent PSG		Percent Retained		Fraction Diff.	Applicable Tolerance	Disposition
	Monitor	Certified	Monitor Fraction	Certified Fraction			
9.5 mm (3/8 in.)	100	100					
4.75 mm (#4)	95	95	5	5	0	(+4) 3	OK
2.36 mm (#8)	88	86	7	9	2	2	OK
1.18 mm (#16)	72	71	16	15	1	3	OK
600 µm (#30)	44	44	28	27	1	(-4) 4	OK
300 µm (#50)	12	13	32	31	1	4	OK
150 µm (#100)	1.5	1.3	10.5	11.7	1.2	3	OK
75 µm (#200)	0.4	0.4	1.1	0.9	0.2	1	OK
Pan	0.0	0.0	0.4	0.4	0	1	OK



EXAMPLE #3 - 13.2 mm (1/2 in) ACC STONE - COMBINED AGGREGATE

Sieve Size	Gradation Percent PSG		Percent Retained		Fraction Diff.	+4.75 mm Applicable Tolerance	Disposition
	Monitor	Certified	Monitor Fraction	Certified Fraction			
19 mm (3/4 in.)	100	100					
12.5 mm (0.5 in.)	99	99	1	1	0	2	OK
9.5 mm (3/8 in.)	87	86	12	13	1	5	OK
4.75 mm (#4)	69	75	18	11	7	5	SUSPECT
2.36 mm (#8)	54	56	15	19	4	5	OK
1.18 mm (#16)	41	42	13	14	1	5	OK
600 $\mu$ m (#30)	28	29	13	13	0	5	OK
300 $\mu$ m (#50)	15	15	13	14	1	5	OK
150 $\mu$ m (#100)	9.1	11	5.9	4	1.9	3	OK
75 $\mu$ m (#200)	6.9	8.6	2.2	2.4	0.2	2	OK
Pan	0.0	0.0	6.9	8.6	1.7	3	OK

**NOTE:** The applicable tolerance for this combined aggregate sample is from the +4.75-mm/#4 table. In this example, the suspect fractions would indicate a possible problem for two pairs of consecutive sieve sizes involving the 4.75 mm (#4) sieves. This evidence and the difference in the test values found for the 4.75 mm (#4) sieves, strongly point to an error in one of the 4.75 mm (#4) sieve results.

When RAP mixes are used the comparison data is of the composite gradation results and not of the cold feed.



Rev 08/99

**Iowa Department Of Transportation**  
**Reported Gradations & I.M. 216 Comparison Report**

Form M201

Project No.: \_\_\_\_\_

Contract ID: \_\_\_\_\_ Intended Use: \_\_\_\_\_

County: \_\_\_\_\_

Cont. / Producer: \_\_\_\_\_

Mix Design No.: \_\_\_\_\_

Mix Change (Y/N): \_\_\_\_\_

Date Of Change: \_\_\_\_\_

Total, % AC: \_\_\_\_\_

Effective % AC: \_\_\_\_\_

Proper Equipment: \_\_\_\_\_

Applicable Specs.: \_\_\_\_\_

Good Fair Poor

Care Of Equipment: \_\_\_\_\_

Sampling Procedure: \_\_\_\_\_

Splitting Procedure: \_\_\_\_\_

Sieving To Completion: \_\_\_\_\_

Computations: \_\_\_\_\_

Reporting: \_\_\_\_\_

D.O.T. Tested By: \_\_\_\_\_ Cert. No.: \_\_\_\_\_ Date: \_\_\_\_\_

Prod. / C.P.I. Tested By: \_\_\_\_\_ Cert. No.: \_\_\_\_\_ Date: \_\_\_\_\_

		Sieve Sizes										
		25	19	12.5	9.5	4.75	2.36	1.18	600um	300um	150um	75um
Specs.												
Sample ID	D.O.T.											
Sample ID	Prod. / C.P.I.											

D.O.T. FBR: 0.00

Sieves	D.O.T. % Retained	Prod. / C.P.I. % Retained	Diff.	Tol. %	Comply (Y/N)
25 - 19	NA	NA	0.0	2	Y
19 - 12.5	NA	NA	0.0	2	Y
12.5 - 9.5	NA	NA	0.0	2	Y
9.5 - 4.75	NA	NA	0.0	2	Y
4.75 - 2.36	NA	NA	0.0	2	Y
2.36 - 1.18	NA	NA	0.0	2	Y
1.18 - 600	NA	NA	0.0	2	Y
600 - 300	NA	NA	0.0	2	Y
300 - 150	NA	NA	0.0	2	Y
150 - 75	NA	NA	0.0	2	Y
75	NA	NA	0.0	2	Y

Sieve Fraction Between			Tolerance, %
Consecutive Sieves, %			
0.0	To	3.0	2
3.1	To	10.0	3
10.1	To	20.0	5
20.1	To	30.0	6
30.1	To	40.0	7
40.1	To	50.0	9

Remarks: \_\_\_\_\_

Distribution \_\_\_\_\_ Central Materials \_\_\_\_\_ TC Materials \_\_\_\_\_ Cont./Producer \_\_\_\_\_ Proj. Engineer \_\_\_\_\_ Technician \_\_\_\_\_



Rev 08/99

**Iowa Department Of Transportation**  
**Reported Gradations & I.M. 216 Comparison Report**

Form M200

Project No.: _____	Intended Use: _____ ( Paving, Structure, Patching, Incidental )
Contract ID.: _____	
County: _____	Good Fair Poor
Cont. / Producer: _____	Care Of Equipment: _____
Design No.: _____	Sampling Procedure: _____
Coarse Agg. T-203A No.: _____	Splitting Procedure: _____
Fine Agg. T-203A No.: _____	Sieving To Completion: _____
Proper Equipment: _____	Computations: _____
Applicable Specification: _____	Reporting: _____
D.O.T. Tested By: _____	Cert. No.: _____ Date: _____
Prod. / C.P.I. Tested By: _____	Cert. No.: _____ Date: _____

Grad No.	Sample ID	Specs	Sieve Sizes											
			37.5	25	19	12.5	9.5	4.75	2.36	1.18	600um	300um	150um	75um
		D.O.T.												
		Prod. / C.P.I.												

Grad No.	Sample ID	Specs														
		D.O.T.														
		Prod. / C.P.I.														

Sieves	D.O.T. % Retained	Prod. / C.P.I. % Retained	Diff.	Tol. %	Comply (Y/N)
37.5 - 25	NA	NA	0.0	2	Y
25 - 19	NA	NA	0.0	2	Y
19 - 12.5	0.0	0.0	0.0	2	Y
12.5 - 9.5	0.0	0.0	0.0	2	Y
9.5 - 4.75	0.0	0.0	0.0	2	Y
4.75 - 2.36	0.0	0.0	0.0	2	Y
2.36 - 75	0.0	0.0	0.0	2	Y
75um	0.0	0.0	0.0	2	Y

9.5 - 4.75	0.0	0.0	0.0	2	Y
4.75 - 2.36	0.0	0.0	0.0	1	Y
2.36 - 1.18	0.0	0.0	0.0	1	Y
1.18 - 600	0.0	0.0	0.0	1	Y
600 - 300	0.0	0.0	0.0	1	Y
300 - 150	0.0	0.0	0.0	1	Y
150 - 75	0.0	0.0	0.0	1	Y
75um	0.0	0.0	0.0	1	Y

	Size Fraction Between Consecutive Sieves, %	Tolerance, %
Coarse Aggregate:		
	0.0 to 3.0	2
	3.1 to 10.0	3
	10.1 to 20.0	5
	20.1 to 30.0	6
	30.1 to 40.0	7
	40.1 to 50.0	9
Fine Aggregate:		
	0.0 to 3.0	1
	3.1 to 10.0	2
	10.1 to 20.0	3
	20.1 to 30.0	4
	30.1 to 40.0	4


Remarks: \_\_\_\_\_

Distribution: \_\_\_\_\_ Central Materials \_\_\_\_\_ TC Materials \_\_\_\_\_ Cont./Producer \_\_\_\_\_ Proj. Engineer \_\_\_\_\_ Technician



# NOTES







---

**METHOD OF TEST  
SPECIFIC GRAVITY OF AGGREGATES  
FIELD PROCEDURES FOR LABORATORY TEST METHOD 201**

**SCOPE**

This method describes two procedures used for determining the bulk specific gravity of aggregates proposed for use in Portland Cement Concrete.

**PROCEDURE A – SPECIFIC GRAVITY OF AGGREGATES USING A PYCNOMETER****A. Apparatus**

1. Balance having a capacity of at least 5,000 grams, accurate to 0.5 grams
2. Pycnometer – a fruit jar supplied with a gasket and conical pycnometer top. A two-quart pycnometer is used for coarse aggregates, and a one-quart pycnometer is used for fine aggregate. If a two-quart pycnometer cannot be obtained, a one-quart jar may be substituted (The engineer may require 2 samples be obtained and tested in separate 1-quart pycnometers for some aggregates). The quantity of aggregate would be approximated 1100 grams for the one-quart pycnometer.
2. Thermometer – a thermometer with a range of at least 50°F (10°C) to 100°F (38°C)
3. Sieve – a No. 4 (4.75 mm) sieve

**B. Field Sample**

1. Obtain a field sample as prescribed in I.M. 301.

**C. Preparation of Test Sample**

1. Fine Aggregate
  - a. Obtain a test sample of approximately 1100 grams from the material to be tested by one of the following methods:
    - (1) Use of a sample splitter
    - (2) Method of quartering after being thoroughly mixed and in a damp condition



- (3) By taking small scoops of material from various places over the field sample, after it has been dampened and thoroughly mixed. In order to avoid segregation, the material must be damp enough to stand in a vertical face when cut with a trowel. This method of sample reduction is applicable to sands only.
- b. If the material has been continuously wet before being received on the job, it may be assumed to be saturated. Otherwise, the sample must be saturated by immersing it in water for period of not less than 15 hours.
- c. After soaking, pour off the free water, spread the wet sample on a flat, non-absorbent surface, and allow it to come to a surface-dry condition by natural evaporation of free moisture. Circulation of air by means of a fan may also be used to attain the surface-dry condition. The sample should be stirred frequently to secure uniform drying.

2. Coarse aggregate

- a. Obtain the test sample as prescribed in I.M. 336, Methods of Reducing Aggregate Field Samples To Test Samples (See sections on Quartering or Splitting).
- b. Sieve the test sample over the No. 4 (4.75 mm) sieve. The sample should be of sufficient size to produce approximately 2100 grams of material retained on the No. 4 sieve. Discard the material that passes this sieve.
- c. Immerse the sample (plus No. 4 sieve size) in water for a period of not less than 15 hours.
- d. After soaking, pour off the free water and allow the sample to come to a saturated-surface-dry condition by spreading the sample on a flat, non-absorbent surface. The forced circulation of air by means of a fan, if available, may hasten this process. The sample should be stirred frequently to secure uniform drying. The predominance of free moisture may be removed initially by rolling the sample back and forth in a clean, dry, absorbent cloth.
- e. The sample may be considered to be saturated-surface-dry when the particles look comparatively dull as the free moisture is removed from their surfaces. For highly absorptive aggregates, the saturated-surface-dry condition is reached when there is an absence of free moisture.



---

D. Calibration of Pycnometers

1. Fill the pycnometer jar nearly full of water at the temperature to be used in the actual test, plus or minus 3°F (1.7°C). This may be done either before or after the actual test.
2. Screw the pycnometer top down tightly on the jar and mark the position of the top on the jar by a scratch or mark on the threaded rim and a scratch in a corresponding position on the jar, which will establish a constant volume.
3. Fill the pycnometer completely by pouring water into the hole of the pycnometer top until a bead forms above the opening. Immediately wipe the bead of water level with the pycnometer opening. Wipe all other excess moisture from the outside surfaces of the pycnometer. If a bead of water forms at the opening during the final wiping, it should remain for weighing. Weigh the pycnometer to the nearest 0.5 gram.

E. Test Procedure

1. Weigh the saturated-surface-dry sample to the nearest 0.5 gram. For ease in calculations, the fine aggregate sample may be brought to exactly 1000 grams weight, and the coarse aggregate sample may be brought to exactly 2000 grams weight.
2. Place the sample in the appropriate pycnometer containing approximately two inches of water.
3. Nearly fill the pycnometer jar with water at the same temperature plus or minus 3°F (1.7°C) as used in the calibration.
4. Screw the cap down into the proper position by lining up the mark on the pycnometer top and the jar.
5. Entirely fill the pycnometer by adding additional water through the hole in the pycnometer top.
6. Hold one finger over the hole in the top and gently roll and shake the pycnometer to remove any trapped air in the sample.
7. When further rolling and shaking brings no more air bubbles to the top, fill, dry and weigh as in step C3.



F. Calculations

1. Calculate the saturated-surface-dry (SSD) specific gravity to the nearest 0.01 by the following formula:

$$\text{Bulk Specific Gravity (SSD)} = \frac{S}{P + S - W}$$

Where:

S = Weight in grams of aggregate in a saturated-surface-dry condition.

P = Weight in grams of the pycnometer filled with water.

W = Weight in grams of the pycnometer containing the sample and sufficient water to fill the remaining space in the pycnometer.



**Pycnometers for Coarse and Fine Aggregates**

**PROCEDURE B – SPECIFIC GRAVITY OF COARSE AGGREGATE (AASHTO T 85)**


A. Apparatus

1. Balance having a capacity of at least 5,000 grams, accurate to 0.5 grams



- 
2. Sample Container – A wire basket of No. 6 (3.35 mm) or finer mesh, or a bucket of approximately equal breadth and height, with a capacity of 4 to 7 L.. The container shall be constructed so as to prevent trapping air when the container is submerged.
  3. Water Tank – A watertight tank, into which the sample and container are placed for complete immersion while suspended below the balance, equipped with an overflow outlet for maintaining a constant water level.
  4. Suspended Apparatus – Wire suspending the container shall be of the smallest practical size to minimize any possible effects of a variable immersed length.
  5. Sieve - A No. 4 (4.75 mm) sieve
  6. Thermometer – a thermometer with a range of 50°F (10°C) to 100°F (38°C)
- B. Field Sample
1. Obtain a field sample as prescribed in I.M. 301.
- C. Preparation of Test Sample
1. Prepare the test sample identical to that described in Procedure A.
- D. Test Procedure
1. Weigh the saturated-surface-dry sample to the nearest 0.5 gram. For ease in calculations, the fine aggregate sample may be brought to exactly 1000 grams weight, and the coarse aggregate sample may be brought to exactly 2000 grams weight.
  2. After weighing, immediately place the saturated-surface-dry sample in the sample container, remove all entrapped air by shaking the immersed container, and determine its mass in water at 73.4°F ± 3°F (23.0°C ± 1.7°C). Make sure the water is at a depth sufficient enough to cover the container and sample.
- E. Calculations
1. Calculate the saturated-surface-dry (SSD) specific gravity to the nearest 0.01 by the following formula:
- $$\text{Bulk Specific Gravity (SSD)} = \frac{S}{S - W}$$
- Where:
- S = Weight in grams of aggregate in a saturated-surface-dry condition.  
W = Weight in grams of the saturated-surface-dry sample in water
-







## Specific Gravity Problems

Calculate the specific gravity to the nearest 0.01 saturated-surface-dry (SSD) from the following formula:

$$\text{Bulk Specific Gravity (SSD)} = \frac{S}{P + S - W}$$

Where:

- S = Mass in grams of aggregate in a saturated-surface-dry condition  
P = Mass in grams of the pycnometer filled with water  
W = Mass in grams of the pycnometer containing the sample and sufficient water to fill the remaining space in the pycnometer

Given:

1. S = 2000 (C.A.)  $\frac{2000}{4725.7 - 3945.2}$   
P = 2725.7

Sp.Gr. (SSD) = 2.56

W = 3945.2

2. S = 1000 (F.A.)  $\frac{1000}{378}$   
P = 1524.6

Sp.Gr.(SSD) = 2.65

W = 2146.6

3. S = 1000  
P = 1485.9

Sp.Gr. (SSD) = 2.64

W = 2107.1

4. S = 2000  
P = 2739.9

Sp.Gr. (SSD) = 2.62


W = 3976.2

5. S = 2000  
P = 2637.8

Sp.Gr. (SSD) = 2.62

W = 3874.8








# NOTES







---

**METHOD OF TEST**  
**DETERMINATION OF FREE MOISTURE AND ABSORPTION OF AGGREGATES**

**SCOPE**

This method describes several procedures for determining free moisture and absorption of aggregates.

**PROCEDURE A - FREE MOISTURE IN AGGREGATES USING A PYCNOMETER****A. Apparatus**

1. Balance having a capacity of at least 5,000 grams accurate to 0.5 grams
2. Pycnometer - A fruit jar supplied with a gasket and conical pycnometer top. A two-quart pycnometer is used for coarse aggregates. If a two-quart pycnometer cannot be obtained, a one-quart jar may be substituted (The engineer may require 2 samples be obtained and tested in separate 1-quart pycnometers for some aggregates). The quantity of aggregate would be approximately 1000 grams for the one-quart pycnometer. A one-quart pycnometer is used for fine aggregates.
3. Thermometer - -35 to 50°C (-30°F to 120°F) thermometer
4. Scoop

**B. Field Sample**

1. Obtain a field sample as prescribed in I.M. 301.

**C. Preparation of Test Sample**

1. Obtain a test sample of about 1000 grams of fine aggregate or about 2000 grams of coarse aggregate by the following method:

Place the field sample on a clean, hard non-absorbent surface. Mix the sample thoroughly, form a miniature stockpile and obtain small increments of materials from random locations from the stockpile until the desired sample size is obtained.

**Note:** The moisture test should be completed as soon as possible after obtaining the field sample to avoid moisture loss due to evaporation.

2. Weigh to the nearest 0.5 gram, a 1000 gram sample of fine aggregate, or 2000 gram sample of coarse aggregate. To avoid moisture loss due to evaporation the weighing should be done immediately after obtaining the test sample. Also avoid any excessive manipulation of the aggregate, prior to weighing, which could cause a loss of moisture.



D. Calibration of Pycnometer

1. Calibrate the pycnometer by the procedure in I.M. 307.

E. Test Procedure

1. The test procedure is identical to I.M. 307 with the exception that the test sample is wet, as received, and not in a saturated surface dry condition. This procedure is intended for determining the moisture content of aggregates for Portland Cement Concrete.

F. Calculation

1. Calculate the moisture content, based on wet sample mass (weight), to the nearest 0.1 percent as follows:

$$\text{Percent Moisture as received} = \frac{(W - W_1)G_s \times 100}{(G_s - 1)s}$$

Where:

W = Mass (Weight) in grams of the pycnometer containing a saturated-surface-dry sample of the same mass (weight) as "s" and sufficient water to fill the remaining volume of the pycnometer as determined in I.M. 307.

W<sub>1</sub> = Mass (Weight) in grams of the pycnometer containing the wet sample and sufficient amount of water to fill the remaining volume of the pycnometer.

G<sub>s</sub> = Specific gravity of material in a saturated-surface-dry condition. (This is obtained from Method I.M. 307 or I.M. T203.)

s = Mass (Weight) in grams of wet sample

2. The percent of moisture, based on the saturated-surface-dry mass (weight), is calculated as follows:

$$\text{Percent Moisture (SSD)} = \frac{\% \text{Moisture as received}}{100 - \% \text{Moisture as received}} \times 100$$

**PROCEDURE B – FREE MOISTURE IN AGGREGATE BY MASS (WEIGHT) DIFFERENCE**

This procedure is an alternate to using a pycnometer and is also intended for determining the moisture content of aggregates for Portland Cement Concrete.



A. Apparatus

1. Balance having a capacity of at least 5,000 grams and accurate to 0.5 gram

B. Preparation of Sample

1. Prepare the test sample identical to that described in Procedure A.

C. Test Procedure

1. Bring the weighed wet sample to a saturated-surface-dry condition in the manner described in Matls. I.M. 307 and weigh to the nearest 0.5 gram.

D. Calculation

1. Calculate the moisture content, based on wet mass (weight), to the nearest 0.1 percent as follows:

$$\text{Percent Moisture} = \frac{\text{Wt. as received} - \text{Wt. SSD}}{\text{Wt. as received}} \times 100$$

A negative result is due to absorption of the aggregate rather than free moisture.

2. The percent of moisture, based on saturated-surface-dry mass (weight), is calculated to the nearest 0.1 percent as follows:

$$\text{Percent Moisture SSD} = \frac{\% \text{ Moisture as received}}{100 - \% \text{ Moisture by wet mass (weight) as received}} \times 100$$

or

$$\text{Percent Moisture (SSD)} = \frac{\text{wet mass (weight)} - \text{saturated - surface - dry mass (weight)}}{\text{saturated - surface - dry mass (weight)}} \times 100$$

**PROCEDURE C - WATER ABSORPTION IN AGGREGATE**

This procedure is used for determining absorption of aggregates for use in asphaltic concrete as well as determining specification compliance for absorption.

A. Apparatus

1. Balance having the capacity of at least 5000 grams and accurate to 0.5 gram
2. Oven or hot plate



---

B. Preparation of Sample

1. Obtain a test sample of at least 1000 grams of fine aggregate and 2000 grams of coarse aggregate by following the appropriate procedure outlined in I.M. 307.
2. When the sample is not in a saturated condition it must be immersed in water at room temperature for a minimum of 15 hours before continuing with the test.
3. Allow the saturated sample to attain a surface-dry condition by following the procedure in I.M. 307.

C. Test Procedure

1. Weigh the saturated, surface-dry sample to the nearest 0.5 gram.
2. Dry the sample in the oven or on the hot plate or stove to a constant mass (weight).
3. Allow the sample to cool and weigh to the nearest 0.5 gram.

D. Calculation

1. The percent absorption, based on the oven dry mass (weight) is calculated to the nearest 0.01 percent as follows:

Percent Absorption =


$$\frac{\text{Saturated - surface - dry mass (weight) - oven dry mass (weight)}}{\text{oven dry mass (weight)}} \times 100$$



**APPENDIX A**  
**W-W1 TABLE FOR PYCNOMETER MOISTURE DETERMINATION**

<b>W-W1</b> <b>in</b> <b>grams</b>	<b>% Moisture/Absorp.</b>		<b>W-W1</b> <b>in</b> <b>grams</b>	<b>% Moisture/Absorp.</b>		<b>W-W1</b> <b>in</b> <b>grams</b>	<b>% Moisture/Absorp.</b>	
	<b>1000 gm</b> <b>sample</b>	<b>2000 gm</b> <b>sample</b>		<b>1000 gm</b> <b>sample</b>	<b>2000 gm</b> <b>sample</b>		<b>1000 gm</b> <b>sample</b>	<b>2000 gm</b> <b>sample</b>
<b>0</b>	0.0	0.0	<b>15</b>	2.4	1.2	<b>30</b>	4.8	2.4
<b>1</b>	0.2	0.1	<b>16</b>	2.6	1.3	<b>31</b>	5.0	2.5
<b>2</b>	0.3	0.2	<b>17</b>	2.7	1.4	<b>32</b>	5.1	2.6
<b>3</b>	0.5	0.2	<b>18</b>	2.9	1.4	<b>33</b>	5.3	2.6
<b>4</b>	0.6	0.3	<b>19</b>	3.0	1.5	<b>34</b>	5.5	2.7
<b>5</b>	0.8	0.4	<b>20</b>	3.2	1.6	<b>35</b>	5.6	2.8
<b>6</b>	1.0	0.5	<b>21</b>	3.4	1.7	<b>36</b>	5.8	2.9
<b>7</b>	1.1	0.6	<b>22</b>	3.5	1.8	<b>37</b>	5.9	3.0
<b>8</b>	1.3	0.6	<b>23</b>	3.7	1.8	<b>38</b>	6.1	3.1
<b>9</b>	1.4	0.7	<b>24</b>	3.9	1.9	<b>39</b>	6.3	3.1
<b>10</b>	1.6	0.8	<b>25</b>	4.0	2.0	<b>40</b>	6.4	3.2
<b>11</b>	1.8	0.9	<b>26</b>	4.2	2.1	<b>41</b>	6.6	3.3
<b>12</b>	1.9	1.0	<b>27</b>	4.3	2.2	<b>42</b>	6.7	3.4
<b>13</b>	2.1	1.0	<b>28</b>	4.5	2.2	<b>43</b>	6.9	3.5
<b>14</b>	2.2	1.1	<b>29</b>	4.7	2.3			







# NOTES







## *Section V* *Aggregate Source Inspection*

Aggregate source inspection involves monitoring the quality of the material being produced from an approved source, preliminary testing or production will usually have occurred at the site to establish the potential quality of material obtainable. Although at times further assurance samples are required, most construction aggregates are delivered to a project with the only quality requirement being that they were obtained from an approved source. This can be done because the quality level of an aggregate as measured by soundness or abrasion tests remains essentially the same unless some significant change has occurred, either in the material or in the manner in which it was produced. It is the responsibility of the Aggregate Technician to recognize when any such change has occurred and to obtain such as necessary to establish the quality of aggregate being produced under the changed conditions. The factors causing change are somewhat different in quarries than in sand and gravel pits and each shall be covered separately.

### **Quarries**

There are many reasons why an aggregate from a particular quarry can test differently with respect to quality than that previously produced. Most of these reasons fall into the following categories.

- a) Ledge Control: The quarry ledge has not been maintained in the same beds.
- b) Lateral Variations: One or more beds in the quarry ledge have changed laterally in quality.
- c) Faulted and Dipping Beds: The beds are offset along a fault or

**Quarry-** *A deposit of ledge rock from which the rock is excavated by cutting or blasting.*



have such an irregular surface that the quarrying operation cuts across beds to the extent that the same beds are not always being worked.

- d) Deleterious Materials: The quarry ledge has become intruded with pockets or seams of clay and associated weathered material.
- e) Production Changes: Production methods have changed to the extent that a similar product is not being obtained.

### **Ledge Control**

As an aid identifying the various beds and/or quality units in quarry, geologic sections have been prepared for most (Figure 3.1). The various beds are identified by a number and a description. The geologic age of the source is also noted and the relative position of the source age-wise can be found on a time chart such as Figure 3.2. Every layer or bed of rock in a quarry can be quite different in quality while often times quite similar visibly. Consequently, when material is being produced on the basis of previously established quality, we must be sure that the quarry ledge is in the same beds as before, or if it isn't, that any of the new beds in the ledge are of a quality that will assure specification compliance of the final product.

In quarries where bedding planes are distinct and continuous, it is a simple matter for the producer to maintain a ledge in the same beds and for the inspector to ascertain which beds they are. When there are no good bedding planes, the producer can have difficulty remaining in the same beds and difficulty in knowing exactly which beds are being worked. Satisfactory ledge control can be maintained by



SW $\frac{1}{4}$  Sec. 23 T. 95 R. 15 Co. Floyd  
 Carville Qr.  
 Heckman-Reynolds

Peterson

5/6/75

00: Overburden

+3.0'


CEDAR VALLEY FORMATION  
 (Coralville Member)

- |   |   |     |
|---|---|-----|
| 1 | 1. Limestone; light brown; medium crystalline; very petroliferous; carbonaceous laminations; thin to platy bedding.   | +6. |
| 2 | 2. Dolomite; light brown; coarse crystalline; a few small calcite-filled vugs- as 3 or 4 beds; very hard.   | 2   |
| 3 | 3. Limestone; light, pinkish gray; medium crystalline; dolomitic; many large calcite-filled vugs in zones parallel to bedding; flaggy beds 0.3-0.6' thick; upper 1.0' is a distinctive zone of highly concentrated calcite-filled vugs.                         | +4  |
| 4 | 4. Dolomite; light, pinkish gray; fine crystalline; many calcite-filled vugs and "birdseye" calcite; a few small pelecypod fragments; as 3 or 4 wavy beds; reddish brown shale parting at the base; irregular reddish brown shaley bed 0.2' thick at top; hard. | +1  |
| 5 | 5. Dolomite; light, pinkish gray; medium crystalline; has a few small calcite-filled vugs and "birdseye" calcite; massive but fractured; hard.  | +3  |

FLOOR

FIGURE 3.1







# STRATIGRAPHIC COLUMN OF IOWA

SYSTEM	SERIES	GROUP	FORMATION	DESCRIPTION	THICKNESS (feet)	AGE (in millions of years before present)		
Quaternary	Pleistocene		Wisconsin	loess, glacial till and interbedded sand and gravel	500'	2-3		
			Illinoian					
			Kansan					
			Nebraskan					
Cretaceous		Colorado	Carlile	shale	350'	130		
			Greenhorn	limestone and shale				
			Graneros	shale				
		Dakota		sandstone and shale	200'			
Jurassic			Fort Dodge beds	gypsum, red and green shales in Webster County only	50'	185		
Pennsylvanian	Virgil	Wabounee	French Creek	shale	210'			
			Jim Creek	limestone				
			Friedrich	shale				
			Grandharen	limestone				
			Dry	shale				
			Dover	limestone				
			Langdon (includes Hyman Coal)	shale				
			Maple Hill	limestone				
			Warrego	shale				
			Tarkio	limestone				
			Willard	shale				
			Elmont	limestone				
			Harveyville	shale				
			Reading	limestone				
			Auburn	shale				
			Wakarusa	limestone				
			Soldier Creek	shale				
			Burlingame	limestone				
			Silver Lake	shale				
			Rulo	limestone				
			Cedar Vale (includes Elmo bed at top)	shale				
			Happy Hollow	limestone				
			White Cloud	shale				
			Howard	limestone				
			Severy (includes Nodaway coal bed at base)	shale				
		Pennsylvanian	Missouri	Shawnee	Topoka		limestone	180'
					Colfax		shale	
					Deer Creek		limestone	
					Tecumseh		shale	
					Lecompton		limestone	
Kanwaka	shale							
Douglas	Oread			limestone	110'			
	Lawrence			shale				
	Stronger			shale				
Lansing	Iolan			limestone	50'			
	Weston			shale				
	Stanton			limestone				
	Vilas			shale				
	Plattsburg			limestone				
	Bonner Springs			shale				
	Wyandotte	limestone and shale						
	Lene	shale						
	Iola	limestone and shale						
	Chanute	shale						
	Drum	limestone						
	Quivira	shale						
Kansas City	Westerville	limestone	25'					
	Cherryvale	shale						
	Dennis	limestone and shale						
	Galesburg	shale						
	Swope	limestone						
	Ladore	shale						
	Hertha	limestone						
	Pleasanton	undifferentiated		shale and sandstone, thin coal beds	40'			
	Des Moines	Marmaton		Lenape	limestone	145'		
				Nowata	shale			
Altamont			limestone and shale					
Bandera			shale					
Pawnee			limestone and shale					
Labette			shale					
Cherokee		Fort Scott	limestone	755'				
		undifferentiated	shale, sandstone, thin limestones and coal					

FIG. 3.2



# STRATIGRAPHIC COLUMN OF IOWA

SYSTEM	SERIES	GROUP	FORMATION	DESCRIPTION	THICKNESS	AGE	
					(feet)	(in millions of years before present)	
Mississippian	Meramec		Ste. Genevieve	shale and limestone	140'	355	
			St. Louis	sandy limestone			
			Spergen	limestone			
	Osage		Warsaw	shale and dolomite	250'		
			Keokuk	cherty dolomite and limestone			
			Burlington	cherty dolomite and limestone			
	Kinderhook	North Hill	Gilmore City	limestone, pelitic	300'		
			Hampton	limestone and dolomite			
			Starrs Cave	limestone			100'
			Prospect Hill	siltstone			
			McCraney	limestone			
Devonian	Upper	Yellow Spring	English River	siltstone	300'	410-415	
			Maple Mill	shale			
			Aplington	dolomite			
			Sheffield	shale			
			Lime Creek	dolomite and shale	225'		
			Shell Rock	limestone and dolomite			
	Middle		Cedar Valley	limestone and dolomite	270'		
			Wapsipinicon	limestone and dolomites, shales in middle			
	Lower		La Porte City	chert, limestone and dolomite	50 - 100'		
	Silurian	Niagaran		Gower	dolomite		300'
Hopkinton							
Alexandrian			Kankakee	cherty dolomite	100'		
			Edgewood	sandy dolomite			
Ordovician	Cincinnatian		Maquoketa	dolomite and shale	300'	475	
	Mohawkian		Galena	dolomite and chert	320'		
			Decorah	limestone and shale			
			Platteville	limestone, shale and sandstone	70'		
	Chazyan		St. Peter	sandstone	50 - 230'		
	Beekmantown		Prairie du Chien	sandy and cherty dolomite and sandstone	290'		
Cambrian	St. Croixan	Trempealeau	Madison <sup>a</sup>	sandstone	185'	570	
			Jordan				
			Lodi <sup>a</sup>				
			St. Lawrence				dolomite
		Dresbach	-----	Franconia	glauconitic sandstone, siltstone, shale		160'
				Galesville	sandstone		550'
				Eau Claire	sandstone and shale, dolomite		
				Mt. Simon	sandstone		
Precambrian				sediments (sandstones), igneous, and metamorphic rocks			

<sup>a</sup> recognized only in extreme northeast Iowa

FIG. 3.2



applying the answers to the following questions to the source being used.

Do specifications or special provisions require ledge control? Some materials do, such as coarse aggregate for portland cement concrete and graded stone base.

Does the production history indicate that the finished produce will be boarder line on quality or well within the requirements?

What is the quality level of the beds that might be added to the ledge?

Could additional beds improve a borderline product or cause it to fail?

Could the additional beds be of such poor quality that they should not be incorporated into the manufacture of any product?

Often, all that is necessary is a proper identification of the ledge being worked so as to compile a dependable production history for the source. When in doubt, always consult the appropriate supervisor.

### **Lateral Variations**

Most lateral variations in bed quality are caused by the effects of weathering. Other lateral variations are due to the factors of deposition which were present when the bed was formed. Some geologic units characteristically show very little lateral variation (like the Galena Formation), others show a lot (like the St. Louis Formation). Lateral variations may or may not affect the quality of the bed. Each case has to be evaluated individually.



### **Lateral Variations Due to Weathering**

These can be caused by actual compositional changes in a bed or by changes in a bed or by changes in thickness. A 60.7 mm (0.2 ft.) thick shale bed may increase to a very troublesome 304.8 mm (1 ft.) or more in thickness, requiring benching and removal (Figure 4.1). A limestone or dolomite bed may suddenly pinch out, becoming replaced by sandstone or some other type of rock. This happens frequently in the Meramecian Formations common in southeastern Iowa, but not too often elsewhere.

More common are compositional changes characteristic of those geologic formations which contain breccias, angular fragments of rock in generally shaly matrices (Figure 4.2). Breccia thickness can vary considerably within the same quarry, often affecting beds in the adjacent quarry ledges. At other times, beds will gradually change in composition, becoming more shaly, sandy, etc. Either type of change can affect the quality of the rock.

An inspector must learn and be alert to any changes that can occur that will affect the quality of the finished product.

### **Faulted and Dipping Beds**

Frequently, the quarry beds are not flat lying. They may dip at a uniform angle (Figure 5.1), or they may roll up and down from 0.305 m to 0.607 m (1 ft. to 2 ft.) to commonly as much as 2.438 m (8 ft.) over a lateral distance of 30.48 m (100 ft.) (Figure 5.2). When either situation occurs, a flat lying quarry floor will cut across beds that may not be of the quality level required for the aggregate product becoming made. Proper ledge control might require that a quarry floor be raised, lowered, or worked





Figure 4.1




Figure 4.2  
246






Figure 5.1




Figure 5.2



at an angle in order to insure the production of complying material.

True faults, fractures in bedded rock accompanied by differential movement in the fault zone, are not common, but there are a few. A quarry ledge transgressing a fault will suddenly be working different beds depending on the amount of movement that occurred along the fault (Figure 5.3). This can be a problem depending on the nature of new beds incorporated into the ledge. Often, large blocks will exhibit minor slippage along the vertical joints and appear as small faults in a quarry face. These are the most common in the Galena and Cedar Valley Formations, massive rock units with well developed joint systems.

### **Deleterious Materials**

Ground water moving along vertical joints and horizontal bedding planes has often left large void spaces in the rock. These are frequently filled with clay or other materials that were available to the moving ground water (Figure 6.1). Occasionally so much foreign material will be in the rock that it cannot be used for aggregate purposes. Some rock became contaminated with clay or shale during deposition. This is the case with the Silurian reefs found in eastern Iowa. Ordinarily, the rock is of high quality, but the contained clay pockets can become very troublesome (Figure 6.2). The clay content of aggregate being produced from this type of rock should be monitored closely when there are limits placed on clay lumps, clay balls, etc.

### **Production Changes**

Some products can be made at certain quarries only by beneficiating or treating the material in order to improve its properties during the manufacturing process. For instance, when a quarry ledge






Figure 5.3






Figure 6.1






Figure 6.2







consists of beds with argillaceous partings on the bedding planes, the removing or scalping of the minus 19 mm (3/4 in.) from the primary crusher may remove enough of this material to substantially improve the soundness of the final product. These situations should be documented in the source files, so that any future production employs equal or better methods of product beneficiation.

### **Sand and Gravel Pits**

Sand and gravel pits are granular deposits located in areas where moving water has concentrated the sand and gravel-size particles in sufficient quantity. They are generally in or adjacent to the many streams and rivers in Iowa or in glacial outwash deposits where the melting ice had generated the water flow necessary to form sand and gravel deposits. There are many factors which can cause quality changes in sand and gravel pits, but only the main points will be covered.

Flowing water deposits material only in relation to the load it carries (always changing) and its velocity and direction. Most deposits are accumulations over long time periods under a variety of conditions. Consequently, the deposit can be alternately coarse or fine, dirty or clean. Thus a greater degree of dependence is placed on the production methods and equipment to give a uniform quality product than in the case of crushed stone. Any change in production equipment or methods, in the area or depth of working, or in the appearance of the product should be noted since any one could signal a changed quality level in the final product. Most gravel coarse aggregate perform only moderately well in pavement because, despite containing relatively high percentages of extremely durable igneous materials. They also contain significant

*Sand- Granular material almost entirely passing the No. 4 sieve and predominantly retained on the No. 200 sieve.*



**Gravel Pit Face:** Note how the gravel is deposited in layers of coarse and fine with areas containing high shale, etc. Important for the producer to process this type of source properly to maintain consistent quality and gradation (i.e. using a dozer to work the entire exposed face to blend the material before it is processed at the plant.




percentages of good to poor quality limestone, and of course, the cherts, iron spalls, shale particles, and other objectionable materials that frequently cause gravel pavements to have a poor appearance. Held within the specified limits, the objectionable materials will not affect the durability of pavement.

The quality of the limestone fraction, however, can affect the durability of pavement. Consequently, very few gravel coarse aggregates comply with the durability requirements for use in pavements on the primary highway system. When necessary, gravel coarse aggregates can be separated and tested according to rock type using a modification of the ASTM Standard Recommended Practice for Petrographic Examination of Aggregates for Concrete. This can be extremely helpful in identifying the types and amounts of poor quality materials present.



# NOTES









April 25, 2000  
Supersedes May 1995

Mats. I.M. 104

---

## **FIELD EQUIPMENT CLEANING, CALIBRATION, AND REPAIR** **(General Rewrite)**

### **GENERAL**

Various items of field-testing equipment require periodic calibration to ensure reliable results. Specific items requiring calibration are balances and weights, concrete air meters, and concrete beam testing machines, etc.

The Central Materials Laboratory of the Iowa Department of Transportation will, when possible, calibrate and repair testing equipment for county and municipal governments and private organizations when certified technicians are required.

### **COUNTY & MUNICIPAL GOVERNMENTS**

County owned equipment will be cleaned, calibrated and repaired as time permits. For any necessary repair parts, cleaning, etc., the county will be billed. If extensive repair or modification to equipment is required, the county will be billed for parts and labor. Prior to any extensive repair, the County Engineer will be notified with an estimate of the cost and his authorization to proceed must be received prior to the work.

Municipal governments that have projects involving state or federal funding may also have their equipment cleaned, calibrated, and repaired. Charges shall be the same as those imposed upon counties.

### **PRIVATE ORGANIZATIONS**

Testing equipment owned by private organizations will be cleaned, calibrated, and repaired when the Department of Transportation requires that certified technicians be utilized. A charge will normally be made when calibrating or repairing this equipment. Extensive repairs will be billed at actual cost plus labor charges. Prior to extensive repairs the organization will be notified with an estimate of the cost and authorization to proceed must be received prior to the work.

### **NON-STANDARD EQUIPMENT**

The Department of Transportation is not responsible for repairing equipment that is not normally used by the Department and for which replacement parts are not normally stocked by the Central Laboratory.

### **BILLING PROCEDURE**

Upon written notification from, the Office of Materials, the Office of Accounting will bill the appropriate agency or organization.

---



---

**CHARGES FOR CLEANING, CALIBRATION,  
AND REPAIR OF TESTING EQUIPMENT**


<b>ACTIVITY</b>	<b>FEE</b>
Cleaning and Checking of Sieves	\$4.50 each or \$30.00 per set (8-inch) \$9.00 each or \$60.00 per set (12-inch)
Cleaning, Repair, and Checking of Balances	\$30.00 each, plus cost of parts*
Repair and Calibration of Concrete Beam (Flexural Test) Machines	\$50.00 each, plus cost of parts*  Rental is \$100 per month or any part thereof. Includes use by cities & counties, contractors, and consultants.
Cleaning and Repair of PCC Air Meters	<del>\$35.00 for sandblast cleaning, plus parts.</del>
Calibration of Air Meters	<del>\$35.00</del>
Cleaning of Slump Cones	\$25.00 each

**\*NOTE:** The cost of parts includes an additional 7.5 percent for overhead.



# NOTES







---

**METHOD OF TEST**  
**DETERMINATION OF THE AMOUNT OF SHALE IN FINE AGGREGATE**  
**FIELD PROCEDURE OF IOWA TEST METHOD 209**

**SCOPE**

This test method covers the procedure for the approximate determination of the shale content in fine aggregate.

**PROCEDURE****A. Apparatus**

1. Balance having a capacity of not less than 1000 g and sensitive to at least 0.1 g
2. A strainer with openings smaller than 1.18 mm (#16 sieve)
3. Two bowls of sufficient capacity
4. A solution of zinc chloride ( $\text{ZnCl}_2$ ) having a specific gravity between 1.950 and 1.999 at 21°C (70°F)

**NOTE:** To prepare one gallon of solution, slowly add 5670 g (12.5 lb.) of technical grade zinc chloride to 2248 g (4.75 pt.) of water with constant stirring. The zinc chloride is added slowly to all the needed water to avoid generating excessive heat during the dissolving process. When all zinc chloride is in solution, cool to 21°C (70°F) and measure specific gravity with a hydrometer. If the sp. gr. is below 1.95, add zinc chloride in 227 g (0.5 lb.) increments until the sp. gr. of the solution is at least 1.95 at 21°C (70°F). It may be necessary to heat the original solution slightly in order to dissolve additional zinc chloride in a reasonable time.

5. Drying oven or hot plate
6. Mixing spoon

**B. Sample Preparation**

1. Obtain a representative sample by appropriate methods detailed in Materials I.M. 301 and 336.
  2. Dry the test sample to a constant weight, allow to cool, weigh, and record. When the material includes aggregate retained on and above the 4.75mm (#4) sieve, the representative sample shall be large enough to yield at least 500 grams of dry material passing the 4.75mm (#4) sieve.
  3. Sieve the test sample over the 1.18mm (#16) sieve. Discard the material passing
-



~~X~~ this sieve and subject the test sample to the test procedure. The test sample for P.C. concrete fine aggregate is the total material retained on the 1.18 mm (#16) after the fine aggregate sieve analysis has been completed, which could include +4.75 mm (+#4) materials. The test sample for asphalt fine aggregate is the quantity of -4.75 mm (-#4) materials retained on the 1.18 mm (#316) sieve after sieve analysis.

### C. Test Procedure

1. Pour the zinc chloride solution into a mixing bowl until the volume of the liquid is at least 3 times the absolute volume of aggregate.

**CAUTION:** There is no particular hazard from the fumes of the zinc chloride solution, but protective clothing should be worn. This includes gloves, goggles, and face shield. Mix in a well-ventilated area.

2. Stir the fine aggregate sample into the solution until all particles are coated.
3. Pour the liquid off into a second container, passing it through the strainer. Make sure that only the floating pieces are poured off and that none of the fine aggregate is decanted onto the skimmer.
4. Return to the first container the liquid that has been collected in the second container and after further agitation of the sample by stirring, repeat the decanting process just described until the sample is free of floating pieces.
5. Thoroughly wash the removed particles in the strainer to remove the zinc chloride. Dry to a constant mass (weight) in an oven at a temperature of  $110 \pm 5^{\circ}\text{C}$  ( $230 \pm 9^{\circ}\text{F}$ ) or on a hot plate at a low heat setting. Weigh to the nearest 0.1 g.

### D. Calculations

1. Calculate the percentage of shale (and other low specific gravity materials) by the following formula:

$$\% \text{ Shale} = \frac{\overset{\text{shale}}{\text{Dry Mass (Weight) of Washed Decanted Particles}}}{\underset{\text{whole sample}}{\text{* Dry Mass (Weight) of Original Sieve Analysis Sample}}} \times 100$$


\* This mass (weight) includes the material passing the 1.18 mm (#16 sieve) and represents the total sample mass (weight) of the fine aggregate.

.170



# NOTES







May 2, 1997  
Supersedes November 1992

Matls. I.M. 345

---

**METHOD OF TEST**  
**DETERMINATION OF THE AMOUNT OF SHALE IN COARSE AGGREGATE**  
**FIELD PROCEDURE OF IOWA TEST METHOD 210**

**SCOPE**

This test method covers the procedure for the approximate determination of the shale content in coarse aggregate. This method separates, along with the shale, other particles of low specific gravity.

**PROCEDURE**

**A. Apparatus**

1. Balance having a capacity of at least 2500 g and sensitive to 0.1 g
2. A strainer with openings not larger than 2.36 mm (#8 sieve)
3. Two bowls of sufficient capacity
4. A solution of zinc chloride ( $\text{ZnCl}_2$ ) having a specific gravity between 1.950 and 1.999 at 21°C (70°F).

NOTE: To prepare one gallon of solution, slowly add 5670 g (12.5 lb.) of technical grade zinc chloride to 2248 g (4.75 pt.) of water with constant stirring. The zinc chloride is added slowly to all the needed water to avoid generating excessive heat during the dissolving process. When all zinc chloride is in solution, cool to 21°C (70°F) and measure specific gravity with a hydrometer. If the sp. gr. is below 1.95, add zinc chloride in 227 g (0.5 lb.) increments until the sp. gr. of the solution is at least 1.95 at 21°C (70°F). It may be necessary to heat the original solution slightly in order to dissolve additional zinc chloride in a reasonable time.

5. Drying oven or hot plate
6. Mixing spoon

**B. Test Procedure**

1. A sample of approximately 2500-grams of + 4.75 mm (+ #4) material shall be selected by quartering or splitting to insure representation.



2. Dry the sample to a constant mass (weight) in an oven at a temperature of  $110 \pm 5^{\circ}\text{C}$  ( $230 \pm 9^{\circ}\text{F}$ ) or on a hot plate at low heat setting with frequent stirring to avoid local overheating. Weigh to the nearest 0.1 g.

**CAUTION:** There is no particular hazard from the fumes of zinc chloride solution, but protective clothing should be worn. This includes gloves, goggles, and face shields. Mix in a well-ventilated area.

3. Place the dried sample of aggregate in the bowl and pour the solution of zinc chloride over the aggregate until the volume of the liquid is at least 3 times the absolute volume of the aggregate.
4. Agitate the aggregate by vigorously stirring with a large mixing spoon until no additional pieces float to the surface.
5. Skim off the floating particles within one minute.
6. Thoroughly wash the removed particles in the strainer to remove the zinc chloride. Dry to a constant mass (weight) in an oven at a temperature of  $110 \pm 5^{\circ}\text{C}$  ( $230 \pm 9^{\circ}\text{F}$ ) or on a hot plate at a low heat setting. Weigh to the nearest 0.1 g.
7. Particles of low specific gravity other than shale may be handpicked and removed prior to weighing.

#### C. Calculation

1. Calculate the percentage of shale (or shale and other low specific gravity materials) from the following formula:

$$\% \text{ Shale} = \frac{\text{Dry Mass (Weight) of Washed Decanted Particles}}{\text{* Dry Mass (Weight) of Sample}} \times 100$$

\* Mass (weight) of the + 4.75 mm (+ #4) material



# NOTES







# Appendix A:

## Forms







### Aggregate Sieve Analysis

(Coarse or fine using Box and 203 mm (8 in.) Sieves; or 305 mm (12 in.) Sieves)

1. Obtain a field sample (per I.M. 301)
2. Reduce the field sample (per I.M. 336) to the proper test sample size listed in I.M. 301.
3. When required to determine the percent passing the 75  $\mu\text{m}$  (#200) sieve, or when testing a Fine Aggregate sample, dry the test sample to a constant mass (weight).  
(Note: A second (smaller) sample of coarse aggregate may be obtained (per I.M. 336) from the field sample to test for the percent passing the 75  $\mu\text{m}$  sieve. See I.M. 306 for the appropriate sample size. In this case, the larger sample of coarse aggregate needs only to be in a "surface-dry" condition when sieving down through the 2.36 mm (#8) screen).
4. Cool the sample if dried to a constant mass, weigh and record as the Original Dry Mass.
  - 4a. When testing for the percent passing the 75  $\mu\text{m}$  sieve, wash the entire sample over a 75  $\mu\text{m}$  wash sieve per I.M. 306.
  - 4b. Dry the washed sample to a constant mass, cool, weigh, and record as Dry Mass Washed.
  - 4c. Determine washing loss and record in both places on worksheet.
5. Place the sample in the appropriate sieves and sieve to completion:
  - Coarse Aggregate in box sieves, 37.5 mm through 2.36 mm (1 ½ in. through #8)
  - Fine Aggregate in 203 mm or 305 mm round sieves, 9.5 mm through 75  $\mu\text{m}$  (3/8 in. through #200)
  - Combined or Fine Aggregate in 305 mm sieves, 25 mm through 75  $\mu\text{m}$  (1 in. through #200)

(Note the largest sieve size needed in any case is dependent on the maximum particle size in the sample).
6. Clean the retained material from each sieve, weigh, and record each increment to the nearest 0.5 gram saving each increment individually until the entire test procedure is completed.



7. Add the mass retained column, including the washing loss and pan if the sample was washed. Check weighing accuracy by dividing the total by the original mass x 100 (and/or the total minus the washing loss divided by the dry mass washed x 100 if the sample was washed).
8. Calculate the percent retained for each sieve by dividing the mass retained on each sieve by the Original Dry Mass x 100. Remember to combine the washing loss and pan for this calculation if sample was washed.
9. Add the percent retained column, prorating as needed, to equal 100 %.
10. Determine the percent passing each sieve by consequently subtracting the percents retained starting with the sieve that had 100 % passing (the smallest sieve used which had no material retained).



**Coarse Aggregate Wash Sample**  
**(Percent passing 75  $\mu$ m sieve only)**

1. Dry the sample to a constant mass, cool, weigh, and record as Original Dry Mass (at the bottom of the worksheet).
2. Wash the sample over the 75 mm sieve per I.M. 306.
3. Dry the washed sample to a constant mass, cool, weigh and record as Dry Mass Washed.
4. Determine the Washing Loss and record in appropriate places on worksheet.
5. Screen the sample over a box 2.36 mm sieve, discarding the material retained on the 2.36 mm sieve.
6. Place the minus 2.36 mm material in a nest of round sieves (300  $\mu$ m, 150  $\mu$ m, and 75  $\mu$ m) and pan.
7. Place the nest of sieves in a mechanical shaker (or sieve by hand) until sieving to completion is achieved (usually 5 minutes in a mechanical shaker).
8. Weigh and record only the material retained in the pan.
9. Combine the Washing Loss and Pan masses and divide by the Original Dry Mass x 100.
10. Record as percent passing the 75  $\mu$ m sieve.

(Now it is safe to discard your sample increments)



**Combined Aggregate Sieve Analysis**  
**(With Box and Round 203 mm (8 in.) diameter sieves)**

**Phase 1**

1. Obtain a field sample (per I.M. 301).
2. Reduce the field sample (per I.M. 336) to the proper test sample size listed in I.M. 301.
3. Dry the test sample to a constant mass (weight), allow to cool, weigh to nearest 0.5 gram and record as Original Dry Mass.
4. Wash the sample over the 75  $\mu$ m wash sieve (per I.M. 306).
5. Dry the washed sample to a constant mass, cool, weigh and record the mass as the Dry Mass of Washed Sample.
6. Determine the Washing Loss and record in both locations on worksheet.
7. Sieve the sample through the required box sieves finishing with the 4.75 mm (#4) or 2.36 mm (#8).
8. Clean the retained material from each sieve; weigh and record each increment (record in the second column of worksheet), saving each increment individually until the entire test procedure is completed.

**Note: At this point technician must decide if the amount of material passing the 4.75  $\mu$ m or 2.36  $\mu$ m box sieve will create an overload situation on any of the 203 mm sieves (over 200 grams on a sieve).**

**Phase 2 (Overload not anticipated)**

1. Place the minus 4.75 mm (or 2.36 mm) material in the nest of 203 mm round sieves and sieve in the mechanical shaker for a period long enough to obtain sieving to completion (usually 10 minutes).
2. Clean the retained material from each sieve; weigh and record each increment (record in the second column of worksheet), saving each increment individually until the entire test procedure is completed.
3. Add the entire mass retained column including the pan and washing loss
4. Determine the weighing accuracy ( $\pm 0.5\%$ )



5. Calculate the percent retained on each sieve (individual mass + dry mass x 100) to nearest 0.1%. (Remember to combine the washing loss and pan for this calculation)
6. Total the percent retained column, prorating as necessary, to equal 100%.
7. Calculate the percent passing each sieve by consecutively subtracting the percent retained, starting with the sieve that had 100% passing (the smallest sieve used which had no material retained).
8. The percent passing the 75  $\mu\text{m}$  (#200) sieve must equal the last result obtained in the percent retained column.

**Phase 2 (overload on 203 mm sieves anticipated)**

1. Weigh and record the material passing the 4.75 mm box sieve as the total minus 4.75 mm mass (W1).
2. Reduce the material passing the 4.75 mm box sieve using the 25 mm (1 in.) sample splitter (a smaller splitter may be used if available). **The minimum mass of the reduced sample is 500 grams.**
3. Weigh and record the reduced minus 4.75 mm material as the reduced minus 4.75 mm mass (W2).
4. Divide W1 by W2 and record as conversion factor (four places to the right of the decimal point).
5. Place the reduced sample into the nest of 203 mm sieves (starting with the 2.36 mm sieve) and sieve in the mechanical sieve shaker for a period long enough to obtain sieving to completion (usually 10 minutes).
6. Clean the retained material from each sieve; weigh and record each increment (record in first column on worksheet), saving each increment individually until the entire test procedure is completed.
7. Add the column including the pan (excluding the washing loss) and check weighing accuracy by dividing the column total by the W2 weight ( $\pm 0.5\%$  tolerance).
8. Multiply each mass retained (B) including the pan by the conversion factor and record the result in the second column (A) to the nearest 0.1%.
9. Add the entire second column (including the masses retained on the +4.75 mm sieves and washing loss).



10. Divide this total by the Original Dry Mass of Sample x 100. The result must be within  $\pm 0.5\%$ .
11. Divide each mass retained in this column (second column) by the Original Dry Mass of Sample x 100 and record in the percent retained to the nearest 0.1%.
12. Add the percent retained column, prorating as needed to equal 100%.
13. Determine percent passing each sieve by consecutively subtracting the percents retained starting with the sieve that had 100% passing.
14. The percent passing the 75  $\mu\text{m}$  sieve must equal the last result obtained in the percent retained column.

(Now it is safe to discard your sample increments)



Form 821278  
12/92

# IOWA DEPARTMENT OF TRANSPORTATION

## CERTIFIED GRADATION TEST REPORT

- ☐ Certified Sample  
☒ Monitor Sample  
☐ Verification Sample

County: Delaware  
Project: WHS  
Contractor: \_\_\_\_\_  
Contract #: \_\_\_\_\_  
Design: \_\_\_\_\_  
Date: Oct. 27, 2000 Report No.: 3

Source Name Tegler Pit T-203A No. A28504 Source Location NE Sec 36 Twp 89 Range w2 County Delaware

Material Concrete Sand Class \_\_\_\_\_ Gradation No 1 Beds \_\_\_\_\_

Material Producer BARD Concrete Company Destination Stockpile Sampled At Pit 10-5,13,19

Date Sampled	Sample Identification	Sampled By	Tested By	Sieve Analysis										Percent Passing				Other Test Results				Comp	Tons
				37.5mm (1 1/2in)	26.5mm (1.00in)	19mm (3/4in)	13.2mm (0.50in)	9.5mm (3/8in)	4.75mm (No. 4)	2.36mm (No. 8)	1.18mm (No. 16)	600µm (No. 30)	300µm (No. 50)	150µm (No. 100)	75µm (No. 200)								
* Production Limits			Max.					100	100	100		54			1.5								
			Min.						90	70					0								
Oct. 5	DL-192-00	DOT	Like					100	97	85	68	44	15	1.7	0.4								
Oct. 5	T18-00	Producer	S.L.					100	94	83	64	42	15	1.3	0.2								
Oct. 13	DL-197-00	DOT	Like					100	97	86	68	45	16	1.9	0.4								
Oct. 13	T21-00	Producer	L.M.					100	96	84	67	44	15	1.2	0.2								
Oct. 19	DL-202-00	DOT	Like					100	97	90	76	49	15	1.5	0.4								
Oct. 20	T23-00	Producer	S.L.					100	96	86	70	46	16	1.5	0.4								

Note to County and Resident Engineers- If County or Project Number is incorrect, please notify Inspector and Ames Office promptly. Corrected Reports will be issued.

Comments Bard Concrete Company  
Roger Boulet  
\_\_\_\_\_  
File

District 6 personnel have made a comparison of gradations. No significant difference exists between these results.

\*AGREED by the Contractor/producer

Distribution: Materials Engr.; Project Engr.; Certified Technician; Area Inspector

ESTIMATED QUANTITY 0 TONS

TOTAL PREVIOUSLY CERTIFIED 30,000 TONS

TOTAL CERTIFIED TO DATE 42,000 TONS

CERTIFICATION NUMBER EC222

Reported By Don Like

Representing Iowa DOT



## IOWA DEPARTMENT OF TRANSPORTATION

## CERTIFIED GRADATION TEST REPORT

☒ Certified Sample☐ Monitor Sample☐ Verification SampleCounty: JasperProject: Im-80-561p4)1160-13-5Contractor: Mancini's

Contract #:

Design:

Date: 7/24/00Report No.: 36Source Name #552 Colfax T-203A No. A50502 Source Location NE Sec 01 Twp 79 Range 21W County 50Material Concrete Sand Class \_\_\_\_\_ Gradation No 1 Beds \_\_\_\_\_Material Producer Van Dusseldorp S&G Destination \_\_\_\_\_ Sampled At Colfax Plant

Date	Sample	Sampled	Tested	Sieve Analysis										Percent Passing				Other Test Results			
Sampled	Identification	By	By	37.5mm (1 1/2in)	25.0mm (1.00in)	19mm (3/4in)	13.2mm (0.50in)	9.5mm (3/8in)	4.75mm (No. 4)	2.36mm (No. 8)	1.18mm (No. 16)	600µm (No. 30)	300µm (No. 50)	150µm (No. 100)	75µm (No. 200)				Comp	Tons	
			* Production Limits	Max.					100	100		50			1.0						
				Min.				100	90	70		10			0						
7/17/00 CCC00-0258 CC CC				Local Area				100	99	91	75	46	12	1.7	0.4					1500	
7/18/00 CCC00-0267 CC CC				"				100	99	91	75	46	12	1.2	0.3					1500	

Note to County and Resident Engineers- If County or Project Number is incorrect, please notify inspector and Ames Office promptly. Corrected Reports will be issued.

Comments Copies: Materials Eng.  
Van Dusseldorp  
Mancini's  
Des Moines Lab  
CC

ESTIMATED QUANTITY 3000 0 TONSTOTAL PREVIOUSLY CERTIFIED 33,750 0 TONSTOTAL CERTIFIED TO DATE 36,750 0 TONSCERTIFICATION NUMBER CI 906Reported By Charlotte CunninghamRepresenting Van Dusseldorp Sand & Gravel

\*AGREED by the Contractor/producer

Distribution: Materials Engr.; Project Engr.; Certified Technician; Area Inspector



## PCC Plant Report

Project No.: STPN-3-6(29)--2J-09  
 Plant Name: Croell - Waverly  
 Contractor / Sub: PCI/CFI  
 Weather: Sunny-Cool

Contract ID.: 09-0036-029  
 County: Bremer  
 Temp. (°F) Min.: 65  
 Temp. (°F) Max.: 75

Report No.: 1  
 Date This Report: Aug. 31, 00  
 Date Of Last Report: Aug. 30, 00  
 Design No.: \_\_\_\_\_

Check Mix (x)	Check Type (x)	
Central	Paving	X (Send Daily or End of Lot)
Ready	Structure	(Send Weekly or End of Lot)
	Incidental	(Send Weekly or End of Lot)
	Patching	(Send Weekly or End of Lot)

Date Mo / Day	Mix Number	Time		Batched ( CY )	% of Est. Used	Fine Aggregate			Coarse Aggregate			Actual Quantities Used Per CY ( in pounds )							Avg. W/C Ratio	Max. W/C Ratio
		Moist. (%)	T-203 Sp. G.			Dry Wt. (lbs)	Moist. (%)	T-203 Sp. G.	Dry Wt. (lbs)	Cement	Fly Ash	Fine	Coarse	Water						
		Start	Stop													In Agg.	Plant	Grade		
31-Aug	C4WRC20	07:26	02:49	506.00	101.2	2.6	2.66	1510.0	0.2	2.65	1500.0	474.0	119.0	1550.0	1503.0	43.0	207.0	3.0	0.427	0.489
																			0.000	
																			0.000	
																			0.000	
																			0.000	
																			0.000	
																			0.000	
																			0.000	

C	Sieve Accuracy= 99.8%					Sieve Accuracy= 0.0%				Sieve Accuracy= 0.0%						
O	Orig. Dry Weight ( OD Wt.):					6924.2	Orig. Dry Weight ( OD Wt.):				Orig. Dry Weight ( OD Wt.):					
A	Dry Wt. Washed ( D Wt. W.):						Dry Wt. Washed ( D Wt. W.):				Dry Wt. Washed ( D Wt. W.):					
R	Sieve Size	Wt. Retd.	% Retd.	% Retd.	% Psg.	Wt. Retd.	% Retd.	% Retd.	% Psg.	Wt. Retd.	% Retd.	% Retd.	% Psg.	Specs.	Avg.	
S	1 1/2 "		0.0		100.0		0.0		0.0		0.0		0.0	100	0	
E	1 "		0.0		100.0		0.0		0.0		0.0		0.0	95-100	0	
	3/4 "	1731.4	25.0		75.0		0.0		0.0		0.0		0.0		0	
S	1/2 "	1710.0	24.7		50.3		0.0		0.0		0.0		0.0	25-60	0	
A	3/8 "	1796.9	26.1		24.2		0.0		0.0		0.0		0.0		0	
M	#4	1251.2	18.1		8.1		0.0		0.0		0.0		0.0	0-10	0	
P	#8	317.4	4.6		1.5		0.0		0.0		0.0		0.0	0-5	0	
L	Pan	103.8	1.5				0.0				0.0					
E	Total	6910.7	100.0			0.0	0.0			0.0	0.0					
W	#200				0.9				0.0				0.0	0-1.5	0	
a	Wash Loss	15.3	OD Wt.: 3020.6			0.0	OD Wt.: _____			0.0	OD Wt.: _____					
s	Pan	10.5	D Wt. W.: 3005.3				D Wt. W.: _____				D Wt. W.: _____					
h	Total	25.8				0.0				0.0						

Sieve Accuracy= 100.0%					Sieve Accuracy= 0.0%					Sieve Accuracy= 0.0%						
		Orig. Dry Weight:		617.3			Orig. Dry Weight:					Orig. Dry Weight:				
		Dry Wt. Washed:		615.7			Dry Wt. Washed:					Dry Wt. Washed:				
		Washing Loss:		1.6			Washing Loss:		0.0			Washing Loss:		0.0		
F I N E S A M P L E	Sieve Size	Wt. Retd.	% Retained	% Passing	Wt. Retd.	% Retained	% Final	% Passing	Wt. Retd.	% Retained	% Final	% Passing	Specs.	Avg.		
	3/8 "		0.0	100.0		0.0				0.0			100	0		
	#4	13.7	2.2	97.8		0.0		0.0		0.0		0.0	90-100	0		
	#8	50.7	8.2	89.6		0.0		0.0		0.0		0.0	70-100	0		
	#16	109.5	17.7	71.9		0.0		0.0		0.0		0.0		0		
	#30	172.4	27.9	44.0		0.0		0.0		0.0		0.0	10-60	0		
	#50	197.0	32.0	12.0		0.0		0.0		0.0		0.0		0		
	#100	66.8	10.8	1.2		0.0		0.0		0.0		0.0		0		
	#200	5.2	0.8	0.4		0.0		0.0		0.0		0.0	0-1.5	0		
	Wash	1.6	0.4			0.0	0.0			0.0	0.0					
	Pan	0.7														
	Total	617.6	100.0			0.0	0.0			0.0	0.0					
	Sample ID:		BC2700			(ID):					(ID):					
Tested By / Cert. No.:		Bill Croell NE463			(TB/CN):					(TB/CN):						

Distribution: \_\_\_\_\_ Central Materials \_\_\_\_\_ TC Materials \_\_\_\_\_ Res. Engineer \_\_\_\_\_ Contractor \_\_\_\_\_ Plant \_\_\_\_\_

Batched			
Check One (x):	Today	Week	To Date Total
Concrete (CY):	506.00		506.00
Cement (Tons):	119.65		119.65

Brand / Source	Rate	Lot No.
Air Ent: DV1000		CF06-183-22
Wat. Red: WRDA82		CF05-A178-49
Retarder:		
Cal Chlor:		
Superplas:		

Concrete Treatment (x)	lbs / CY
Ice	
Heated Water	
Heated Materials	

Type	Sp. Gr.	Source
Cement:		
Fly Ash:		

T-203 A - #	Grad. #
Rock:	
Sand:	

Remarks

C.P.I.: Bill Croell  
 Monitor: Lee Dahlin

Cert. No.  
NE463  
NE113



## DAILY ACC PLANT REPORT

Project No.: NHS-6-3(41)--12-77  
 Contract ID: 77-0006-41  
 Mix Design No.: ABD8-1007

Contractor: Quality Asphalt, Inc.  
 County: POLK  
 Recycle Source: \_\_\_\_\_

Class: \_\_\_\_\_  
 Size: 19 mm  
 Mix Type: A Superpave

Report No.: 1  
 Design Blows: \_\_\_\_\_  
 Design Gyration: 109

Hot Box I.D. No.:		SU6-18A	SU6-18B	SU6-18C	SU6-18D		Time	7:00	9:00	11:00	1:00	3:00	5:00	7:00	
Date Sampled:		06/18/98	06/18/98	06/18/98	06/18/98		Air Temp. °C	14	17	21	22	22	20	20	
Gradation ID:	Specs	GRAD 1-A	GRAD 1-B				A.C. Temp. °C	150	152	151	153	155	150	150	
1 in. (25mm) Sieve	100	100	100				Mix Temp. °C	145	155	159	151	145	148	150	
3/4 in. (19mm) Sieve	90-100	99	100				Date Placed: <u>06/18/98</u> Date Tested: <u>06/19/98</u> Course Placed: <u>surface</u> Tested By: <u>John Rayson</u>								
1/2 in. (12.5mm) Sieve	83-90	89	89												
3/8 in. (9.5mm) Sieve	76-90	76	77												
* #4 (4.75mm) Sieve	43-57	47	48												
* Moving Average							Density Record								
* #8 (2.36mm) Sieve	23-35	29	30												
* Moving Average															
#16 (1.18mm) Sieve		19	19												
* #30 (600um) Sieve	7-15	13	12				Core No.:	1	2	3	4	5	6	7	
* Moving Average							Station	110+66	144+35	166+81	198+45	212+16	238+77	254+75	
#50 (300um) Sieve		7.6	7.3				CL Reference	1.0 RT	1.0 LT	2.8 LT	1.9 RT	2.8 LT	1.0 RT	2.8 RT	
#100 (150um) Sieve		5.4	4.7				W 1 Dry	1,205.5	1,236.6	1,388.5	1,279.4	1,145.5	1,401.2	1,215.8	
* #200 (75um) Sieve	2.0-5.3	4.2	3.6				W 2 in H2O	685.9	701.6	799.6	736.1	648.2	795.5	696.1	
* Moving Average							W 3 Wet	1,206.6	1,238.1	1,389.6	1,280.9	1,147.0	1,402.5	1,217.1	
Compliance (Y/N)							Difference	520.7	536.5	590.0	544.8	498.8	607.0	521.0	
Intended Added, % AC	5.40						Field Density	2.315	2.305	2.353	2.348	2.297	2.308	2.334	
Actual Added, % AC		5.28					% Density	97.638	97.216	99.241	99.030	96.879	97.343	98.439	
Intended Total, % AC	5.40						% Voids	6.5	6.9	5.0	5.2	7.2	6.8	5.7	
Actual Total, % AC		5.28					Thickness (mm)	40	45	50	45	35	50	45	
Gmb:		2.373	2.365	2.375	2.371		Gmb (Lot Avg.):	2.371			Avg. Field Density:				2.323
Gmm:		2.469	2.477	2.480	2.478		Gmm (Lot Avg.):	2.476			Avg. % Density:				97.969
Pa:		3.9	4.5	4.2	4.3		Dist. Labs Pa:				Avg. % Field Voids:				6.2
Moving Average	3.5-5.0						Target % RAP:	NA			Specified % Density:				95
Time		7:05 AM	8:35 AM	1:30 PM	4:55 PM	This	Q.I. = $\frac{2.323}{0.022} - \frac{2.252}{0.022} = 3.21$								
Station		112+55	134+22	189+98	244+55	Column									
Side		WB	WB	WB	WB	Is For									
Sample Mg's		118.00	504.00	2,374.00	3,160.00	Dist. Lab									
Sublot Mg's		500.00	1,100.00	1,100.00	1,105.24	Test									
Mg's to Date						Results									
Fines / Bitumen Ratio	0.6-1.4	1.13													

Gsb: 2.577      Gb: 1.0240      Effective % AC: 3.71

Mix Change Information: \_\_\_\_\_

Distribution: \_\_\_\_\_ Central Materials \_\_\_\_\_ TC Materials \_\_\_\_\_ Proj. Engineer \_\_\_\_\_ Contractor \_\_\_\_\_ Plant \_\_\_\_\_

Certified Tech: Ray Johnson  
 Certified Tech: John Rayson

c1213      Cert. No.  
 c1312      Cert. No.



# Notes







# Notes







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:	1		
Material:	FINE AGGREGATE-PCC	Grad. No.:	1
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	511.3	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	509.0	Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)		19.1			
2.36mm (8)	(B)	98.3 (A)			
1.18mm (16)	(B)	124.0 (A)			
600µm (30)	(B)	160.9 (A)			
300µm (50)	(B)	77.2 (A)			
150µm (100)	(B)	22.6 (A)			
75µm (200)	(B)	7.3 (A)			
Wash		2.3			
Pan	(B)	0.4 (A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass Retd.	% Retd.	% Passing	Specs.	
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:

Lab. No.:	2		
Material:	FINE AGGREGATE-PCC	Grad. No.:	1
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	542.0	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	539.6	Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			


Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	101.3 (A)			
1.18mm (16)	(B)	160.7 (A)			
600µm (30)	(B)	179.0 (A)			
300µm (50)	(B)	80.0 (A)			
150µm (100)	(B)	10.9 (A)			
75µm (200)	(B)	5.8 (A)			
Wash		2.4			
Pan	(B)	0.3 (A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass Retd.	% Retd.	% Passing	Specs.	
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:	1		
Material:	FINE AGGREGATE-PCC	Grad. No.:	1
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	511.3	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	509.0	Reduced Minus 4.75 mm (W2):	
Washing Loss:	2.3	Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)				100.0	100
4.75mm (4)		19.1	3.7	96.3	90-100
2.36mm (8)	(B)	98.3 (A)	19.2	77.1	70-100
1.18mm (16)	(B)	124.0 (A)	24.3	52.8	
600µm (30)	(B)	160.9 (A)	31.5 (31.4)	21.4	10-60
300µm (50)	(B)	77.2 (A)	15.1	6.3	
150µm (100)	(B)	22.6 (A)	4.4	1.9	
75µm (200)	(B)	7.3 (A)	1.4	0.5	0-1.5
Wash		2.3	0.5		
Pan	(B)	0.4 (A)			
Total		512.1	100.1 (100.0)		
Tolerance		100.2			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_

Lab. No.:	2		
Material:	FINE AGGREGATE-PCC	Grad. No.:	1
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	542.0	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	539.6	Reduced Minus 4.75 mm (W2):	
Washing Loss:	2.4	Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			


Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					100
4.75mm (4)				100.0	90-100
2.36mm (8)	(B)	101.3 (A)	18.7 (18.8)	81.2	70-100
1.18mm (16)	(B)	160.7 (A)	29.6 (29.7)	51.5	
600µm (30)	(B)	179.0 (A)	33.0 (33.1)	18.4	10-60
300µm (50)	(B)	80.0 (A)	14.8	3.6	
150µm (100)	(B)	10.9 (A)	2.0	1.6	
75µm (200)	(B)	5.8 (A)	1.1	0.5	0-1.5
Wash		2.4	0.5		
Pan	(B)	0.3 (A)			
Total		540.4	99.7 (100.0)		
Tolerance		99.7			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:	1	Grad. No.:	3
Material:	COARSE AGGREGATE-PCC		
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	3759.4	Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)		23.0			
19mm (¾)		381.2			
12.5mm (½)		1476.8			
9.5mm (3/8)		1243.5			
4.75mm (4)		501.0			
2.36mm (8)	(B)	100.7 (A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash		(A)			
Pan	(B)	30.8 (A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:	2603.3			
	Dry Mass Washed:	2590.4			
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan	1.1				

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_

Lab. No.:	2	Grad. No.:	4
Material:	COARSE AGGREGATE-PCC		
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	5348.7	Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)		169.0			
19mm (¾)		516.7			
12.5mm (½)		1817.0			
9.5mm (3/8)		1798.3			
4.75mm (4)		713.9			
2.36mm (8)	(B)	307.1 (A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash		(A)			
Pan	(B)	24.6 (A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:	2582.8			
	Dry Mass Washed:	2561.9			
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan	0.9				

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:	1		
Material:	COARSE AGGREGATE-PCC	Grad. No.:	3
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	3759.4	Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)				100.0	100
25mm (1)		23.0	0.6	99.4	95-100
19mm (¾)		381.2	10.1	89.3	
12.5mm (½)		1476.8	39.3 (39.4)	49.9	25-60
9.5mm (3/8)		1243.5	33.1	16.8	
4.75mm (4)		501.0	13.3	3.5	0-10
2.36mm (8)	(B)	100.7 (A)	2.7	0.8	0-5
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash		(A)	0.8		
Pan	(B)	30.8 (A)			
Total		3757.0	99.9 (100.0)		
Tolerance		99.9			

Wash Sample	Original Dry Mass:		2603.3		
	Dry Mass Washed:		2590.4		
	Washing Loss:		12.9		
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)				0.5	0-1.5
Wash	12.9		0.5		
Pan	1.1				

Date Reported:	Cert. No.:
Tested By:	

Comments:

Lab. No.:	2		
Material:	COARSE AGGREGATE-PCC	Grad. No.:	4
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:	5348.7	Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)				100.0	100
25mm (1)		169.0	3.2	96.8	
19mm (¾)		516.7	9.7	87.1	
12.5mm (½)		1817.0	34.0	53.1	
9.5mm (3/8)		1798.3	33.6	19.5	
4.75mm (4)		713.9	13.3	6.2	0-10
2.36mm (8)	(B)	307.1 (A)	5.7	0.5	0-5
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash		(A)	0.5		
Pan	(B)	24.6 (A)			
Total		5346.6	100.0		
Tolerance		99.96			


Wash Sample	Original Dry Mass:		2582.8		
	Dry Mass Washed:		2561.9		
	Washing Loss:		20.9		
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)				0.8	0-1.5
Wash	20.9		0.8		
Pan	0.9				

Date Reported:	Cert. No.:
Tested By:	

Comments:

278







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:		
Material:	1" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using Box and 203mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	3581.0	Total Minus 4.75 mm (W1):	2262.9
Dry Mass Washed:	3393.7	Reduced Minus 4.75 mm (W2):	563.1
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)		76.5			
19mm (¾)		178.4			
12.5mm (½)		202.0			
9.5mm (3/8)		296.1			
4.75mm (4)		377.8			
2.36mm (8)	103.1 (B)	(A)			
1.18mm (16)	167.6 (B)	(A)			
600µm (30)	186.3 (B)	(A)			
300µm (50)	62.1 (B)	(A)			
150µm (100)	20.3 (B)	(A)			
75µm (200)	14.8 (B)	(A)			
Wash					
Pan	6.9 (B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_

Lab. No.:		
Material:	3/4" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using Box and 203mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	2296.0	Total Minus 4.75 mm (W1):	1023.9
Dry Mass Washed:	2201.9	Reduced Minus 4.75 mm (W2):	512.0
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			


Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)		15.0			
12.5mm (½)		196.0			
9.5mm (3/8)		477.3			
4.75mm (4)		489.7			
2.36mm (8)	163.2 (B)	(A)			
1.18mm (16)	101.0 (B)	(A)			
600µm (30)	97.6 (B)	(A)			
300µm (50)	80.0 (B)	(A)			
150µm (100)	41.3 (B)	(A)			
75µm (200)	26.0 (B)	(A)			
Wash					
Pan	2.4 (B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:		
Material:	1" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using Box and 203mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	3581.0	Total Minus 4.75 mm (W1):	2262.9
Dry Mass Washed:	3393.7	Reduced Minus 4.75 mm (W2):	563.1
Washing Loss:	187.3	Conversion Factor: W1 / W2	4.0186
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)				100.0	
25mm (1)		76.5	2.1	97.9	
19mm (¾)		178.4	5.0	92.9	
12.5mm (½)		202.0	5.6	87.3	
9.5mm (3/8)		296.1	8.3	79.0	
4.75mm (4)		377.8	10.6	68.4	
2.36mm (8)	103.1 (B)	414.3 (A)	11.6	56.8	
1.18mm (16)	167.6 (B)	673.5 (A)	18.8	38.0	
600µm (30)	186.3 (B)	748.7 (A)	20.9 (21.0)	17.0	
300µm (50)	62.1 (B)	249.6 (A)	7.0	10.0	
150µm (100)	20.3 (B)	81.6 (A)	2.3	7.7	
75µm (200)	14.8 (B)	59.5 (A)	1.7	6.0	
Wash		187.3	6.0		
Pan	6.9 (B)	27.7 (A)			
Total	561.1	3573.0	99.9 (100.0)		
Tolerance	99.6	99.8			

Wash Sample	Original Dry Mass:				Specs.
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_

Lab. No.:		
Material:	3/4" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using Box and 203mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	2296.0	Total Minus 4.75 mm (W1):	1023.9
Dry Mass Washed:	2201.9	Reduced Minus 4.75 mm (W2):	512.0
Washing Loss:	94.1	Conversion Factor: W1 / W2	1.9998
Calculated Weight (A)=Conversion Factor x (B)			


Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)				100.0	
19mm (¾)		15.0	0.7	99.3	
12.5mm (½)		196.0	8.5	90.8	
9.5mm (3/8)		477.3	20.8	70.0	
4.75mm (4)		489.7	21.3	48.7	
2.36mm (8)	163.2 (B)	326.4 (A)	14.2	34.5	
1.18mm (16)	101.0 (B)	202.0 (A)	8.8	25.7	
600µm (30)	97.6 (B)	195.2 (A)	8.5	17.2	
300µm (50)	80.0 (B)	160.0 (A)	7.0	10.2	
150µm (100)	41.3 (B)	82.6 (A)	3.6	6.6	
75µm (200)	26.0 (B)	52.0 (A)	2.3	4.3	
Wash		94.1	4.3		
Pan	2.4 (B)	4.8 (A)			
Total	511.5	2295.1	100.0		
Tolerance	99.9	100.0			

Wash Sample	Original Dry Mass:				Specs.
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:		
Material:	3/4" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using 305mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	2247.5	Total Minus 4.75 mm (W1):		
Dry Mass Washed:	2091.9	Reduced Minus 4.75 mm (W2):		
Washing Loss:		Conversion Factor: W1 / W2		
Calculated Weight (A)=Conversion Factor x (B)				

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)		27.0			
12.5mm (½)		243.3			
9.5mm (3/8)		301.1			
4.75mm (4)		511.8			
2.36mm (8)	(B)	432.0 (A)			
1.18mm (16)	(B)	211.6 (A)			
600µm (30)	(B)	116.9 (A)			
300µm (50)	(B)	100.4 (A)			
150µm (100)	(B)	83.0 (A)			
75µm (200)	(B)	54.0 (A)			
Wash					
Pan	(B)	8.3 (A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_

Lab. No.:		
Material:	1/2" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using 305mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	1631.0	Total Minus 4.75 mm (W1):		
Dry Mass Washed:	1526.5	Reduced Minus 4.75 mm (W2):		
Washing Loss:		Conversion Factor: W1 / W2		
Calculated Weight (A)=Conversion Factor x (B)				

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)		13.1			
9.5mm (3/8)		295.4			
4.75mm (4)		383.7			
2.36mm (8)	(B)	396.0 (A)			
1.18mm (16)	(B)	167.7 (A)			
600µm (30)	(B)	86.6 (A)			
300µm (50)	(B)	77.0 (A)			
150µm (100)	(B)	62.3 (A)			
75µm (200)	(B)	39.1 (A)			
Wash					
Pan	(B)	6.6 (A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments: \_\_\_\_\_







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:		
Material:	3/4" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using 305mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	2247.5	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	2091.9	Reduced Minus 4.75 mm (W2):	
Washing Loss:	155.6	Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)				100.0	
19mm (¾)		27.0	1.2	98.8	
12.5mm (½)		243.3	10.8	88.0	
9.5mm (3/8)		301.1	13.4	74.6	
4.75mm (4)		511.8	22.8 (22.9)	51.7	
2.36mm (8)	(B)	432.0 (A)	19.2	32.5	
1.18mm (16)	(B)	211.6 (A)	9.4	23.1	
600µm (30)	(B)	116.9 (A)	5.2	17.9	
300µm (50)	(B)	100.4 (A)	4.5	13.4	
150µm (100)	(B)	83.0 (A)	3.7	9.7	
75µm (200)	(B)	54.0 (A)	2.4	7.3	
Wash		155.6	7.3		
Pan	(B)	8.3 (A)			
Total		2245.0	99.9 (100.0)		
Tolerance		99.9			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:

Lab. No.:		
Material:	1/2" COMBINED AGGREGATE	Grad. No.:
Co. & Proj. #:	(Using 305mm sieves)	
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:	1631.0	Total Minus 4.75 mm (W1):	
Dry Mass Washed:	1526.5	Reduced Minus 4.75 mm (W2):	
Washing Loss:	104.5	Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			


Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)				100.0	
12.5mm (½)		13.1	0.8	99.2	
9.5mm (3/8)		295.4	18.1	81.1	
4.75mm (4)		383.7	23.5	57.6	
2.36mm (8)	(B)	396.0 (A)	24.3	33.3	
1.18mm (16)	(B)	167.7 (A)	10.3	23.0	
600µm (30)	(B)	86.6 (A)	5.3	17.7	
300µm (50)	(B)	77.0 (A)	4.7	13.0	
150µm (100)	(B)	62.3 (A)	3.8	9.2	
75µm (200)	(B)	39.1 (A)	2.4	6.8	
Wash		104.5	6.8		
Pan	(B)	6.6 (A)			
Total		1632.0	100.0		
Tolerance		100.1			

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:			
Material:	Grad. No.:		
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	(A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:

Lab. No.:			
Material:	Grad. No.:		
Co. & Proj. #:			
Producer:			
Contractor:			
Sampled By:	Date:		
Sample Loc.:			

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			


Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	(A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:		
Material:	Grad. No.:	
Co. & Proj. #:		
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	(A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:			
	Dry Mass Washed:			
	Washing Loss:			

Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Lab. No.:		
Material:	Grad. No.:	
Co. & Proj. #:		
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	(A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:			
	Dry Mass Washed:			
	Washing Loss:			


Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:

Comments:







# IOWA DEPARTMENT OF TRANSPORTATION SIEVE ANALYSIS WORKSHEET

Lab. No.:		
Material:	Grad. No.:	
Co. & Proj. #:		
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	(A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					

Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Lab. No.:		
Material:	Grad. No.:	
Co. & Proj. #:		
Producer:		
Contractor:		
Sampled By:	Date:	
Sample Loc.:		

Original Dry Mass:		Total Minus 4.75 mm (W1):	
Dry Mass Washed:		Reduced Minus 4.75 mm (W2):	
Washing Loss:		Conversion Factor: W1 / W2	
Calculated Weight (A)=Conversion Factor x (B)			

Sieve Size	Reduced Minus 4.75mm	Total or Calc. Weight Retd	% Retd.	% Passing	Specs.
37.5mm (1½)					
25mm (1)					
19mm (¾)					
12.5mm (½)					
9.5mm (3/8)					
4.75mm (4)					
2.36mm (8)	(B)	(A)			
1.18mm (16)	(B)	(A)			
600µm (30)	(B)	(A)			
300µm (50)	(B)	(A)			
150µm (100)	(B)	(A)			
75µm (200)	(B)	(A)			
Wash					
Pan	(B)	(A)			
Total					
Tolerance					


Wash Sample	Original Dry Mass:				
	Dry Mass Washed:				
	Washing Loss:				
Sieve Size	Mass	Retd.	% Retd.	% Passing	Specs.
75µm (200)					
Wash					
Pan					

Date Reported:	Cert. No.:
Tested By:	

Comments:

Comments:







# **Iowa Department of Transportation Technical Training and Certification Program**

## **COURSE EVALUATION SHEET**

In an effort to improve the Iowa DOT Technical Training and Certification Program, we ask that you fill out this evaluation form after you have taken the exam. Thank you for your cooperation.

Course: \_\_\_\_\_

Location: \_\_\_\_\_

Instructor: \_\_\_\_\_

1. What type of agency are you employed by?

\_\_\_\_\_

2. Please rate the following portion of the course on a scale of 1-5. 1=Poor, 5= Excellent

Facility : \_\_\_\_\_

Material : \_\_\_\_\_

Instructors : \_\_\_\_\_

Course Activities : \_\_\_\_\_  
( lectures, videos, demonstrations, etc. )

3. Are there any changes you would like to see made in the course?

\_\_\_\_\_

\_\_\_\_\_

**REMARKS:**







## Moisture Tests (I.M. 308)

Calculate the percent of free moisture of each of the examples below by using the following formula:

$$\text{Percent Moisture} = \frac{(W - W_1)(G_s)(100)}{(G_s - 1)(s)}$$

**W=** Mass in grams of the pycnometer containing a saturated-surface-dry sample of the same mass as "s" and sufficient water to fill the remaining volume of the pycnometer as determined in I.M. 307.

**W<sub>1</sub>=** Mass in grams of the pycnometer containing the wet sample and sufficient amount of water to fill the remaining volume of the pycnometer.

**G<sub>s</sub> =** Specific Gravity of material in a saturated-surface-dry condition (this is obtained from Method I.M. 307).

**s =** Mass in grams of wet sample

**What is the percent of free moisture in the aggregate when:**

1. W = 3916.5    W<sub>1</sub> = 3907.0    G<sub>s</sub> = 2.61    s = 2000.0

$$\frac{(3916.5 - 3907.0)(2.61)(100)}{(2.61 - 1)(2000)}$$

2. W = 2096.5    W<sub>1</sub> = 2078.5    G<sub>s</sub> = 2.66    s = 1000.0

$$\frac{2479.5}{3220} = 0.777$$

$$\frac{4788}{1660} = 2.88 = 2.9$$


3. W = 3903.5    W<sub>1</sub> = 3911.0    G<sub>s</sub> = 2.70    s = 2000.0

$$\frac{2025}{3400} = 0.596$$

4. W = 2204.5    W<sub>1</sub> = 2184.0    G<sub>s</sub> = 2.60    s = 1000.0

$$\frac{5333}{1600} = 3.33$$













3 1723 02116 7796